

**TEXT FLY WITHIN  
THE BOOK ONLY  
PAGES MISSING  
WITHIN THE  
BOOK ONLY  
(35 to 40) (43&44)**

UNIVERSAL  
LIBRARY

**OU\_166801**

UNIVERSAL  
LIBRARY



OSMANIA UNIVERSITY LIBRARY

Call No. 792

Accession No. 35225

G97I  
Author Gupta, Chandra Bhan

Title Indian Theatre. 1954.

This book should be returned on or before the date last marked below.



**THE  
INDIAN THEATRE**



# **THE INDIAN THEATRE**

**ITS ORIGIN  
AND DEVELOPMENT UP TO THE  
PRESENT DAY**

*BY*

**CHANDRA BHAN GUPTA, M. A., D. Litt.**

HINDU COLLEGE,  
UNIVERSITY OF DELHI ( INDIA )

*Thesis approved by Banaras Hindu University  
for the award of the degree of Doctor of Letters in  
1949 under the title 'Presentation of Sanskrit Plays.'*

**MOTILAL BANARASIDASS**

*Publishers and Booksellers*

**POST BOX 75, BANARAS.**

**1954**

**MUNSHI RAM MANOHAR LAL**

*Published by*  
**SUNDARLAL JAIN**  
**M/s Motilal Banarasidass**  
**POST BOX 75, BANARAS (INDIA)**

*First Edition 1000 Copies*  
*Price Rs 10/- .*

*Printed by*  
**SHANTILAL JAIN**  
**Jinendra Press**  
**NEPALI-KHAPARA, BANARAS.**

This volume  
is  
Gratefully inscribed  
to  
the memory  
of  
the late Professor  
S. C. Mukerjee  
&  
Dedicated  
to  
Professor  
P. L. Vaidya



## **FOREWORD.**

I have had an opportunity of watching the progress of Dr. Chandra Bhan Gupta's book. I had some connection with it, while I was Vice-Chancellor at Banaras. It is a matter of genuine pleasure that he has succeeded in producing a work of great merit, which provides valuable information and has much critical material which will provoke thought. The portion dealing with the contemporary theatre is naturally incomplete, but that does not detract from the merit of the whole book. I congratulate the author on giving us such an informative volume and trust he will continue his scholarly career with even greater success.

**Amaranatha Jha**

January 6, 1954.

## Extracts from Examiners' Report on the Thesis

### "Presentation of Sanskrit Plays"

In this thesis Shri Chandra Bhan Gupta has dealt comprehensively with all aspects of the '*Presentation of Sanskrit Plays*' in ancient India. He has drawn his material from the *Nāṭya-śāstra* of Bharata and other works on dramaturgy as well as from descriptions and incidents in Sanskrit plays.

He has shed new light on some aspects of the subject. I recommend it for the award of the degree of D. Litt.

**V. V. Mirashi**

Mr. Chandra Bhan Gupta's thesis '*Presentation of Sanskrit Plays*' is a product of great industry, skill and judicious selection of topics. He has utilized the original sources and succeeded in reconstructing a picture of the ancient theatre of India which he takes care to support with documentary evidence.

As regards his main conclusions I feel inclined to agree with him that the origination of Sanskrit drama and theatrical representation was indigenous. He has succeeded in showing the improbability of the theories of foreign influence. I also feel disposed to accept his contention that Indian drama was born and developed in a religious atmosphere just like the Greek drama. But the religious heaven was at work throughout its career, where as it has faded out in Europe. His suggestions for remodelling the National Theatre of India are sage, sober and unbiased.

**Satkari Mukerjee**

I have carefully gone through Mr. Chandra Bhan Gupta's thesis '*Presentation of Sanskrit Plays*.' The thesis is divided into nine chapters dealing, among others, with topics such as objects and objectives of the presentation of plays, types of theatres, scenic arrangement, stage paraphernalia, types of gesticulation, ornaments for the use on stage, paints, dresses, music and dance, stage conventions, troupe, audience, and *rasas* for the dramatic composition. There is a special chapter on the utility of the study of ancient Indian plays and how this study is useful in shaping the *Loka-Nāṭya* or popular theatre.

Mr. Gupta has also discussed the much debated question whether Indian theatre is of indigenous or foreign origin, and has come to the conclusion that it originated in India.

The whole subject is studied in a scientific spirit and contributes to the advancement of knowledge.

**P. L. Vaidya**



# PREFACE

Sanskrit drama in general has received a great deal of attention at the hands of European scholars since the *Abhijñānaśākuntala* was translated into English by William Jones in 1789. The origin of the Sanskrit drama has been the subject of elaborate investigation by professors Von-Schroeder, Pischel, Hertel, W. Ridgeway, Levi, Luders, Konow, Jacobi and Keith, and the significance and value of the Indian theory of dramatic art have been brought out by them. I have also come across certain articles, pamphlets and books in connection with some aspects of the Indian theatre, which I have mentioned in the 'Bibliography.' Mulk Raj Anand's book on 'The Indian Theatre' deals only with the different theatres in modern times in India in a stylish and sketchy way. It has nothing to do with the ancient Indian theatre, and so it cannot establish any connected study of the development of the theatre in India. R. K. Yajnik's book on 'The Indian Theatre' deals mainly with the influence of British drama on the Indian stage of today with special reference to western India. A pamphlet entitled 'Ancient Indian Theatre' by D. R. Mankad and the English translation of the *Nāṭyaśāstra* Chapters I-XXVII by Manomohan Ghosh came out in August 1950 and 1951, respectively. The pamphlet by Mankad has only interpreted the *Nāṭyaśāstra's* second chapter. There are certain aspects of Indian theatre which have not yet received much attention, for example, the actual scenic arrangement, stage paraphernalia etc. The present study deals with the Indian theory of dramatic art as employed in the actual performance or presentation of a play. The title of this thesis was, therefore, fixed as "Presentation of Sanskrit Plays." It is now published under the title "The Indian Theatre."

A new chapter has been added on 'Dramatic Practice Today.' The thesis will now give the reader, it is hoped,

a connected account of the presentation of dramas in the country from the earliest times to the present day.

I began this thesis in July, 1941, when I registered myself as a regular research student for D. Litt. for a period of three years under the supervision of Dr. S. C. Mukerjee, Mayurbhunj Professor and Head of the Department of Sanskrit at Banaras Hindu University, Banaras. I got every kind of guidance and help from Dr. Radhakrishnan, the then Vice-Chancellor of B. H. U.

In December 1941, I went on a tour of Central India and Bombay and visited the Ellora, Ajanta and Elephanta caves and Sanchi Stūpa etc. In May and June, 1942, I joined the Uday Shankar India Culture Centre, Almora, as a summer student to study histrionics and dancing. I also visited Udaipur to study the dances of the Bhils.

In 1943, I met Dr. S. K. De, Dr. Belvelkar and Mahā-mahopādhyāya Dr. P. V. Kane at the Oriental Conference at Banaras. They approved the plan of my research and very kindly discussed certain points of my thesis and suggested as to how I should proceed. In 1947 Dr. Mukerjee passed away. After some time I met Dr. Amaranatha Jha, Vice-Chancellor, B. H. U., who sympathetically provided every kind of facility for my work at B. H. U. and directed me to approach the then Head of the Sanskrit Department, B. H. U. From then I was under the supervision of Dr. P. L. Vaidya, Mayurbhunj Professor and the Head of the Department of Sanskrit, B. H. U., under whose guidance my thesis was recast and presented to the Banaras Hindu University for the degree of Doctor of Letters in 1949.

This thesis mainly depends on the *Nāṭyaśāstra*, the *Abhinavabhāratī* and other works on dramaturgy which are mentioned in detail separately. It is divided into two parts. The first part deals with the 'Ancient Theatre' and has ten chapters: I. The Origin of the Indian Drama; II. Sanskrit Plays; III. Construction of the Theatre; IV. Scenic Representation; V. Paraphernalia; VI. Accessory Arts; VII. The Troupe; VIII. Conventions; IX. Nature and Types of Drama

X. Presentation of Plays. The second part consists of only one chapter [XI] and deals with the "Dramatic Practice Today" and describes Indian theatres in the various parts of the country. Then comes Epilogue [chapter XII]. It gives in brief a resumé of the previous chapters. Then follows 'Bibliography' of standard authentic works and dramas in Sanskrit and articles and works in English on the Indian stage. Lastly the 'Index' will contain mainly terms connected with Sanskrit drama and theatre appearing in the work.

The general plan of the work is arranged in the following manner. Names of all the books as well as Sanskrit words have been italicized. Quotations of translated passages have been given in inverted commas. In the case of dramas, names of books containing translations have not been referred to in the footnotes as those translations are very popular.

Diagrams of different types of theatres mentioned in the *Nāṭyaśāstra* and seating arrangement in a palace theatre as mentioned in the *Saṅgītaratnākara* are drawn by Shri Vijaya Srivastava according to the plan given by the author.

This work, it is hoped, will prove of great service not only to students of the history of Sanskrit literature but also for the regeneration of a people's theatre, according to national traditions. The threads of the topic of this work are woven in such a manner as to present a systematic account of the presentation of Sanskrit plays for the use of scholars and the public. It suggests the model on which a national theatre in India can be planned.

I am beholden to Late Pt. Madan Mohan Malaviya and Dr. Radhakrishnan, who helped me in the initial stages of my thesis by their encouragement and assistance. I also express my gratitude to Mahāmahopādhyāya Dr. P. V. Kane and Dr. Gopi Nath Kaviraj, Dr. S. K. De, Dr. S. K. Belvalkar, Dr. P. K. Acharya, Dr. V. Raghavan, Dr. R. K. Yajnik and Mr. D. R. Mankad for their valuable suggestions in the initial stages of my work. My grateful thanks are due to Dr. Bhagavan Das, Dr. V.S. Agarwala, Pt. Vishva Bandhu Shastri,

Mrs. Rukmini Devi Arundale, Pt. Giridhar Sharma Chaturvedi, Pt. Baldeo Upadhyaya and Pt. Sitaram Chaturvedi, who have given me their valuable opinions on my book.

My heart-felt thanks go to Dr. Amaranatha Jha for his contributing an appreciative 'Foreword' to it.

HINDU COLLEGE,  
*University of Delhi*  
1954

**Chandra Bhan Gupta**

# CONTENTS

## ANCIENT THEATRE

CHAPTER	PAGE
<b>I The Origin of the Indian Drama</b>	
A. The Indian Tradition. ...	3
B. Genesis of Indian Drama. ...	5
C. Theories. ...	8
<b>II Sanskrit Plays</b>	
A. Significance. ...	13
B. Object. ...	14
C. Occasions for Enactment. ...	21
D. Places for Performance. ...	24
<b>III Construction of the Theatre</b>	
A. Types and Measurements. ...	30
B. <i>Raṅgupiṭha</i> and Decoration. ...	34
C. <i>Raṅgaśirṣa</i> , Green Room and <i>Mattavāraṇīs</i> . ...	46
D. Pillars and Seating Arrangements. ...	50
E. Doors and Roof. ...	52
<b>IV Scenic Representation</b>	
A. The Curtain. ...	55
B. Origin of the Curtain. ...	61
C. Employment of Painting. ...	64
D. Time of Presentation. ...	69
<b>V Paraphernalia</b>	
A. Significance of <i>Āhāryābhinaya</i> [Costumes and Make-up] ...	72
B. <i>Pusta</i> [Model Work] ...	73
C. <i>Alaṅkāra</i> [Decoration] ...	77
D. <i>Aṅgaracanā</i> [Painting of the Limbs] ...	82
E. <i>Saṅjīva</i> [Living Creatures] ...	86
<b>VI Accessory Arts</b>	
A. Music and Orchestra. ...	88
B. Histrionics. ...	94
C. Dancing. ...	98
D. Dialogue. ...	101

CHAPTER	PAGE
<b>VII The Troupe.</b>	
A. Roles of Characters [ <i>Bhūmika</i> ]	... 104
B. <i>Nāṭyācāryas</i>	... 106
C. Actors and Actresses	... 108
D. Spectators and Judges	... 111
E. Social Position of Actors and Actresses.	... 115
<b>VIII Conventions.</b>	
A. <i>Pūrvaraṅga</i> .	... 119
B. Religious ceremonies.	... 124
C. Dialects.	... 127
D. Injunctions and Prohibitions.	... 129
<b>IX Nature and Types of the Drama.</b>	
A. <i>Nṛtta</i> , <i>Nṛtya</i> and <i>Nāṭya</i> .	... 136
B. Major Types of Drama [ <i>Rūpakas</i> ]	... 139
C. Minor Types [ <i>Uparūpakas</i> ]	... 144
<b>X Presentation of Plays.</b>	
A. Actual Performance.	... 148
B. Portrayal of Sentiment [ <i>Rasa</i> ]	... 151
C. Success.	... 153
<b>DRAMATIC PRACTICE TODAY.</b>	
<b>XI Modern Theatres.</b>	
Introduction	... 159
A. The Folk Tradition.	... 160
B. The Madras Theatre.	... 162
C. The Bengal Theatre.	... 164
D. The Marathi Theatre.	... 165
E. The Parsi and the Gujarati Theatre.	... 167
F. The Hindi Theatre.	... 170
G. Idea of a National Theatre.	... 174
<b>XII Epilogue.</b>	... 177
<b>Bibliography.</b>	... 185
<b>Index.</b>	... 195

## METHOD OF TRANSLITERATION

a अ	i इ	u उ		
ā आ	ī ई	ū ऊ		
r ऋ	ri ॠ	l लृ		
e ए	o ओ	ai ऐ		
au औ	m अं	h अः		
k क्	kh ख्	g ग्	gh घ्	n ङ्
c च्	ch छ्	j ज्	jh झ्	ñ ञ्
ṭ ट्	ṭh ठ्	ḍ ड्	ḍh ढ्	ṇ ण्
t त्	th थ्	d द्	dh ध्	n न्
p प्	ph फ्	b ब्	bh भ्	m म्
y य्	r र्	l ल्	v व्	
ś श्	ṣ ष्	s स्	h ह्	

This method of transliteration is followed throughout this work for Sanskrit words, books and authors. The word 'Sanskrit' has been treated like other English words.

## Abbreviations used in Footnotes

Abh. Bh.	...	<i>Abhinavabhāratī</i>
AD	...	<i>Abhinayadarpaṇa</i>
AR	...	<i>Anargharāghava</i>
AS	...	<i>Arthaśāstra</i>
BP	...	<i>Bhāvaprakāśana</i>
DR	...	<i>Daśarūpa</i>
GOS	...	<i>Gaekwad Oriental Series</i>
Kar. M.	...	<i>Karpūramañjarī</i>
KM	...	<i>Kāvyamāla</i>
KP	...	<i>Kāvyaprakāśa</i>
KSS	...	<i>Kaśī Sanskrit Series</i>
Māl	...	<i>Mālavikāgnimitra</i>
MM	...	<i>Mālatīmādhava</i>
Mṛch	...	<i>Mṛcchakaṭika</i>
MS	...	<i>Mānasāraṣilpaśāstra</i>
ND	...	<i>Nāṭyadarpaṇa</i>
NLR	...	<i>Nāṭakalakṣaṇaratnakōṣa</i>
NS	...	<i>Nāṭyaśāstra</i>
PR	...	<i>Pratāparudrīya</i>
Pra. Y.	...	<i>Pratijñāyugandharāyaṇa</i>
PD	...	<i>Priyadarśikā</i>
Rat	...	<i>Ratnāvalī</i>
RS	...	<i>Rasārṇavasudhākara</i>
Śāk	...	<i>Abhijñānaśākuntala</i>
ŚR	...	<i>Śilparatna</i>
SD	...	<i>Sahityadarpaṇa</i>
SR	...	<i>Sanḡitaratnākara</i>
URC	...	<i>Uttararāmacarita</i>
VD	...	<i>Viṣṇudharmottara</i>
Vik	...	<i>Vikramorvaśīya</i>



# ANCIENT THEATRE



# CHAPTER I

## THE ORIGIN OF THE INDIAN DRAMA

### A. The Indian Tradition

The earliest authority in India on the presentation of plays on the stage is the *Nāṭyaśāstra* of Bharata. The mythological character of the traditional account of the origin of the Indian drama given in the *Nāṭyaśāstra* forces on us the conclusion that all exact knowledge about it had been lost by the time the *Nāṭyaśāstra* was written.

Gods, according to the account preserved in the *Nāṭyaśāstra*, entreated Brahmā to produce something to play [ *kṛīḍanīyaka* ] which could be seen and also heard, a fifth *veda*, that would benefit all castes [ *sārvavārṇika* ]. Accordingly he took recitation [ *pāṭhya* ] from the *Rgveda*, song [ *gīta* ] from the *Sāmaveda*, the art of acting [ *abhinaya* ] from the *Yajurveda*, and sentiment [ *rasa* ] from the *Atharvaveda* and asked Bharata to make known to mankind the new *Nāṭyaveda* thus produced and bring into practice the precepts with the help of his sons and disciples, and the *gandharvas* and *apsarās*, as the actors and actresses, at the 'banner festival of Indra'. This enraged the *asuras* from whom mischief was apprehended. Indra, therefore, took the banner and attacked them with the staff. That is why his banner is called *jarjara* and it is given as a mark of Indra's protection for all stage productions. The *asuras* had to accept the assurance that the drama was a representation of facts of a general nature and would not be deliberately applied to anybody. The *Nāṭyaśāstra* refers to two other dramas enacted in very early times on two subjects the 'Churning of Nectar from the Sea' and the 'Burning of Three Cities'.<sup>1</sup>

---

1. NS—KM I. 11, 12, 14, 17, 20 b-25, IV. 1-10; KSS I. 11, 12, 14, 17, 54b-60, IV. 1-11; GOS I. 11, 12, 14, 17, 54-59a, IV. 1-11.

The traditional account as furnished by the *Abhinaya-darpaṇa* is as follows: 'In the beginning Brahmā gave the *Nāṭya-veda* to Bharata. Bharata, with groups of *gandharvas* and *apsarās*, performed *nāṭya*, *nṛtta* and *nṛtya* before Śiva. Śiva, remembering his own majestic dance had Bharata instructed in the art by his attendants [*gaṇas*]. And before this, out of his love for Bharata, he gave the latter instruction in *lāsya* through Pārvatī, and in *tāṇḍava* through Taṇḍu. Then sages spoke of it to mortals. Pārvatī, on the other hand, instructed Uṣā, daughter of Bāṇa, in *lāsya*. The latter taught the art to the milkmaids of Dvārakā, and they taught it to women of Saurāṣṭra who, in their turn, taught it to women of other countries. In this manner this art was traditionally handed down and came to stay in the world'.<sup>1</sup>

With regard to the origin of the *Nāṭyaveda*, the *Bhāva-prakāśana* records two stories. The first is that at the end of the *kalpa*, Maheśvara created Brahmā and Viṣṇu, and Brahmā created the world. Nandikeśvara came to Brahmā and taught the *Nāṭyaveda* and its application to him. He said "the *Nāṭyaveda* may be enacted by Bharata" and disappeared. Brahmā and other gods were pleased and the *Tripuradāha-rūpaka* was played.

According to the second account, disgusted with the worries of ruling his kingdom, Manu approached *Sūryadeva* for consolatory advice. *Sūryadeva* said that in days of yore Brahmā disgusted with his work for mankind went to the Lord of Lords for relief. He was advised to go to Śiva. Śiva asked his pupil Nandikeśvara to teach the *Nāṭyaveda* to Brahmā. Nandikeśvara taught Brahmā the *Nāṭyaveda* and its method of representation. He came back to his abode and meditated for a while. Then there appeared before him a *muni* with five disciples. They were taught the *Nāṭyaveda*. They put the *Nāṭyaveda* on the stage and thus pleased Brahmā who gave

---

1. AD 2-7a.

them a boon. *Sūryadeva* advised Manu to pray to Brahmā for relief from the troubles experienced by him in sustaining the earth. Then Manu went to Brahmā who knowing his difficulty ordered Bharata to go with Manu to Bhāratavarṣa. Accordingly Bharata came to Ayodhyā with Manu.<sup>1</sup>

### B. Genesis of Indian Drama.

The earliest representation of plays on the stage appears to be associated with the religious observances of the people. In Greece, for example, the drama derived its origin from the hymns which were sung at the festivals of Bacchus. In the *Ṛgveda* we come across certain hymns in the form of dialogues [*saṁvāda sūktas*]<sup>2</sup> some of which seem to contain dramatic flavour consisting, as they do, of conversation, speech and repartee. The *Vājasaneyī Samhitā* of the *Śukla Yajurveda* makes mention of the word *śailūṣa* which means an actor. It says that a *sūta* was to be employed for *nṛtta* and a *śailūṣa* for song.<sup>3</sup> The *Sāmaveda* with the hymns set to tune clearly shows that the art of music was fully developed in the *Vedic Age*.<sup>4</sup> *Vedic* sacrifices were essentially a *mimesis*. In the *Kauṣītaki Brāhmaṇa* sacrificial priests are described as dancing. In the same *Brāhmaṇa*, *saṅgīta* [ which comprehends music, dance and playing on instruments ] forms a part of *yajña-yāgādi*.<sup>5</sup> At the Mahāvratāstoma rite young maidens danced.<sup>6</sup>

The *Rāmāyaṇa* refers to *naṭa*, *nartaka*, *nāṭaka*, dances and theatrical acts in cities and palaces. Bharata, son of Daśaratha, who was upset by bad dreams at his maternal uncle's house, was cheered with songs, dances and joyous *nāṭakas*.

---

1. BP III. p. 55, l. 22 and p. 56.

2. *Ṛgveda* I, 165, 170, 179; III. 33; IV. 18, 42; V. 11; VII. 33; VIII. 100; X. 10, 28, 51-53, 86, 95, 108.

3. *Vājasaneyī Samhitā* XXX. 6.

4. *Nirukta* 7. 12. 4.

5. *Kauṣītaki Brāhmaṇa* XVII. 8, pp. 77-78; XXIX. 5, pp. 140-141.

6. *Kāṇhakaṁ* XXXIV. 5.

We hear of festivals and concourses [ *samājas* ] where actors [ *naṭas* ] and dancers [ *nartakas* ] delighted themselves.<sup>1</sup> The *Mahābhārata*, like the *Rāmāyaṇa*, refers to dramatic terms like *naṭa*, *nartaka*, *gāyakas* and *sūtradhāra*.<sup>2</sup>

The *Harivaṃśa* which is a supplement to and a continuation of the *Mahābhārata* makes explicit reference to the drama. We learn from it of players who produced a drama out of the *Rāmāyaṇa* legend. It makes direct mention of a dramatic treatment [ *nāṭakīṣṭam* ] of the *Rāmāyaṇa*. We are informed that “the renowned actor represents in a drama ‘the birth of the immeasurable Viṣṇu’ for the purpose of fulfilling his wish to slay the prince of the *rākṣasas*”. Lomapāda and Daśaratha, in the drama, caused the great *muni* Rṣyaśṛṅga to be brought by Sautā and courtesans. Rāma, Lakṣmaṇa, Bharata and Śatrughna, Rṣyaśṛṅga and Sautā were personated by characteristically dressed actors.<sup>3</sup>

In some of the *Purāṇas* also we find references to the representation of plays. In the *Śrīmadbhāgavata Purāṇa*, reference is made to actors.<sup>4</sup> In the *Mārkandeeya Purāṇa*, we find Rṭadhvaja, son of king Śakrajit, fond of dramatic performance [ *nāṭakābhinaya* ] and passing his days delightfully in the cultivation of poetry, music and drama.<sup>5</sup>

Elaborate Buddhistic evidence about the early existence of drama is available. The *Brahma-Jālasutta* of the *Digghanikāya* contains a list of terms denoting various amusements and shows.<sup>6</sup> In the *Avadānaśataka* there is a clear mention of a *rūpaka* being enacted on the stage.<sup>7</sup>

1. *Rāmāyaṇa* II. 69. 4; II. 67. 15.

2. *Mahābhārata* I. 51. 15, p. 102; III. 16. 14, p. 55.

3. *Harivaṃśa* II. 88—93.

4. *Śrīmadbhāgavata Purāṇa* I, XI, 20.

5. *Mārkandeeya Purāṇa* XX. 4b and 6a.

6. *Digghanikāya* I. 1. 13.

7. *Avadānaśataka* II. 24 [75], pp. 29-30.

The *Arthaśāstra* supplies us with a good deal of information on the maintenance and working of the *nāṭakamaṇḍalis*. In one place we find that if any *nāṭakamaṇḍalī* came from another country to present a play on the stage, it was required to pay five *paṇas* [ a particular coin equal in value to 80 cowries ] to the king. In another place it is stated that the king's duty was to provide teachers for women, who acted on the stage, to teach them such arts as singing, dancing, acting, writing, painting, playing on instruments, particularly *vīṇā*, *veṇu* and *mṛdaṅgā*, preparing garlands, ornamenting the body with different materials, and to spend on the above-mentioned items from the treasury of the *rājamaṇḍala* [ government ]. The sons of *ganikas* [ courtesans ] and the principal *naṭas* were appointed head *ācāryas* [ teachers ] for all other stage-players.

In the *Arthaśāstra* it is also mentioned that the king used to employ *naṭas*, dancers, singers, instrumentalists, story-tellers, actors and *aindrajālikas* [ jugglers ] as spies who would try to reach the enemy-king. Salaries for the different categories of stage-players were fixed. A *Kuśilava* [ *naṭa* ] was to be paid 350 *paṇas* yearly, while those who were conversant with playing on high class instruments were given 700 *paṇas* yearly.<sup>1</sup> This shows that the stage-craft was highly developed at the time of the *Arthaśāstra*.

Vātsyāyana mentions writers on dramatic art of remote ages whose works are lost save in stray quotations. He describes the recreations of citizens [ *nāgaraka* ] and refers to the doings of *Piṭhamarda*, *viṭa*, *vidūṣaka*, *kuśilavas* etc. *Naṭas* appointed by the king were to play *nāṭakas* in the temples of Sarasvatī on the days of *parva*. *Naṭas* who came from outside the state to stage plays were treated in the same manner as the *naṭas* of the place.<sup>2</sup>

By the time of the *Sūtras*, literature on the practice of the histrionic art must have grown in bulk so as to have

---

1. AS I. II. 27, pp. 305-306; II. V. 3, p. 204; II. VII. 17, p. 354.

2. Kāmasūtra IV. 27-30, pp. 44-57.

created the necessity of codifying laws governing them. Pāṇini mentions *naṭasūtras* to show that acting had sufficiently developed and formulation of principles of dancing and acting in the form of *sūtras* was necessary.<sup>1</sup>

In the *Mahābhāṣya* we find more effective evidence of the existence of plays when it makes mention of two regular plays, the *Kaṁsavadha* and the *Balibandha* being acted on the stage. We have phrases in the *Mahābhāṣya* such as 'they cause the death of Kaṁsa', 'they cause the binding of Bali.' The phrase '*rasiko naṭaḥ*' in the *Mahābhāṣya* indicates that the theory of *rasa* was well-known in the days of Patañjali.<sup>2</sup>

Coming to the classical period, we find distinct evidence of the representation of plays available with the discovery of the manuscripts on palm-leaf among the Central Asian finds. One of the plays, *Śāriputra-prakaraṇa* was found to be written by Aśvaghoṣa, but no mention of the names of the authors of the other two fragments could be discovered there.

MM Gaṇapati Śāstrī of Travancore discovered 13 dramas with similarity of expression and construction and ascribed them to Bhāsa. These were also found to be the earliest complete specimens of dramatic composition available. From these it is evident that a long series of dramas were produced and enacted before him.

### C. Theories.

The question of the origin of Sanskrit plays has been of much interest to scholars. In this respect various theories have been propounded. It has been held that the drama [ from 'Greek *draine*'—to imitate or represent and 'Sanskrit *avasthānukṛtirnāṭyam*'<sup>3</sup>—the imitation of the circumstances is *nāṭya* ] originated in Greece. E. Windisch<sup>4</sup> is the exponent of this theory. He relies for his evidence

1. Pāṇini IV. 3. 110; IV. 3. 111; IV. 3. 129.

2. *Mahābhāṣya* II, pp. 36 and 394.

3. DR 1. 7.

4. Keith: 'Sanskrit Drama', P. 57; Windisch 'Der griechische Einfluss im indischen Drama', ( 1882 ),



on the *Mṛcchakaṭika* which he held to be the oldest Indian drama. Attic comedies were available about the third century B. C. and according to Windisch the *Mṛcchakaṭika* was written about the same time. But we know now that the Sanskrit drama had taken a settled form long before the origin of the *Mṛcchakaṭika*.

The oldest Sanskrit dramas known to us are of an entirely different kind and have no similarity with the Greek drama. Development of a story, shortening of knots and generally the entire characterization of the Sanskrit drama is different from that found in Greece. The conflict in the Sanskrit drama as opposed to the Greek is not based on the character of the person appearing and no correct gradation and climax of the opposition is met with in the former. In its outer form also the Sanskrit drama is different from the Greek. Sanskrit and several *Prākṛta* dialects are employed in the Sanskrit dramas. Moreover, there is no internal connection whatever between the Greek and the Sanskrit dramas. The Greek tragedy belongs to the classical type and the Sanskrit drama is by universal assent admitted to be romantic.

It has been suggested that 'yavanikāpāṭanam' in a Sanskrit play has a significant derivative relation to the word 'yavana', which name the Indians gave to the Greeks. While dealing with the question of the origin of *yavanikā* in Chapter IV of this book it will be shown that it was not in the least borrowed from Greece.

Bloch<sup>1</sup> believes that he has found support for the Greek hypothesis in the arrangement of the theatre in the Sītā-bēṅgā cave. He sees in it the imitation of a Greek theatre. But the points of resemblance are extremely meagre as there is no arrangement here of prosinium or orchestra as in the Greek theatre.

To conclude, there is nothing in Indian plays to correspond to the high shoes and limitation in the number of

---

1. 'Archaeological Survey of India Report,' 1903-1904, PP. 123-132.

characters that might appear at the same time on the stage or the observance of the unities, especially those of time and place. In these respects Indian plays are more analogous to those of Elizabethan England. No importance can be attached to the parallelism between the *vidūṣaka* who is a Brāhmaṇa and the confidential slave of the Greek stage. Thus they belong to two opposite schools, totally alien to each other in composition, taste and sentiment. Dr. Horace H. Wilson<sup>1</sup> declares emphatically 'Whatever may be the merits or defects of the Hindu drama, it may be safely asserted that they do not spring from the same parent, but are unmixedly its own'. Thus the theory of Greek origin is entirely without any foundation and we can say without hesitation that the Sanskrit drama had an indigenous origin entirely free from any foreign influence.

The argument put forward by MM Haraprasāda Śāstri<sup>2</sup> in support of the Maypole theory is that the first Indian play is stated to have been produced at the '*Indradhvaja* festival' in which a pole plays a prominent part as the object of worship. This suggested to him the Maypole dance of Europe. He therefore held that the origin of the Indian drama was to be connected with the ceremonies associated with spring festivities coming after the end of the dreary and lifeless winter. Unhappily for this theory, the '*Indradhvaja* festival' comes at the end of the rains and indicates Indra's victory over clouds represented as demons.

Dr. Ridgeway's<sup>3</sup> theory of the 'cult of the dead' and Dr. Keith's<sup>4</sup> 'vegetation spirit' theory are equally unfounded. Dr. Ridgeway says that there is a feeling of respect for the

- 
1. Wilson: 'Select Specimens of the Theatre of the Hindus', I. XI.
  2. Journal and proceedings of the Asiatic Society of Bengal, V, PP. 351-361.
  3. Ridgeway: 'The Dramas and Dramatic Dances of Non-European Races', P. 211; Journal of Royal Asiatic Society of Great Britain and Ireland, 1916, pp. 821-829.
  4. Keith: 'Sanskrit Drama', pp. 37-38.

departed heroes. But Sanskrit dramas are mostly erotic in sentiment and descriptions of the heroic sentiment end with the hero's satisfaction in getting the heroine. As to the 'vegetation spirit' theory, Keith himself could not maintain the view.

Dr. Pischel<sup>1</sup> of Germany advances the 'puppet show' theory saying that puppet dance first originated in India. Puppets are mentioned in Sanskrit literature frequently. The stage manager in Indian plays is called '*sūtradhāra*' [string holder]. This has suggested to Dr. Pischel the theory that the Indian play was in origin a puppet show. The theory falls flat when we realize that naturally men must have acquired the art of acting, dancing and speaking in a dramaturgic form before making a show on the stage through puppets. Moreover this theory is wrongly based on the word *sūtradhāra*, for the word means a person who in brief and in the form of aphorism describes the plot, hero and sentiment employed in the drama.

Prof. Luders<sup>4</sup> is the exponent of the 'shadow play' theory. Ancient India had also shadow plays wherein moving shadows thrown upon a curtain from behind formed the action of the plot. The shadow Sītā introduced in the *Uttararāmacarita* acquired a new theatrical value from this point of view. But we find no reference of *chāyānāṭaka* in dramaturgic works. Hence this theory cannot be regarded as explaining the origin of the Indian drama.

Legendary traditions thus indicate that the genesis of the drama lie in the *Vedas* where all its ingredients, song, dance, dialogue and some sort of acting as well are found. They also bring out the fact that the Sanskrit drama was

1. Keith: 'Sanskrit Drama', P. 52; Pischel: 'Die Heimat des puppenspiels', [ 1902 ].

2. Mahābhārata, V. 39. 1, p. 179; Bālarāmāyaṇa, V. p. 251.

3. BP X. p. 288, LL. 7-8.

4. Keith: 'Sanskrit Drama', p. 53; Luders: 'Sitzungsberichte der Königl. Akademie der Wissenschaften zu Berlin,' 1916, pp. 698 ff.

5. URG II

introduced to provide a source of pleasure to people of all castes. The *Vedic* ritual contained in itself the germs of the drama as is the case with practically every form of primitive worship. The ritual did not consist merely of the singing of songs or recitations in honour of gods; it involved a complete round of ceremonies in some of which was undoubtedly present an element of dramatic art. Performers of rites assumed for the time being personalities other than their own. In a sense, therefore, it may be said that the Indian drama has its origin in the *Vedic* period. However, there is not the slightest evidence that the essential synthesis and development of plot which constitute a true drama were made in the *Vedic* Age. On the contrary there is every reason to believe that it was through the use of the epic recitation that the latent possibilities of the drama were made patent. From a study of the *Arthaśāstra* and the *kamasūtra* it becomes evident that in their times the science of stage-craft was highly developed and that the *naṭas* were employed by kings for amusement and for state work. In the *Mahābhāṣya* there is effective evidence on the existence of a drama and it may be concluded safely that the Indian drama attained its full form by the time of Patañjali. Bharata and the commentary of Abhinavagupta remain the principal authorities on the ancient stage. Distinct evidence for the presentation of plays is available in the dramas of Aśvaghoṣa and Bhāsa.

It has been seen clearly that the different theories such as 'Greek' theory, 'May-pole' theory, theory of the 'cult of the dead', 'vegetation spirit' theory and theories of 'puppet and shadow play' are not tenable and cannot explain the origin of the Sanskrit drama as a whole but deal with its individual aspects only.

Thus it can be asserted that the Indian drama is a product of centuries; it was an organism that was continually in a process of evolution, assimilating into itself many new and foreign factors and yet preserving its own peculiar individuality.

## ~~CHAPTER II~~

# SANSKRIT PLAYS

### A. Significance

According to Bharata, when the peculiarities of life in a society are connected with certain gestures or when the actions of gods, ṛṣis and kings are represented on the stage it is a dramatic play.<sup>1</sup> This fact is corroborated by the *Daśarūpa*, the *Rasārṇavasudhākara* and the *Sāhityadarpaṇa*. According to the *Daśarūpa*, the drama is the imitation of situations. It is a show because it is seen. It is a representation due to the assumption of parts by actors.<sup>2</sup> According to the *Sāhityadarpaṇa*, poetry is of two sorts—poetry to be seen and heard, and poetry to be heard only. Of these, ‘visible poetry’ is that which can be represented, and this is called *rūpaka*, from the assumption of form [ *rūpa* ] by the actors.<sup>3</sup> In the *Rasārṇavasudhākara* the term *rūpaka* is applied to a play on the analogy of *rūpaka* or metaphor, because in a play we assume a non-distinction between characters and the actors representing them.<sup>4</sup> The *Nāṭakalakṣaṇaratnakoṣa* defines a play as a performance which can be dramatised by gestures.<sup>5</sup> In a commentary on the *Anargharāghava*, the drama is defined as the representation by gestures of the condition of people as affected by their pleasurable and unpleasurable feelings.<sup>6</sup>

In *dṛśya kāvyas* the audience enjoys something more than the words uttered by actors and actresses on a stage. This something consists of the emotion and its intensity

---

1. NS—KM XVIII. 10-13 ; KSS XX, 10-13 ; GOS XVIII. 10-13.

2. DR I. 7.

3. SD VI. 1-2.

4. RS III. LL. 1-5, p. 209.

5. NLR LL. 8-9, p.1.

6. AR I, commentary p. 9. Here śloka is attributed to Bharata

expressed in their intonations, the presentation of their characteristic features under the stress of different emotions, the "temperament" of actors putting an original significance into the lifeless words of the drama, the dress and the decoration of the stage producing an illusion about actual life in different periods and countries.

### B. Object

*Abhinaya* or acting is the representation of high and low characters on the stage under suitable guises. The successful drama should contain suggestiveness in order to conform to the highly cultivated *dhvani* [ suggestion ] theory of the Sanskrit critics. The finer the suggestion, the higher the enjoyment.<sup>1</sup>

A representation is to reflect the life of the world as in a mirror. Bharata lays down that all arts and sciences are to be met with there.<sup>2</sup> The purpose of a play like that of all poetry is to please and 'to instruct in a pleasing manner in the style of a loving wife,' as Mammata puts it<sup>3</sup>. The aim of combined pleasure and instruction is to be achieved by inspiring various sentiments [ *rasas* ] in the audience while the actors imitate the different situations of life in the midst of diverse actions. Bharata says that a plot which has 64 divisions and subdivisions should get nourishment from the *rasas*, Bharata instructs the dramatist to bring the incidents of the plot together, each in its own place, solely with reference to the *rasa* appropriate to each.<sup>4</sup> He further says that the essentials of a play, other than *rasa* and *bhāva*, are to subserve them. Of these two, *bhāvas* are there only to nourish and develop *rasa*. The elements that help us in realizing the main import of a play brought by means of acting are

---

1. KP I. 3, p. 19; Dhvanyāloka śloka I, p. 9.

2. NS—KM I. 77b-82; KSS I. 108-114a; GOS I. 112-118a,

3. KP I. 2, P. 6.

4. NS—KM XIX. 52b-53a, 98b-99a; KSS XXI. 58, 106.

called *bhāvas*. The *bhāvas* secure for us [*bhāvayanti*] the sentiments [*rasān*] which are the very soul of a play.<sup>1</sup> Each of the essentials of a play will be taken separately and it will be shown that they are all used in the Sanskrit play only to subserve the *rasas*.

While giving the etymology of *abhinaya*, Bharata says that *abhinaya* is certainly the most prominent of all, as that is indispensable in helping us to visualise the main import of play. *Abhinaya* has four aspects: the *sātvika* [temperament], the *vācika* [words], the *āṅgika* [gestures] and the *āhārya* [dresses and make-up]. On examination it is found that each of these aspects subserves the highest dramatic end of the development and manifestation of *rasa*.<sup>2</sup>

Bharata emphasizes dramatic realism and idealism under the heading *dharmī*. *Lokadharmī* stands for realism in drama and *nāṭyadharmī* for idealism. As the drama is a representation of the world, Bharata justly emphasizes propriety in the presentation of life on the stage. Each act performed, word uttered and garment worn must all be in agreement with what is actually found in life. Thus the representation of life on the stage by the dramatist is realistic. It is *lokadharmī*.<sup>3</sup>

It is the duty of the dramatist to see that his truths are imaginative truths, not actual truths, that his representations are ideal and not photographic. The exhaustive treatment of selection and reticence, dialogue, music, dancing and the minute turns of gesture and expression and other devices on the stage make-up adopted by the artist to idealise facts and help the onlooker to imagine things of his experience and things outside it—all these come within the scope of the *nāṭyadharmī* [conventional]. Moreover, if anything used by people, appears in a play as endowed with a corporal form and speech, we have what is called *nāṭyadharmī*.<sup>4</sup>

1. NS—KM VI. 10, 35, VII. P. 69 Prose; KSS VI. 10, 34, VII. P. 69 Prose; GOS VI. 10, 38, VII. P. 343 Prose.

2. NS—KM and KSS VIII. 6-9; GOS VIII. 7-10.

3. NS—KM XIII. 50-52; KSS XIV. 69-71; GOS XIII. 70-72.

4. NS—KM XIII. 53-62; KSS XIV. 72-81; GOS XIII. 73-85.

Thus the drama is the result of the direct intellectual observation of life by the playwright and his artistic imagination. The end of all these means is manifestly the realization of emotional pleasure by the spectators.

Bharata insists on the dramatist making his characters employ the speech, dress, manners and conduct that are theirs. Local usages regarding costumes, languages, manners and professions differ in the different countries of the world. They are the *pravṛtti* or local colour in drama.<sup>1</sup>

The mental disposition of particular personages in particular situations is their *vṛtti*. There are four *vṛttis*: *bhāratī*, that which is brought out in words; *sātvatī*, that which is disclosed in conduct, *kaiśikī*, that which consists of words and acts of mildness and delicacy and *ārabhaṭī*, that which consists of vigorous, strong or even violent words and actions. Bharata details the *rasas* enjoyed by the spectator in each of these forms of *vṛtti* and says that *vṛttis* are the constituent elements of all dramas and that the ten kinds of dramatic composition are considered to have proceeded from these.<sup>2</sup>

Bharata deals elaborately with what ought to be the effect of the stage representation on the spectator. The penetrating onlooker must be made to forget himself and his own identity in his absorption in what happens on the stage. Involuntary expressions of appreciation must come from his lips and he must jump to heights of joy or shed tears in uncontrollable sorrow.<sup>3</sup>

According to Bharata, music, vocal and instrumental is a powerful aid in the realization of *rasa* by the spectator. He tells us how music aids the spectator's realization of *rasa* and serves to concentrate his attention on the representation of a play on the stage.<sup>4</sup>

---

1. NS—KM [XIII. 25b, c and Prose P. 147; KSS XIV. 36b, c and Prose P. 165; GOS XIII. 37 and Prose PP. 205-207.

2. NS—KM XVIII. 4-9a; KSS XX. 4-9a; GOS XVIII. 4-9a; ND I, III. 103, PP. 11, 152.

3. NS—KM and KSS XXVII. 1-18a.

4. NS—KM XXXVI. 16a; KSS XXXVI. 20a.



Bharata also deals with the acoustic and other arrangements of the theatre and says that there should be nothing in the theatre to hinder the spectators' sight and hearing, and to obstruct in their maximum enjoyment of the emotional pleasure.<sup>1</sup>

As everything employed in a Sanskrit play points to the arousing of *rasa* in the spectator, it becomes essential for us to understand the nature, process and essence of *rasa* very clearly.

Bharata describes the nature of *rasa* as follows. What are known in ordinary language as causes, effects and auxiliaries of the latent emotion of love and the like come to be spoken of as excitants, ensuants and variants respectively, when found in drama and poetry, and when the latent emotion comes to be manifested by these, it is known as *rasa*.<sup>2</sup> There are different theories regarding the psychological nature of *rasa*.

Bhaṭṭa-Lollaṭa holds the theory of production [*utpattivāda*] which is allied to the Mīmāṃsā school of philosophy. According to it, the sentiment is generated in the personated character and secondarily recognized in the personating actor. The *naṭa* imitates the original hero and becomes the source of charm to the audience. This theory is open to objection as Bhaṭṭa-Lollaṭa fails to recognize that the sentiment must be in the spectator, otherwise he cannot enjoy it.

Śrī-Śaṅkuka's theory which is based on inference is called *anumitivāda* and is affiliated to the Nyāya school. According to this doctrine *rasa* is inferred to exist in the actor, though not really present in him. The emotion, thus inferred, and then sensed by the audience, adds to itself a peculiar charm and fully develops into a sentiment in the spectator. In this theory the actor is identified with the original hero in the same way as the idea of a 'horse' that one has in regard to the picture of a

---

1. NS—KM II, 24; KSS II, 21; GOS II, 24.

2. NS—KM VI, Prose, P. 62; KSS VI, Prose, P. 71; GOS VI, Prose, PP. 274-289.

horse [ *citraturaganyāya* ]. The objection to this view is that it is not inference but perception and feeling that add charm.

Bhaṭṭa-Nāyaka's theory is based on the threefold potency of a piece of poetry and is related to the Sāṅkhya philosophy. According to him, the sentiment is due neither to production [ *utpatti* ], nor apprehension [ *pratīti* ]. "What happens is that in poetry and drama words are endowed with a peculiar presentative potency, distinct from direct denotation [ and indirect indication ]—which tends to generalize the excitants, ensuants and variants, and thereby presents to consciousness the 'latent emotion,' which thereupon comes to be relished by a process of delectation abounding in enlightenment and bliss, due to the plenitude of the quality of harmony [ *sattva* ]". According to this view the relishing of *rasa* is the outcome of the purely verbal process of 'generalized presentation.' This is open to the objection that it makes the unwarrantable assumption of what is called verbal process.

Finally, we come to the view of Abhinavagupta who holds that a new potentiality like '*bhojakatva*' [ power of enjoyment ] as enunciated by Bhaṭṭa-Nāyaka is not necessary. Its work can be done by suggestion [ *vyañjanā* ]. Abhinavagupta's theory is *rasa-abhivyaktivāda* [ theory of the manifestation of *rasa* ]. The sentiments already exist in the form of *saṁskāras* [ predisposition ] in the minds of the cultured [ *sahṛdaya* ] spectators. It is aroused by the witnessing of a dramatic performance, or on hearing a poem. The actions of Arjuna will excite the heroic sentiment.

The explanation offered by Abhinavagupta is as follows: "In the mind of such spectators as are proficient in the art of feeling emotion, a particular emotion is already present in the form of a 'pre-disposition'; thus lying latent, it becomes patently manifested by such agencies as the feminine figure and such other objects which, in ordinary parlance are known as 'causes', 'effects' and 'auxiliaries'; but in poetry and drama, they renounce these names by reason of their being endowed with the faculty of exciting

and so forth, and, on this account, come to be known by the extraordinary names of 'excitants', 'ensuants' and 'variants': These excitants and the rest are recognized in their most generalized forms, not partaking of any restrictions due to either the affirmation or negation of any of these specific relationships that are involved in such conceptions as 'this is mine' or 'this is my enemy's,' or 'this belongs to a disinterested person' [ where specific relationship is affirmed ] or 'this is not mine,' 'this is not my enemy's,' 'this does not belong to a disinterested person' [ whose specific relationship is denied ]. Though the said emotion actually subsists in the particular spectator himself, yet by reason of the generalized form in which it is presented, the man loses, for the moment, all consciousness of his personality and has it merged in the universal, and thus representing the mental condition of all men of poetic sensibility, he apprehends the said emotion. As it becomes manifested in its most generalized form, it has no existence apart from its own apprehension. In fact its essence consists in its being relished, and it lasts as long as the excitants, ensuants and variants continue to exist. It is relished in the same manner as a mixed beverage, and when it is relished, it appears as if it were moving before the eyes, entering the inmost recesses of the heart, inspiriting the entire body, and throwing into the background everything else; it makes one feel the rapturous bliss of Brahman; the emotion thus manifested becomes the source of transcendent charm and is spoken as *rasa*".<sup>1</sup> Thus Sanskrit rhetoricians approach the aesthetic pleasure from the point of view of the reader or spectator, while European writers of poetics view it from the poet's standpoint.

A distinction is drawn between sentiment [*rasa*] and emotion [*bhāva*]. Emotion may be both pleasant and unpleasant but a sentiment is always pleasurable and unique. There is no unpleasantness in a sentiment as it is aroused through a process of generalization [*sādhāraṇīkaraṇa*]. This explains why

---

1. KP Prose, pp. 87-95. For Translation of the passage see 'Translation of Kāvya-prakāśa' by Gaṅgānātha Jhā.

the pathetic [ *karuṇa* ] and repulsive [ *vibhatsa* ] sentiments find place in the scheme of *rasa*. They are unpleasant as emotion [ *bhāva* ] but when generalized become pure and pleasurable [ *ānandamaya* ]. In this connection and against the above, Rāmacandra and Guṇacandra, authors of the *Nāṭyadarpaṇa*, observe that some *rasas* do produce pain while others produce pleasure. As *rasas* producing pain, they mention the pathetic [ *karuṇa* ], furious [ *raudra* ], repulsive [ *vibhatsa* ] and terrific [ *bhayānaka* ]. They assert that the statement that all scenes whether of pathos or of horror invariably cause pleasure is against experience. If pleasure is experienced in all scenes, a spectator should not be alarmed—for being alarmed is not consistent with the feeling of pleasure experienced in witnessing a scene of horror. But the spectator gets alarmed on seeing the scenes of Draupadī's or Sītā's misery. In reply to the question why people go to witness *duḥkḥātmaka* dramas [ whose essence is sorrow ], they say that it is owing to the skill of the poet or the actor.<sup>1</sup>

But the analogy given by Rāmacandra and Guṇacandra does not make any appeal. According to Abhinavagupta, aesthetic pleasure has no reference to the actual feelings common in the world of realities but to dormant mental conditions awakened under certain circumstances. A particular *rasa* is pleasurable not exclusively because of its nature. The erotic sentiment [ *śṛṅgāra* ] is not pleasurable because it is *śṛṅgāra* but because the reader or the spectator has his mind rid of distractions.<sup>2</sup> We agree with Madhusūdana Sarasvatī who opines in this connection that the tears caused by a pathetic situation were to the original character no doubt tears of worldly sorrow [ *laukika* ] but to the spectator they were tears only of joy and absolutely transcendental [ *alaukika* ] in their essence.<sup>3</sup>

The Sanskrit dramas in their preludes state that the object of their presentation is the pleasure of the audience.

---

1. ND 109 and Prose, PP. 158-159.

2. Abh, Bh, PP, 289-290.

3. Bhagavadbhaktirasāyana III. 5-6, PP, 129-130.

Thus in the prelude of the *Abhijñānaśākuntala*, the manager explains the object of the presentation of the play to the *naṭī* clearly; 'Lady, I tell you the real truth until the wise are satisfied with the representation, I do not consider my skill in representation to be perfect. The heart of man although well instructed has no confidence in itself'.<sup>1</sup> In the *Pāravatīpariṇaya*, the *sūtradhāra* tells the *naṭī* that a play is presented for the pleasure of the cultured.<sup>2</sup> In the *Dhūrtaviṭasaṁvāda*, the object of presentation is said to be the pleasure of the wise and the good.<sup>3</sup> In the *Mālavikāgnimitra*, it is stated that the presentation is for the gratification of all, though their tastes differ in various ways.<sup>4</sup> Thus the object of presentation of plays is to bring satisfaction to the audience by evoking in their minds *rasa*, the transcendental pleasure.

### C. Occasions for Enactment

Legendary tradition about the origin of the drama tells us that the practical exhibition of a drama named 'Fall of Asuras' was arranged for on the occasion of the '*Indradhvaja*' festival, the sons and disciples of Bharata and *gandharvas* and *apsarās* being the actors.<sup>5</sup> The first play was enacted on the occasion of the religious festival, the '*Indradhvaja*', which comes at the end of the rains and in the beginning of autumn. According to the *Abhinayadarpaṇa*, *nāṭya* and *ṛtta* should be witnessed particularly at the time of a festival. Those who desire good luck should cause *ṛtta* to be performed on such occasions as coronation, celebration by a king, a festival, a procession with an image of a god, a marriage ceremony, reception of a friend, entry into a new town or house and the birth of a son, for *ṛtta* is auspicious.<sup>6</sup>

---

1. Śāk Prelude, 2, P. 6.

2. Pāravatīpariṇaya I, 5, P. 2.

3. Dhūrtaviṭasaṁvāda prelude, p. 1.

4. Māl. I, 4, p. 7.

5. NS—KM I, 20b-25; KSS I, 54b-60; GOS I, 54-59a.

6. AD, 12b-14, P. 2.

From a close study of the introductory scenes in dramas it is evident that the plays were enacted on different occasions according to their nature. They were not only enacted at the annual fairs of temples and festivals in different seasons but were also performed at the pleasure of the poet's patron or before a learned assembly or the village people.

In the prelude of the *Uttararāmacarita* the *sūtradhāra* says "Let me address the respectable gentlemen assembled today at the fair of the divine Kālapriyanātha. Let it be known to your honours—there is, as you know well, an illustrious scion of the Kaśyapa's race, bearing the distinctive title of 'Śrī-Kaṇṭha,' versed in grammar, *mīmāṃsā* and logic, Bhavabhūti by name and son of Jātukarṇī, a Brāhmaṇa, whom the Goddess of Speech follows like one enslaved. The *Uttararāmacarita*, a play composed by him, will now be represented."<sup>1</sup> In the prelude of the *Anargharāghava* the *sūtradhāra* states that an actor named Kalahakandala enacted a drama in the *yātrā*<sup>2</sup> in honour of god Puruṣottama.<sup>3</sup>

In the *Mālavikāgnimitra*, the *sūtradhāra* says: "I am asked by the learned audience that I should represent on the occasion of the spring festival the play *Mālavikāgnimitra*, the plot of which has been composed by Kālidāsa. Please therefore begin music."<sup>4</sup> In the *Ratnāvalī*, the *sūtradhāra* says; "Enough of prolixity. To-day, on the occasion of the spring festival, being called with great respect by the multitude of kings, who are dependent on the lotus-like feet of our king, the illustrious Śrī-Harṣa, and who have come here from regions of the various directions, I was thus addressed: "Our master, Śrī-Harṣa has composed a *nāṭikā* entitled

---

1. URC Prelude, P. 3.

2. Yātrā literally means a 'procession', and also a 'pilgrimage'. In the whole of Northern India yātrās are taken out in honour of a deity and they occupy a unique position in Bengal. Huge crowds of all sects of people move in a procession, sing and dance to the glorification of the deity in a temple, street or courtyard,

3. AR Prelude, p. 6.

4. Māl prelude, p. 2.

*Ratnāvalī*, graced with a novel arrangement of the plot. We have heard about it from hearsay but have not seen it acted. Out of respect, therefore, for that very king, the gladdener of the hearts of all people, and with a mind to favour us, the same should be enacted on the stage by you with proper acting.”<sup>1</sup> In the *Dūtāṅgada*, the *sūtradhāra* tells us that the *Dūtāṅgada*, a shadow play, may be enacted during the spring festival in the procession of Śrīkumārapāla-deva.<sup>2</sup>

In the *Vikramorvaṣīya*, the *sūtradhāra* says, “Oh Mārīṣa ! this assembly has very often witnessed the plays of former poets. I shall, therefore, bring on the stage to-day a new play known as the *Vikramorvaṣīya*. Let the company of actors be told that they should be very careful about their respective parts. Actor: As you command, Sir. *Sūtradhāra*: I shall now announce to the honourable gentlemen here with a bow. Either out of curiosity for us, your humble petitioners, or out of respect for the excellent hero of the plot, you will please listen with attentive minds to this play of Kālidāsa.”<sup>3</sup> In the *Prabodhacandrodaya*, the *sūtradhāra* says: “We want to enact the play with the action in which the quietistic sentiment plays an important part. You should enact the drama, the *Prabodhacandrodaya*, in front of the king, Kīrtivarma. The king wishes to see the play with his associates. The king, who has entered the path of *Śāntapatha* for his own pleasure, has ordered me to enact this drama. Therefore, instruct the *naṭas* to dress themselves according to the theme.”<sup>4</sup> The *sūtradhāra* in the *Kundamālā* says “I have been commanded by the audience that I should stage *Kundamālā*, the work of the revered poet Dīnāga, resident of Arātālapura. So having called the noble lady [ wife ] rendering co-operation in the performance of this

---

1. Rat prelude, p. 5.

2. Dūtāṅgada p. 2.

3. Vik prelude, p. 3.

4. Prabodhacandrodaya prologue, pp. 13-14.

dramatic composition I betake myself to the stage.”<sup>1</sup> In the *Kirātārjunīavyāyoga* [ military spectacle ] it is stated that the drama was enacted at the pleasure of the king.<sup>2</sup>

Certain plays were enacted only for the amusement of the village people. The *Mahānāṭaka* is the best and the only preserved drama which was improvised by village artists.<sup>3</sup> We find explanation for this when we consider that these are also the prominent features of the *yātrās* of the modern days.

The view of Wilson and some other European scholars with regard to the occasion of the enactment of Sanskrit plays is as follows:

‘The dramatic entertainments of the Hindus essentially differed from those of Modern Europe in the infrequency of their representation. They seem to have been enacted only on solemn or public occasions. In this respect they resembled the dramatic performances of the Athenians, which took place at distant intervals, and especially at the spring and autumnal festivals of Bacchus.’<sup>4</sup>

But in this connection our view is different from that of the European scholars. Though the occasions mentioned by the authorities on Sanskrit dramaturgy are of infrequent occurrence, the mention of the theatre for general people and regular troupe of actors and actresses and also the reflection from the preludes of dramas as to their enactment at the will of the poet’s patron at any time of the year, shows that they were kept in regular occupation by more frequent representation than what is generally considered.

#### D. Places for Performance

The theatre is a place specially designed and equipped for the presentation of plays. The various terms used in Sanskrit for the theatre are *nāṭyagrha*, *nāṭyamaṇḍapa*, *prekṣāgrha* or *prekṣāgāra*. The drama and the theatre point to each other’s

---

1. Kundamālā prelude, p. 7.

2. Kirātārjunīavyāyoga prologue, p. I.

3. Mahānāṭaka 1.5.

4. Wilson: ‘Select Specimens of the Theatre of the Hindus’ I. XIII-XIV.



mutual existence and a dramatic work becomes most impressive when it is enacted on the stage. They constitute a very important chapter in the social and cultural history of a nation. The *Mṛcchakatika* gives a more graphic description of the ancient Indian society than any other work of that time.

The ancient Indian kings had pleasure gardens, theatres and music halls attached to their spacious palaces, generally for the entertainment of their queens. Play-wrights and regularly appointed professors and actors were patronised by them. Histrionics, music and dancing were a part of the education of the high-born ladies. In the *Mālavikāgnimitra*, Gaṇadāsa and Haradatta were appointed professors and Mālavikā was taught not only dancing but also histrionics.<sup>1</sup> In the *Śilparatna*<sup>2</sup>, the *Kāvyamīmāṃsā*<sup>3</sup> and the *Saṅgītamakaranda*<sup>4</sup> there is reference to a palace theatre. From the seating arrangement of the theatre described in the *Saṅgītaratnākara* it is clear that it belonged to a king. The audience consisted of men of education, culture and artistic sense, such as kings, queens, ministers, court-poets and courtiers.

From an account given in the *Saṅgītaratnākara* the following information is available: The music hall was decorated in a unique manner. It was furnished with flowers, flags and jewelled pillars. The president, generally the king, took his seat on a beautiful lion throne in the middle of the auditorium. To his left, court ladies of the harem were seated, but the chief queens were provided seats to his right. Behind these chief queens, seats for the chief treasury officers were arranged. Close thereto, honoured astronomers, astrologers, physicians, psychologists, humorous poets and people conversant with tradition were seated. To the right of the chief queens were the seats for ministers and military officers of high rank. Fashionable men and women were seated in such a manner as to surround the ladies of the court. Just behind the king youthful

---

1. Māl. II 8.

2. ŚR I. XXXIX 35-36a, p. 199.

3. Kāvyamīmāṃsā Prose, pp. 54-55.

4. Saṅgītamakaranda I. 2-7, p. 27.

and beautiful women guards, wearing twinkling bracelets and holding beautiful chowries, were to occupy their places. Forward guards were seated to the left, having in front the vocal singers, conversationalists, bards and experts in panegyric. Seats for members of the royal family were provided in the surrounding places. Then there were seats for dexterous guards holding canes. Armed body-guards used to stand in the four corners of the theatre. In the above manner the audience was provided seats and thus the king used to see the performance. In this type of ancient theatre<sup>1</sup>, a diagram of which is given herein, there appears to be no place for the general public. This is apparently a theatre in the palace itself.

In the *Mānasāraśilpaśāstra*, there is a reference to the seating arrangement in a temple theatre as also in a palace theatre. Theatres are said to have been built in continuation of the open courtyard, linking the tank or shed in the temple and the palace. In the theatre the divine and royal thrones and seats made of wood, stone and brick were arranged in compartments partitioned by low sliding walls.<sup>2</sup>

Most of the celebrated temples in India had *nāṭa-mandiras* where dancers and actors propitiated the god or goddess through the representation of their art. The name *nāṭamandira* is significant as pointing to the existence of temple theatres. Paid women dancers were employed in all rich temples and dramas in praise of a deity were represented in festivals. The *Uttararāmaçarita* was enacted at the annual *yātrā* in honour of Kālapriyanātha.<sup>3</sup> In some of the temples even now dances are prominent items of the daily programme after the evening offerings to the gods. Devadāsīs dance in temples in Jagannāthapurī and south India even these days. In ancient India places, halls or yards, were specially provided in temples for dancing, music and recitations. In the Kailāsa

---


1. SR VII, 1351-1361a. For diagram See p. 27.

2. MS XLVII. 1-17, pp. 308-309.

3. URC prelude, p. 3.

Diagram showing the seating arrangement  
in a PALACE THEATRE according to S.R.

STAGE





temple at Ellora caves a *nāṭamandira* hall is easily noticeable. These *nāṭamandiras* were meant for priests, *sādhus*, religious and learned men.

Plays were presented to the general public in open courtyards and on improvised stages. The stage was temporarily built and so, evidently, its paraphernalia was very simple. There was preponderance of singing and dancing and of the comic element. The *Māhānāṭaka* is the only available drama of this species. The general setting is given by the poet with some excellent poetry. Dialogue is improvised by the actors and actresses. It is easily understood because the subjects are taken from the *Rāmāyaṇa*, the *Mahābhārata* or the *Purāṇas*. The religious or mythological theme of the *Māhānāṭaka*, its epic or narrative character, the imperfect nature of its dialogues, its descriptive passages interspersed with elaborate and vivid stage directions, its charms like *vaitālika vākya*s, its length and extended working out of the story—all these peculiarities find natural explanation when we consider that these are also the prominent features of the *yātrās*. As the imperfect dialogues and narrative passages were frequently supplemented by the improvisation of the players it is not surprising that a work meant for such performances increased in bulk, incorporating into itself fine poetic passages from various sources.

# CHAPTER III

## CONSTRUCTION OF THE THEATRE

### A. Types and Measurements

A detailed account of the interior arrangement of the theatre is given by Bharata. Later authorities also furnish details which show that the main features described by Bharata were adhered to in later times.

According to the *Nāṭyaśāstra*, the *Śilparatna* and the *Bhāvaprakāśana*, the play-house as made ready for performance may be of three types. The *Viṣṇudharmottara*<sup>1</sup> states that the theatre might be of two types, rectangular and square. The square theatres, according to it, should be 32×32 *hastas* [ cubits ] in area.

In Sanskrit texts dealing with architecture, dimensions of all kinds of buildings are comparative and suggestive and can be altered to suit the requirements of the various kinds of structures. The *Śilparatna* says that the play-house may be of two or rather three types, divided into four equal parts, either by drawing lines lengthwise or breadthwise externally or from top to bottom, every part or two parts being separated by pillars for the audience and the fourth part, left for the stage proper.<sup>2</sup>

The architectural details of the *nāṭyamaṇḍapa* are very clearly laid down in the *Nāṭyaśāstra*. There are three types of play-house—*vikṛṣṭa* [ rectangular ], *caturasra* [ square ] and *tryasra* [ triangular ].

The *Bhāvaprakāśana* reads *vr̥tta* in place of *vikṛṣṭa*,<sup>3</sup> but no structural details are given there. One has therefore to rely on the three types given in the *Nāṭyaśāstra*—*vikṛṣṭa*.

---

1. VD III, 20. 4.

2. ŚR I, XXXIX, 60-67, pp. 201-202.

3. BP X, p. 295, LL, 9-18.

*caturasra* and *tryasra*.<sup>1</sup> The *vikṛṣṭa* is a rectangular theatre according to Abhinavagupta.<sup>2</sup>

He notes two views about the varieties of theatres. According to one opinion, *vikṛṣṭa* is *jyeṣṭha*, *caturasra* is *madhya* and *tryasra* is *avara*. The other divides each of the first type into *jyeṣṭha*, *madhya* and *avara*, thus getting nine types which when measured in *hastas* and *daṇḍas* would be eighteen. Abhinavagupta accepts this opinion and propounds clearly his view about the nine divisions of the theatre. But we should accept the three types of the theatre as they are referred to at various places and are actually defined in the *Nāṭyaśāstra*. The only question which arises is that at one place the *Nāṭyaśāstra* states that *jyeṣṭha* is 108 *hastas*, *madhya* is 64 *hastas* and *kaniya* is 32 *hastas*, and at another place  $64 \times 32$  *hastas* is said to be the measurement of the *vikṛṣṭa* type and  $32 \times 32$  *hastas* of the *caturasra* type. Thus no clear indication about the measurement of the *avara* type is available. It is therefore difficult to establish any connection between the two statements. So, to harmonise the statements, it can be said that there were nine varieties, or even eighteen varieties of theatres taking the *hasta* and the *daṇḍa* measurements into consideration as stated by Abhinavagupta. Though Abhinavagupta himself feels that so many divisions have no purpose to serve, yet he refers to them only to maintain a particular standpoint.<sup>3</sup>

From the *Nāṭyaśāstra* one can find that the *jyeṣṭha* type is specially meant for gods, *madhya* for kings and *avara* for ordinary people. Abhinavagupta says that the *jyeṣṭha* theatre may be used for dramas where gods are heroes, as in *Dima*, the *madhya* when kings are heroes, as in *Prakarāṇa*, and

---

1. NS—KM II. 8-14; KSS II. 7-11; GOS II. 7-14. In GOS and KM editions, verses 13 and 14 are repeated. The repeated verses in GOS are numbered as 25 and 26 while in KM they are not numbered but written between verses 24 and 25.

2. Abh Bh. I. p. 50.

3. Abh. Bh. I. pp. 50-51.

the *avara* when ordinary men are heroes as in *Bhāṇa* and *Prahasana*.<sup>1</sup>

When we consider the verse of the *Nāṭyaśāstra* '*Pramāṇam Eṣāṁ nirdiṣṭam hastadaṇḍasamāśrayam*'<sup>2</sup> we find that measurement for the building of theatres was dependent upon the conception of *hasta* and *daṇḍa*. What are these measurements? The *Nāṭyaśāstra* accepts that the smallest measure is *aṇu* [ atom ]. The table of measurement according to this authority is as follows. Eight *aṇus* make one *raja* [ cardust ], eight *rajas* one *bāla* [ hairend ], eight *bālas* one *likṣā* [ nit ], eight *likṣās* one *yūkā* [ louse ], eight *yūkās* one *yava* [ barley ], eight *yavas* one *aṅgula*, 24 *aṅgulas* one *hasta*, four *hastas* one *daṇḍa*.<sup>3</sup> This list substantially agrees with the one given in the *Arthaśāstra* of kautilya.

From the *Mānasāraṇīpaśāstra* we find that *aṅgula* [ finger breadth ] and the *hasta* [ cubit ] measures are in fact of the same category. The finger breadth, equivalent to three-fourths of an inch, is perhaps the earliest unit of measure. It has its own defects, namely, the finger of two persons is hardly of equal breadth and the length of the finger of a person is liable to change owing to various natural causes. Apparently with a view to avoid these defects the finger breadth is ascertained by the measure of certain other objects, atom, cardust, hairend, nit, louse and barley grain. The largest finger breadth is stated to be equal to eight barley grains, the intermediate of seven barley grains and the smallest of six barley grains.<sup>4</sup> The *aṅgula* measure is practically the same in almost all Sanskrit works, such as the *Arthaśāstra*<sup>5</sup>, bearing on the subject.

The measuring tape should be made of *kārpāsa*, *vādara* *valkala* or *muñja* and must have no joints. Wise people

1. Abh. Bh. I. pp. 51-52.

2. NS—KM II. 10a; KSS II. 9a; GOS II. 9a.

3. NS—KM II. 15-19; KSS II. 12-16; GOS II. 15-19.

4. MS II. 20-32, pp. 4-5.

5. AS I. XX. p. 263.



should employ such thread as cannot be broken. The tape should be handled carefully.<sup>1</sup>

In constructing a play-house it is necessary, according to Bharata, that the soil should be first examined. It must be even, steady, hard and black or white. The whole field must be ploughed and bones, nails, skulls and such other things taken out. Then in the *pusya* constellation it must be measured with a white string. After the foundation walls have been constructed the pillars may be erected in the *Rohini* or the *Śravaṇa* constellation. Emphasis is thus laid on the selection of hard land, on its purification from bones and bushes and on fixing definite boundaries with a thread, so that the prescribed measurements are adhered to.<sup>2</sup>

The standard theatre [*nāṭyaveśman*] is a rectangular building, 64 cubits in length and 32 cubits in breadth, marked out into two equal divisions, the auditorium [*raṅgamaṇḍala*] and the stage [*raṅgabhūmi*]. The stage is divided into two equal parts—the front and the rear, the latter being the green room. The front part is again divided into two equal parts. Of these two parts the one behind is the head of the stage [*raṅgaśirṣa*] and the front part is the stage proper where a play is acted. On both sides of the stage proper, two *mattavāraṇīs*, equal in measure to the stage, are constructed. It is clear from the diagram of the rectangular theatre that the auditorium is thus 32×32 cubits, the front stage 8×16 cubits, the back stage 8×32 cubits and the green room 16×32 cubits.<sup>3</sup> Abhinavagupta gives two views on the measurements of the stage proper. According to one view, it was 16 cubits in length and 8

- 
1. NS—KM II. 30b-34; KSS II. 28b-32; GOS II. 31-34. Here in GOS numbering is wrong: 31, 32, 33 are repeated.
  2. NS—KM II. 27-30a; KSS II. 24-28a, 46a; GOS II. 29-33a, 48a. Here in GOS numbering is wrong. The numbers 31, 32, 33 are repeated but the verses are different.
  3. NS—KM II. 36-37, 57-58, 74b; KSS II. 34b-36a, 64b-66a, 69-70, 86b; GOS II. 36b-38a, 66b-68a, 71, 72, 90a. For diagram see p. 35.

cubits in breadth, and according to the other, it was 8 cubits in length and 16 cubits in breadth.<sup>1</sup>

The *caturasra* type of theatre is 32 cubits in length and 32 cubits in breadth.<sup>2</sup> Abhinavagupta quotes Śaṅkuka's opinion on the divisions of the *caturasra* theatre. He states: The whole field 32×32 cubits should be divided lengthwise and breadthwise into eight equal parts, thus making 64 squares as is done in a chessboard. The *raṅgapīṭha* should be in the four inner squares. In this type the *mattavāraṇīs* will be 8×8 cubits each and the *raṅgaśīrṣa* 8×8 cubits [ or 8×32 cubits as there are no walls on the breadth line]. The size of the *nepathyagrha* is 4×32 cubits and that of the auditorium 12×32 cubits. This type is also shown in the diagram of the *caturasra* theatre.<sup>3</sup>

The *tryasra* theatre is in the form of an equilateral triangle. It is divided into eight parts on each side and from each dividing point lines are drawn parallel to those on the side of the equilateral triangle. Thus 64 triangles are formed. In four triangles in the middle the *raṅgapīṭha* is constructed. Behind the *raṅgapīṭha* is placed the *raṅgaśīrṣa* in five triangles [ or 13 triangles in the absence of walls ] and the *nepathyagrha* in 15 triangles. Each of the *mattavāraṇīs* is constructed in eight triangles. The remaining triangles are reserved for the audience. This is illustrated in the diagram of the *tryasra* type.<sup>4</sup> But no exact measurement of this type of theatre is available in the *Nāṭyaśāstra* or the *Abhinavabhāratī*.

### B. Rāṅgapīṭha and Decoration

The height of the theatre invariably depended on the type of the play to be presented in it. Theatres were constructed in two storeys having the shape of a mountain

1. Abh. Bh. I, p. 58.

2. NS—KM II, 75-77, 84b-89; KSS II, 87-89, 96b-101; GOS II, 90b-93a, 100-105a.

3. Abh. Bh. I, p. 66, For diagram See p. 39.

4. NS—KM II, 90-93a; KSS II, 102-104; GOS II, 105b-108, For diagram see p. 43.

presenting a change an actor would walk on the stage and take rounds as required by distance.

We may take the *Mṛcchakaṭika* as an example to illustrate the use of *kakṣyās* on the stage.

In the *Mṛcchakaṭika* Cārudatta and Maitreya after attending a music concert come to their house. Maitreya says: 'Well, here is our house. Vardhamānaka, open the door.'

Vardhamānaka says: 'I hear the voice of the noble Maitreya. The noble Cārudatta has come. So I will open the door for him.' [He does so]. Entering the house they both go to sleep.

Now Śarvilaka enters the stage and looks at the sky joyfully: 'Why, the moon is setting'. He feels the wall, finds it deteriorated. He measures and surveys the wall with his sacred thread. A snake bites him. He binds his finger with his sacred thread and acts the manifest effect of poison.

He resumes his work shoving in a dummy man at first. With that he enters the house and looking before him says: 'I see there are two persons sleeping here. All right, I shall open the door as a defensive measure. But hark, the door squeeks as the house is very old. Let me go in search of water. Now where can water be found?' [He goes about in search, brings water and sprinkles it on the door and enters the house and takes ornaments].

Radanikā [entering] 'Oh, alas, Vardhamānaka is sleeping in the outer rooms'. Śarvilaka wants to kill Radanikā, leaves her because of her being a woman and escapes.

She wakes Maitreya and Cārudatta.

From the above incident one can anticipate the existence of a door on the stage, but in reality there was none. It was all done with gestures. Only Maitreya and Cārudatta enter one *kakṣyā* from another *kakṣyā*. Then Śarvilaka searches for water and brings it.<sup>1</sup> Of course, as described

---

1. Mṛch III. pp. 69-77.

in the *Nāṭyaśāstra* he must have come the same way through which he might have gone out. Vardhamānaka is said to be sleeping in the outer room when really he might have been sleeping in another *kakṣyā*.

Further, in the same drama a court-scene is represented. Śodhanaka, a court peon, enters and says: 'Officials of the court have commanded me, Śodhanaka, go to the court and lay the seats.' I shall just go to the hall of justice to keep it ready. [He walks a few steps and looks before him]. Here is the hall of justice. I will enter. [He enters and sweeps it and spreads a carpet]. I have swept the hall of justice and laid the seats. So I shall just go back to the officials to tell them about it. [He walks a few steps and looks before him]. 'What ? It is that bad man, the king's brother-in-law, who is coming this way. So I shall avoid his sight and go in another direction.' [He stands away: Now enters Saṁsthānaka, gorgeously dressed. Saṁsthānaka walks a few steps and looks before him]. 'Here it is the hall of justice. I shall enter.' [He enters and looks round]. 'Why, the seats have been placed. The court officials will come in a moment. I shall take my seat here in this grassy quadrangle and wait.' [He does so. Śodhanaka walks in another direction and looks before him]. 'Here come the officials of the court, I will approach them.' [He approaches them].

[Enters the Judge accompanied by the Mayor, the clerk and others]. Śodhanaka: Please come your Lordship, come this way, please. [They walk a few steps]. Here is the hall of justice. May your Lordship enter.' [They all enter].

Judge: 'Good Śodhanaka, go out and see if there are any petitioners.'

Śodhanaka goes out and Saṁsthānaka places his complaint before the judge.

Cārudatta and Vasantasenā's mother are called. And the petition is considered.<sup>1</sup>

From the above it is quite clear that the carpet is spread in the court and the seats are arranged. This is one division [ *kakṣyā* ]. Samsthānaka waits for the officials to come outside the court hall. He is in another division of the stage [ *dvitīyā kakṣyā* ]. The judge, accompanied by the Mayor, the clerk and others, enters. The judge is naturally in front of them all and then others enter according to their rank. The servant who goes out to call Cārudatta and Vasantasenā's mother might have brought them the same way as he had gone.

The use of *kakṣyās* can be shown with reference to other dramas also. Thus from the testimony of the *Nāṭyaśāstra* and the actual incidents in the *Mṛcchakaṭika*, we find that the stage could be used to represent a place where persons sleep and court scenes are enacted and that it was divided into as many apartments [ *kakṣyās* ] as the plot required.

Theatres were decorated with all the oriental splendour, colour and brilliance. The front portion of the stage used to be built of wood and richly decorated with wooden carvings. Garlands were hung on it and ornamental arches added to its grace. The *maṇḍapa* had windows. The wood work was polished and the walls white washed before pictures were painted on them. The wood work had *ūha* [ an additional moulding-upper-most portion of a column ], *pratyūha* [ a supporting member, lower-most portion of a column ], *sañjavana* [ quadrangle ], *vyāla* [ an arch marked with leograph ], *sālabhañjikā* [ an image or figure made of *sāla* wood i. e. statuettes ], *nirvyūha* [ a cross circle ], *kuhara* [ interior window ], *vedikā* [ pedestal ], *yantra* [ an architectural member of the bedstead, a band ], *jāla* [ a latticed window ], *gavākṣa* [ windows resembling the cow's eye ], *pīṭha* [ pedestal, a pavement ], *dharaṇī* [ a kind of tree on which pillars are constructed ], *kapotālī* [ a dove-cote, crown

work, fillet ] and *kuṭṭima* [ a pavement ] and *stambha* [ column ]. Thus it is decorated with various columns. After the wood work, come the walls. The column, *nāga-danta* [ a kind of window resembling the hood of a cobra ], *vāṭāyana* [ window ], *koṇa* [ a class of building ], *pratidvāra* [ moulding of the base or column of a door ], *dvāra* [ door, a gate ] should not come opposite a door leading to the *raṅgaṭṭha*.<sup>1</sup> Dr. A. K. Coomarswamy notes some changes of meaning in the terms quoted above. He thinks that *nirvyūha* means 'storey', *vedikā* 'a railing' and *gavākṣa* 'an ordinary curved window.'<sup>2</sup>

### C. Rangasirsa, Green Room and Mattavaranis

In the *vikṛṣṭa* type of theatre the back stage [ i. e. *raṅgaśirṣa* ] is 8×32 cubits and in the *caturasra* type it is 8×8 cubits. As there are no walls breadthwise it may also be imagined to be 8×32 cubits. The exact measurements of the *tryasra* type are not available.

¶ The *raṅgaśirṣa* is built of six pieces of wood and furnished with two doors leading into the green room. It is smooth and even like a mirror and decorated with jewels. Its surface is not like the back of a tortoise or the back of a fish. The intermediate space is filled with very fine black earth, having the lustre of a pure mirror and studded with emeralds, sapphires, corals and other precious stones, arranged in various designs on the four sides \*

¶ The *raṅgaśirṣa* is constructed with six planks. According to Abhinavagupta, attached to the wall of the *nepathyagrha* and *raṅgaśirṣa*, two pillars should be erected, each at a distance of eight cubits from the other. By their side two

1. NS—KM II. 64-74; KSS II. 76-86; GOS II. 78-90a. The meanings of architectural terms have been taken from 'A Dictionary of Hindu Architecture' by P. K. Acharya and 'A Sanskrit English Dictionary' by Monier Williams.

2. Indian Historical Quarterly Volume IX. p. 594.

3. NS—KM II. 57b-62a; KSS II. 69b-74a; GOS II. 71b-76a.

other pillars, with a mutual distance of four cubits are raised. They will thus be four and with the upper and lower planks, will make the total six. At this place two doors one for the exit from and the other for entry into the *nepathyagrha* are constructed.

Portions of the back stage [ *raṅgaśīrṣa* ], as Abhinavagupta points out, seem to have been reserved as a place of rest for actors, for maintaining the secrecy of the entrance and exit and for purposes such as prompting, securing some stage effect and storing stage paraphernalia.<sup>1</sup>

It can be proved easily that the *raṅgapīṭha* and the *raṅgaśīrṣa* were two different portions. Scholars, except Monomohan Ghosh, hold that *raṅgapīṭha* and *raṅgaśīrṣa* were two distinct parts of the theatre. The *Nāṭyaśāstra* testifies to this. Again the terms *raṅgapīṭha* and *raṅgaśīrṣa* are suggestive of the whole theatre being regarded as one construction. According to Abhinavagupta, there is a curtain between the *raṅgapīṭha* and the *raṅgaśīrṣa*. The *raṅgaśīrṣa* was of a level higher than the *raṅgapīṭha* in the *vikṛṣṭa* type of theatre and of the same level in the *caturasra*. The *raṅgapīṭha* and the *raṅgaśīrṣa* were situated in two different parts of the theatre as they were used for different purposes. The *raṅgapīṭha* is meant for the actual representation of the plot whereas the *raṅgaśīrṣa* is left as a place of retirement for actors.

The *raṅgaśīrṣa* was also used for accommodating the orchestra. In the *Nāṭyaśāstra* it has been laid down that the musicians should sit in the *raṅgaśīrṣa*.<sup>2</sup>

The green room [ *nepathyagrha* ] is a part of the main building. Behind the curtain are the quarters of the actors [ *nepathyagrha* ]. In the *vikṛṣṭa* type of theatre the green room is 16×32 cubits and in the *caturasra* type it is 4×32 cubits. No measurements are available regarding the *tryasra* type.

The green room is fairly spacious to enable the several characters to attend to their 'make up'. The *nepathyagrha*

1. Abh. Bh. I. pp. 62-63.

2. NS—KM XXXIV. Prose, p. 429; KSS XXXIII, Prose, p. 449.

is a place from where sounds are raised to indicate uproar and confusion; here also are uttered the voices of gods and other persons whose presence on the stage is not desirable. In the *Mṛcchakatika*, when Śarvilaka boards the cart with Madanikā and starts on his journey, a voice from behind the curtain is heard, 'who hears? Who hears?' The chief of the police issues these commands. 'Here is the cowherd boy named Āryaka, whom a prophecy has declared to be a prospective king. King Pālaka, alarmed on account of his faith in the prophecy, has removed him from his hamlet and has put him in prison. Be diligent, therefore, in your respective posts.'<sup>1</sup> In the above passage the confusion and alarm which could not be represented on the stage were reported from the green room. Then, again, in the *Ratnāvalī* the magician's art which could not be shown on the stage was described through uproar behind the scenes: 'Here in the upper apartment, fire has broken out all of a sudden, imparting to the mansions the beauty of golden turrets by its masses of flames; its intense heat is indicated by its scorching the top of the trees in the garden; the pleasure-mountain looks dark like a watery cloud with smoke descending on it; the women-folk are distressed by the heat. Moreover, this fire has sprung up to give veracity, as it were, to the rumour about the queen's being burnt, which was formerly circulated in Lāvaṇaka.'<sup>2</sup>

The *Nāṭyaśāstra* prescribes that on both the sides of the *raṅgapīṭha*, two *mattavāraṇīs* are to be constructed. Both of them are higher than the *raṅgapīṭha* by one and a half cubit. A *mattavāraṇī* has four columns. Here it may be noted that the plinth of the auditorium [*raṅgamaṇḍala*]<sup>3</sup> should be equal

---

1. Mṛch IV. pp. 96-97,

2. Rat IV, 14-15, p. 103.

3. J. Grosset's edition of the NS reads *raṅgamaṇḍala* but other editions of NS read *raṅgamaṇḍapa* instead. In our opinion the correct reading seems to be *raṅgamaṇḍala*. Mankad seems not to be right when he says that "these two *mattavāraṇīs* and *raṅgapīṭha* should be higher [than the auditorium] by one and a half cubit," [Mankad's pamphlet on Ancient Indian theatre 1950].



in height to that of the two *mattavāraṇīs*. In the *vikṛṣṭa* and the *caturasra* types of theatre the *mattavāraṇīs* are to be 8×8 cubits each.<sup>1</sup>

Abhinavagupta says that *mattavāraṇīs* in *vikṛṣṭa* theatre may be eight cubits square. He holds out two distinct interpretations. According to one, the *mattavāraṇīs* are one and a half cubit higher than the *raṅgapīṭha*, and according to the other, the *raṅgapīṭha* and *mattavāraṇīs* are of the same height. Abhinavagupta seems to believe that *mattavāraṇīs* were used as *kakṣyās*.<sup>2</sup>

Scholars have interpreted the term *mattavāraṇīs* differently. Dr. P. K. Acharya considers the *mattavāraṇīs* as part of the pillars supporting the stage. On the two sides of the stage, over the four pillars is erected an entablature [ *mattavāraṇa* ] one and a half cubits or two feet and three inches high. This is the total height of the stage pavilion [ *raṅgamaṇḍapas* as stated by the commentator ]. But neither the height of the platform nor of the pillar is mentioned. The actual height of the stage is unspecified.

Some scholars think that *mattavāraṇīs* performed the same functions as the wings of modern theatres. But if we follow the *Nāṭyaśāstra* faithfully we find that *mattavāraṇīs* were higher than the *raṅgapīṭha* and that they were some special portions of the *raṅgapīṭha* because action was performed on these *mattavāraṇīs*. At one place Abhinavagupta refers to the size of the *raṅgapīṭha* as 8×32 cubits which, it seems, includes the *mattavāraṇīs* also. In *svāṅgas* or folk theatres of Northern India we find even to-day that there is a structure on both sides of the stage which is supported by wooden pillars from where some special and exciting speeches are made and scenes shown. The *mattavāraṇīs* could be used as *kakṣyās* if they were really used in this manner. The *kakṣyās* could be built low or high according to the requirement of the plot.

---

1. NS—KM II, 87-88a; KSS II, 64b-65, 99-100a; GOS II, 66b-67, 102b-103,

2. Abh. Bh. I. nn. 61-62.

### D. Pillars and Seating Arrangements

In connection with the *caturasra* theatre the *Nāṭyaśāstra* describes the arrangement of pillars as follows: On the *raṅgapīṭha* there must be ten columns strong enough to bear the burden of the *maṇḍapa*.<sup>1</sup> According to Abhinavagupta, who states the view of Śaṅkuka, four columns, Nos 1, 2, 3 and 4, should be raised at the four corners of the *raṅgapīṭha*. From the pillars in the *āgneya* [ south-east ] and *naiṛta* [ south-west ] directions, two pillars, Nos 5 and 6, each at a distance of four cubits towards the south, should be erected. Two more pillars, Nos 7 and 8, each at a distance of four cubits towards the north should be placed from the pillars in the *vāyava* [ north-west ] and *aiśāna* [ north-east ] directions. And from the pillars in *āgneya* and *aiśāna* directions, two pillars, Nos 9 and 10, each at a distance of four cubits towards the east, should be placed. Thus there are ten pillars to support the *raṅgapīṭha*.

In the auditorium [*raṅgamaṇḍala*] at first six columns and then eight columns are erected.<sup>2</sup> According to Śaṅkuka, Abhinavagupta explains: From the pillars Nos 5 and 6, two pillars Nos 11 and 12 are placed at a distance of four cubits towards the south, at a distance of eight cubits from each other. From the pillars, Nos 7 and 8, two pillars, Nos 14 and 15, should be placed at a distance of four cubits towards the north but they should also be at a distance of eight cubits from each other. Then from the pillars, Nos 5 and 8, two pillars, Nos 13 and 16, should be placed each at a distance of four cubits towards the east. These are the first six pillars supporting the auditorium.

From pillars Nos 11 and 15, two others, Nos 17 and 18, are placed to the east, each at a distance of four cubits. These pillars are also stated to be at a distance of four cubits from the southern and northern walls. Then at a distance of four cubits, half-way from the eastern wall on

---

1. NS—KM II, 78-79a; KSS II, 90-91a; GOS II, 93b-94.

2. NS—KM II, 81b-82; KSS II, 93b-94; GOS II, 97-98a.

both sides, two pillars Nos 19 and 20 may be placed. And from these pillars, Nos 19 and 20, pillars Nos 21 and 22, 23 and 24 should be placed, each at a distance of four cubits apart. Thus the next eight pillars should be arranged in the auditorium<sup>1</sup> The positions of pillars are marked in the diagram of the *caturasra nāṭyagrha*.

This is the arrangement of columns according to Saṅkuka and others. Abhinavagupta, following Vārtikākāra and Upādhyāya, has explained the arrangement in a different way to signify that the last eight columns should be in the *nepathyagrha*. But this view is not found in the *Nāṭyaśāstra* and is, therefore, rejected.

The auditorium in the *vikrṣṭa* theatre was 32×32 cubits, in the *caturasra* 12×32 cubits and in the *tryasra* according to the measurement of the theatre. People of different castes were to sit at places indicated by columns of various colours. Brāhmaṇas had the front seats indicated by a white column. Kṣatriyas occupied seats indicated by a red column. Behind them sat Vaiśyas and Śūdras, the former to the north-east and the latter to the north-west, their seats being indicated by yellow and blue columns.<sup>2</sup> There were other columns too, perhaps, to accommodate those who were not included in the four castes. Galleries were to be erected one behind the other. Seats in the auditorium were to be arranged in the form of a staircase to ensure visibility. They were to be made of wood and bricks and were to be one and a half feet [ one *hasta* or cubit ] above the ground. On these the spectators sat.

Thus, as the *Nāṭyaśāstra* prescribes different places for the castes and for various strata of society, it becomes clear that the theatres, in ancient India though constructed as a temporary structure, were planned for the general public.

---

1. Abh. Bh, I, pp. 66-67. For the Positions of Pillars see diagram p. 39.

2. NS—KM II. 48-54; KSS II. 47b-54; GOS II. 49b-56a.

### E. Doors and Roof

According to the *Nāṭyaśāstra*, the *vikṛṣṭa* theatre has two doors leading to the green room from the *raṅgaśīrṣa*. Between these doors sat players of musical instruments. In the *caturasra* type a door leads to the *raṅgapīṭha*. The first door is for people to enter the theatre. The second door is in front of the auditorium. In the *tryasra* type there is one door at the back of the *raṅgapīṭha* and another in one corner for the entry of the audience.<sup>1</sup>

Abhinavagupta cites two views about the construction of doors in a theatre. According to one view, there are only three doors, two from the *nepathyagrha* leading to the *raṅgaśīrṣa* and one in the auditorium for the entrance of spectators. According to the other, there are four doors: two in the *nepathyagrha* wall, one by which the *naṭa* enters with his wife '*bhāryāmīdāya naṭa-parivārah praviśati*' and one in the auditorium. Here Abhinavagupta takes '*ekadvāram*' as a collective use for two doors. Thus there are four doors in the *nāṭyagrha*. Others again hold that the theatre had six doors. They believe that two more doors existed on the southern and northern sides of the *raṅgapīṭha* leading towards the *mattavāraṇīs*.<sup>2</sup> The positions of doors are indicated in the diagrams of all the three types of theatre.

In order to know the directions in the theatre hall it has been mentioned in the *Abhinavabhāratī* that in the representation of drama that direction should be regarded as the east where the orchestra is situated by the side of the door leading to the green room.

The question has been asked if Indian theatres had roofs or they were open-air theatres as in Greece. In this connection we note that in the '*Nāṭyaśāstra*' there is only one reference to theatres without roofs. But the theatres in

---

1. NS—KM II, 57b-58a, 84b-86a, 91-92a; KSS II, 69b-70a, 96b-98a, 103-104a; GOS II, 71b-72a, 100-101, 106b-107.

2. Abh, Bh, I, pp. 69-70. For the positions of doors see diagrams, pp. 35, 39 and 43.

which plays were performed must have had roofs<sup>1</sup> There are indications in the *Nāṭyaśāstra* which prove the existence of roofs. In the section on arrangement of columns the *Nāṭyaśāstra* says that the columns should be *śaktā maṇḍa-padhāraṇe* and *ḍṛḍhānmaṇḍapadhāraṇe* both expressions meaning “capable of supporting the roof.” Bharata further praises a *śailaguhākāra* theatre, which too suggests the existence of roof. Abhinavagupta, emphasising that the theatre should not be too wide or too narrow, explains its properties of resounding [ *anuraṇana* ].<sup>1</sup> This again presupposes a roof. The *Nāṭyaśāstra* itself frequently uses the term *nāṭyamaṇḍapa* for the theatre. Thus there were theatres of both kinds—open-air theatres and those with roofs.

Now the question arises whether the structure of the theatre in ancient India was of a temporary or a permanent type.

Bharata’s description of theatres, their construction, size and shape, the position of the stage, orchestra and auditorium, indicates that theatres were of a permanent nature. The existence of such a word as *prekṣāgrha* or *pekkhāghara* also supports this view.<sup>2</sup> Further the *Nāṭyaśāstra* states that the playhouse should have the form of a mountain cave and should be two-storeyed.<sup>3</sup> The ruins of a cave found in the Rāmgarh hills which seems to have been used for the performance of plays or recitation of poems also support the view that the theatre was of a permanent nature.<sup>4</sup> The *Meghadūta* also refers to *Śilāveśma*.<sup>5</sup> There is, however, no historical record of a permanent theatre in ancient India. As the above-mentioned cave or the *śilāveśma* could have been a *nṛtyaśālā* and not a *nāṭyaśālā* and as it might have been used as a pleasure house by kings, one cannot say definitely that the theatre was of a permanent nature. It is certain that there were public theatres of a temporary nature in ancient India.

---

1. Abh. Bh. I, p. 54.

2. Māl I, P. 21.

3. NS—KM II. 69b; KSS II. 81b ; GOS II. 84a.

4. ‘Archaeological Survey of India Report’, 1903-4, p. 123.

5. Meghadūta I. 25.

I cannot agree with Prof. Macdonell when he says: "There were no special theatres in the Indian Middle Ages, and plays seem to have been performed in the concert-room [ *saṅgītaśālā* ] of royal palaces."<sup>1</sup> The above remark of the learned professor seems to be based on a superficial study of the problem and on insufficient data.

---

1. Macdonell: "A History of Sanskrit Literature," p. 352.

# CHAPTER IV

## SCENIC REPRESENTATION

### A. The Curtain

In the scenic representation the curtain plays an important part. The word *yavanikā* or *javanikā* occurs in the *Nāṭyaśāstra* in connection with the arrangement of musical instruments required in the presentation of plays on the stage. In the preliminaries (*Pūrvaraṅga*) for the presentation of Sanskrit plays a great deal of musical practice is done: the arrangement of musical instruments, fixing the position of musicians, examining of musical instruments, setting of wind and stringed instruments to vocal music, and the entrance of dancing girls. All these are to be done behind the screen [ i. e. *yavanikā* or *javanikā* ].<sup>1</sup> We have said earlier that musicians sit in the *raṅgaśīrṣa*, between the two doors leading to the *nepathyaḅṛha*. Thus the curtain cannot be behind the *raṅgaśīrṣa* but in front of it. So it appears there is a curtain between the *raṅgaśīrṣa* and the *raṅgaṇṭha*. After the musical instruments are arranged and tuned, the curtain is drawn aside and dances and recitals are given with the playing of musical instruments and a *dhruvā* song in praise of gods is sung.

The *Nāṭyaśāstra* has a phrase from which it is clear that the curtain is drawn aside on two sides and not pulled up by pulleys after the *dhruvā* song. After the curtains are drawn aside the actors, who are instrumental in bringing about

---

1. NS—KM, KSS and GOS V, 11-21.

the sentiments, enter the stage.<sup>1</sup> This indicates that when the curtain which between the *raṅgapīṭha* and the *raṅgaśīrṣa* is drawn aside, musicians become visible to the audience. In the *Kuṭṭanimata* which refers to the performance of the *Ratnāvalī* the following occurs: The king with *vidūṣaka* is on the *raṅgapīṭha*. Two maids enter and dance for a while, deliver a message to the queen and go behind the *javanikā*. Then the queen enters with her maid after the *tiraskariṇī* [ curtain ] is drawn aside.<sup>2</sup> Here the word *apanītā* is quite clearly mentioned in the text and it proves that the curtain is drawn aside according to the requirement of the stage. But in no case can it be actually removed.

Abhinavagupta says that the *yavanikā* is hung between the *raṅgapīṭha* and the *raṅgaśīrṣa*.<sup>3</sup> With the help of this curtain also phrases such as *apaṭikṣepeṇa*<sup>4</sup> [ with a toss of the curtain ] can be explained. The common view is that the curtain is parted in the middle. Dr. S. K. De does not agree with this view and takes the stage direction for hurried entrance *apaṭikṣepeṇa praviśati* in the sense of 'enters without a toss of the curtain.'<sup>5</sup> But the real sense of this phrase is lost if we accept Dr. De's view. Mankad<sup>6</sup> opines that the character of parting the curtain from the middle given by European scholars to *paṭi* in explaining stage direction *apaṭikṣepeṇa* has no ground. But this statement seems not to be correct.

Our view-point becomes clear when the stage directions *nepathye* and *apaṭikṣepeṇa* so often found in Sanskrit dramas, are explained in connection with each other? In the second act of the *Mṛcchakaṭika* [ Māthura is shouting from behind the scenes ] Samvāha enters with a toss of the curtain in a

---

1. NS—KM XII. 2b-3a; KSS XIII. 3; GOS XII. 3.

2. Kuṭṭanimata—KM 886-887, P. 107; Bombay 909-910, PP. 358-359.

3. Abh. Bh. I, P. 212; II, P. 130.

4. Halāyudha 2. 154. He gives *apaṭi* as a synonym of *paṭi* or *javanikā*.

5. Dr. S. K. De's article on "The curtain in Ancient Indian theatre" Bhāratiya Vidyā Volume IX. 1948.

6. Mankad's pamphlet 'Ancient Indian Theatre', p. 18.



flurry. In the same act Karnaṇapūraka enters in high glee, dressed in gorgeous dress with a toss of the curtain. In act VI Āryaka enters with a toss of the curtain excited and with a chain on one leg he walks about. In act VIII the monk enters with a toss of the curtain. In act X the executors say: [Turning towards the *nepathyagrha*] This way, this way, Sir, come here, child, come [enters Maitreya with Rohasena].<sup>1</sup>

Voices are heard behind the scenes. In the *Pratijñāyau-gandharāyaṇa* the soldier says: "The page has gone to the tavern and is drinking liquor. Well, you may go. [Stepping round]. Here is the liquor shop. I will just call him. He, page ! page !" [voice behind the scene]. "Now who is calling me on the high road, page, page ?" Soldier: "Here comes the page, his eyes as red as china roses, full of liquor laughing aloud and drunk. I won't stand in his way." [Stands aside]. [Enters the page as described].<sup>2</sup>

In the *Avimāraka* the stage-manager looks towards the dressing room and in the same drama, the nurse speaks to a maid behind the scenes.<sup>3</sup>

From these examples, it is clear that there is a curtain between the *raṅgaśīrṣa* and the *raṅgapīṭha* as without it *apaṭikṣeṇa* cannot be explained. As there is a wall between the *raṅgaśīrṣa* and the *nepathyagrha*, it is not easy for a nurse to talk to a maid. So it is quite possible that the maid is in the *raṅgaśīrṣa* behind the curtain and not in the *nepathyagrha*. Uproar and the voice of gods which are made only in the green room can be heard distinctly by spectators in the auditorium. The purpose of the *nepathyagrha*, *raṅgaśīrṣa* and *raṅgapīṭha* has to be very clearly understood. It has been seen in chapter III that the *nepathyagrha* was meant for the make-up and for the representation of uproars, and the *raṅgaśīrṣa* for musicians and prompters, as also for afford-

1. Mṛch II. PP. 46, and 62; VI. P. 142; VIII. P. 190; X. P. 227.

2. Pra. Y. IV. Prose. PP. 94-95.

3. Avimāraka Prose I. PP. 109-110; III. PP 137-138.

ing rest to actors who had done their part or were to appear on the stage very soon. Whenever the orchestra is required, the curtain is drawn aside and music is on; whenever ordinary scenes go on, the curtain is down. The actual action of the drama takes place on the stage [ *raṅgapīṭha* ].

The ancient Indian theatre, it appears, had no drop-curtain. This can be explained from the peculiar ending of Sanskrit dramas. Sanskrit dramas never ended abruptly as is often the case in modern dramas. The acts, in all Sanskrit dramas, end usually with some description of the time of the day or with some other quiet suggestion to the characters on the stage to make for their exit. This peculiar termination of dramas is due to the absence of the drop-curtain.

Let us examine the *Vikramorvaśīya* from this point of view. At the end of act I the king looks up in the direction of Urvaśī and describes her in the following words: 'This celestial damsel, while flying into the sky, violently tears away my heart, as the female swan, before soaring into the sky, draws off a film from a lotus stalk the tip of which has been already cut off.' At the end of act II, the king, looking up, describes the time which is past midday as follows: 'Tired of the heat the peacock sits in the cool basin round the root of a tree; the bee, having forced open the flower-buds of *karṇikāra*, lies therein; the duck, leaving the hot weather, resorts to the lotus-plant growing on the brink, and the encaged parrot in the pleasure-house, being exhausted, calls for water'. At the end of act III the king makes a request to Urvaśī: 'Formerly, when I had not achieved my object, the night seemed to me to increase a hundredfold; if it increases similarly now when I am in your company, I shall be blessed.' At the end of act IV, on a question by Urvaśī as to how he desires to go, the king says: 'Oh, you gifted with a sportive gait, bear me home on a new cloud made into a balloon, with streamers in the form of flashes of lightning and beautified by

fresh painting in the form of the rainbow.' At the end of act V, there is the benedictory stanza: 'May there be always, for the welfare of the good, a union of the goddesses of wealth and learning who are opposed to each other—a union which is difficult to be found in one place.'<sup>1</sup>

From this analysis it is clear that the acts ended not with any dramatic incident so as to require the fall of the curtain, but with the description of some kind or other. And there is a definite instruction after every act that the actors go out. If there were any drop-curtain, there was no need of the actors leaving the stage; they could as well be on the stage while the curtain came down.

But now how to explain scenes where an actor enters seated or any situation is said to be set on the stage as soon as a new act begins? Let us take scenes from different dramas. In the *Mṛcchakaṭika*, in act II, the scene opens with Vasantasenā, seated, deeply in love, and also Madanikā.

In act IV, a female servant enters. Servant: Madam's mother has told me to go to madam. Here is madam with her gaze fixed on a painting. I would just approach. [She advances a few steps]. The scene opens with Vasantasenā who is in the manner described earlier and Madanikā. In act V Cārudatta enters, seated and full of amorous thoughts.<sup>2</sup> In the drama *Avimāra*, Avimāra enters seated.<sup>3</sup> Such instances can be produced from many other dramas. Instructions such as '*praviśati āsanasthaḥ*' and the examples quoted above help us to arrive at the inference that there was some sort of a curtain which was withdrawn to present the actors to the audience at the appropriate moment, thus pointing towards existence of the drop-curtain. But it may also be quite possible that actors used to come and sit on the stage. It could then be said that an actor 'entered seated.'

S. M. Tagore in his '*The Eight Principal Rasas of the*

---

1. Vik Ending of 1-5 acts pp. 16-17, 50-51, 74-75, 98-99 and 122.

2. Mṛch II, p 42; IV. p 84; V. p. 111.

3. Avimāra II, p. 121.

*Hindus* refers to the drop-curtain. He says: 'The scene which hangs before the audience before the commencement of the play, or which drops in the intervals between the scenes is called *yabanikā*. As in every act and its subdivisions, scenes are changed, so the drop-scene should also change. In classical times two comely girls appeared and removed the two wings of every scene.'<sup>1</sup>

While describing the Jogīmārā and Sītābengā Caves, Bloch<sup>2</sup> refers to certain holes on two sides of the caves and presumes that they had been provided to facilitate the use of curtains.

But there is no reference to the drop-curtain in the *Nāṭyaśāstra* or *Abhinavabhāratī*. On the contrary '*The Eight Principal Rasas of the Hindus*' which hints at the drop-curtain is a modern work and the injunction 'such and such actor enters seated' can be represented without the use of the drop-curtain. Further as Bloch's interpretation of the drop-curtains in the Sītābengā and Jogīmārā caves is not conclusively proved and we have already seen that the ending of acts in Sanskrit dramas does not require any drop-scene, we conclude that no drop-curtain was used in presentation of Sanskrit plays.

The theory of a transverse curtain propounded by Wilson is not supported by facts. He superficially remarks: 'It seems possible, also, that curtains were suspended transversely, so as to divide the stage into different portions, open equally to the audience but screening one set of actors from the other, as if the one were within, and the other outside a house or chamber.'<sup>3</sup>

A. K. Coomaraswamy thinks there was no drop-curtain. He remarks: 'As for the curtain, of course, there were two curtains, neither of them a drop-curtain, but one over each door-way leading from the *nepathyagrha* on to and

---

1. '*The Eight Principal Rasas of the Hindus*' pp. 58-59.

2. Bloch: '*Archaeological Survey of India Report*,' 1903-1904, p. 123.

3. Wilson: '*Select Specimens of the Theatre of the Hindus*' I, LXVIII.

from the stage, just as in the Chinese theatre even today, where anyone who cares may see the actor entering with a toss of the curtain.<sup>1</sup> But it is not clear from where A. K. Coomaraswamy got the idea of the two curtains in Indian plays. Probably this theory of his is based on mere conjecture.

Thus from the above analysis we arrive at the conclusion that the ancient Indian theatre had only one curtain and that it was placed between the *raṅgasīrṣa* and the *raṅgapīṭha*.

Apart from this one curtain there were probably some other minor curtains used to partition the *kakṣyās*. Some scenes must have been screened from the audience by curtains and exposed when necessary, for example, the scenes in the *Abhijñānaśākuntala* such as kanva's garden, the *rājasabhā* of Duṣyanta, the street scene where the fisherman is caught, the scene half-way up in heaven showing Marica's *āśrama*, the king's garden and the king painting the portrait of Śakuntalā. These are different parts of scenes. They must have been kept ready and shown with the help of *kakṣyās* partitioned by minor curtains. But this can only be a probability and we are not sure of such scenic representation in ancient India.

### B. Origin of the Curtain

Now the question arises whether the curtain was imported from outside [i. e. Greece] or it was of Indian origin. Let us consider the terms *yavanikā*, *javanikā* and *yamanikā* to get a correct idea about the curtain of the ancient Indian stage. The Kāvya-mālā edition of the *Nāṭyaśāstra* has the reading *javanikā* while the texts of the Kāśī Sanskrit Series, the Gaekwad Oriental Series and also the *Abhinavabhāratī* have the reading *yavanikā*.<sup>2</sup> The edition of Grosset [1898] has the form *javanikā*, but in one of the passages the reading

1. 'Indian Historical Quarterly' Vol. IX Calcutta 1933, p. 594 article on 'Hindu Theatre' by A. K. Coomaraswamy.

2. NS—KM, KSS and GOS V. 11-12.

is *yavanikā*. The form *yamanikā* is found in some manuscripts of Sanskrit plays and poems. Dr. De has tried to show that *yamanikā*<sup>1</sup> is as much a recognized form of the word for curtain as *javanikā* or *yavanikā*.

According to Apte's dictionary the meaning of *yavanikā* and *javanikā* is the same i. e. 'curtain'.<sup>2</sup> On this point we may note that *javanikā* is the *prākṛta* form of *yavanikā*.<sup>3</sup> Let us now take up the word *javanikā* and look to its etymological meaning. *Javana* means going fast and it is derived from the root 'ju' by Bhattoji Dikṣita in his *Siddhāntakaumudī*. Pāṇini has the following *sūtra* 'jucaṅkramyadandramyasṛgrdhijvalaśucalaśapatapadaḥ ju iti sautro dhāturgatau vegeca, javanaḥ'<sup>4</sup> which shows that the word 'javana' was derived from the root *ju*. The feminine form of *javana* is *javanī* or *javanikā*. It may mean a curtain which was to be drawn with force. In the *Amarakoṣa* the meaning of *javanikā* is given as a curtain or *kanāta*, as in the following 'pratisīrā javanikā syāttiraskariṇī ca sā.'<sup>5</sup> As to the word *yavanikā* it can be derived from the root 'yuñ bandhane'<sup>6</sup>, 'yuñ, yunāti, badhnāti āvr̥ṇoti vā anayā iti'<sup>7</sup> i. e. any thing by which something is covered from the sight of the spectators, i. e. curtain. The word *yamanikā*<sup>8</sup> is derived from the root *yam* 'to stop or restrain' signifying a covering or curtain and the word *yamanī*, from which *yamanikā* is directly derived, is traceable

- 
1. Dr. S. K. De's article on "The Curtain in Ancient Indian Theatre." *Bhāratīya Vidyā* Volume IX, 1948.
  2. V. S. Apte 'The Practical Sanskrit English Dictionary'. pp. 450 and 782.
  3. The word *yavanikā* is not included as a synonym of the Curtain by old Indian Lexicographers.
  4. *Siddhāntakaumudī* p. 594; Pāṇini 3-2-150.
  5. *Amarakoṣa* II. 120, p. 152.
  6. *Siddhāntakaumudī* 1480 dhātupāṭha.
  7. Commentary to *Kuṭṭanīmata*, edition by T. M. Tripathi p. 359.
  8. Bohtlingk and Roth summarily dismiss the form *yamanikā* as a scribal mistake for *yavanikā* and Sten Konow take it as merely secondary.

as far back as the *Vājasneyī-Saṁhitā*.<sup>1</sup> Thus as the words *javanikā*, *yavanikā* and *yamanikā* all can be derived to mean curtain it can be asserted that the curtain which was used on the ancient Indian stage had an indigenous origin and growth.

Critics hold that *yavanikā* points to the Greek origin of the curtain as being derived from Ionia or Greek. If the curtain was borrowed from Greece, *yavanikā* could have had no special application to the curtain of the theatre for there was no curtain in the Greek drama. Windisch contends that the curtain was called Greek because it took the place of the painted scenery at the back of the Greek stage. Keith remarks: 'Behind the Indian stage is the painted curtain [ *paṭi*, *apaṭi tiraskarinī*, *pratisīrā* ] to which the name *yavanikā* [ *prākṛta javanikā* ] is given, denoting merely that the material is foreign and forbidding any conclusion as to the Greek origin of the curtain itself or the theatre. Dr. De does not agree with the view of Dr. Keith and says that there is no evidence to support this presumption.<sup>3</sup>

On account of the mention of *yavanas* and *yavanis* and their supposed connection with *yavanikā* it has been put forward that the Sanskrit drama had Greek influence on it. The *Mālavikāgnimitra* speaks of *yavanas* having attacked the army of king Puspamitra when he crossed the Indus.<sup>4</sup> In the *Abhijñānaśākuntala* women *yavana* attendants, who carried bows in their hands, are represented as constituting some of the king's body-guards.<sup>5</sup> Now as to the word *yavana* it is not universally accepted as meaning only Greek. Keith says: 'It applies to anything connected with the Hellenized Persian Empire, Egypt, Syria, Bactria and it, therefore,

---

1. *Vājasneyī-Saṁhitā* 14.22.

2. Keith: 'Sanskrit Drama', pp. 61 and 359.

3. Dr. S. K. De's article on "The Curtain in Ancient Indian Theatre" *Bhāratīya Vidyā*, Volume IX. 1948.

4. *Māl V*, p. 102.

5. *Śāk II*, p. 42.

cannot be rigidly limited to what is Greek. As applied to the curtain it is an adjective, [*paṭi*, *apaṭi*] as foreign, possibly as Levi suggests, Persian tapestry brought to India by Greek ships and merchants.<sup>1</sup> As to the employment of *yavanī* girls in Sanskrit dramas as body-guards of kings, Greek drama offers no parallel. It is probable the *yavanī* women used to draw aside the dissected curtain.

Thus we can assert that the word *yavanikā* which has *javanikā* for its *Prākṛta* form and probably *yamanikā* as its variant was of purely Indian origin. It is however, quite probable that material imported from Greece might have been used to make curtains.

### C Employment of Painting

Painting played a significant role in the secular and religious life of India. The *Viṣṇudharmottara* gives a long account of how the sage Nārāyaṇa in order to put the *apsarās* to shame created the most beautiful nymph Urvāśī by drawing her outline with mango juice.<sup>2</sup> In the above legend the origin of the art of painting is seen in the outlining of a human figure for the purpose of creating a living human form. A similar notion is to be found in the *Svapnavāsavadattā* where king Udayana and princess Vāsavadattā, with whom he had eloped, are united in marriage by their parents by drawing the portraits of the two on a board. Nurse:—"Thus saith the queen: Vāsavadattā has passed away. To me and to Mahāsenā you are as dear as our Gopāla and Pālaka, for from the very first we intended you to be our son-in-law. That is why you were brought to Ujjain. Under the pretext of learning the lute we gave her to you, with no ritual fire as witness. In your impetuosity you carried her off without celebrating the auspicious nuptial rites. So we had portraits painted of you and of Vāsavadattā on a panel, and therewith celebrated the marriage. We send you the portraits and hope they will give you satisfaction."<sup>3</sup> This instance proves that the artist draws from his memory when visualising a portrait.

1. Keith: 'Sanskrit Drama', p. 61; Levi: *le Theatre Indien* I. 348.

2. VD I, CXXIX. 1-19.

3. *Svapnavāsavadattā* VI. prose, pp. 50-51.



The modelling capacity of the outline is also described in the 'Viddhaśālabhañjikā'.<sup>1</sup>

The *Viṣṇudharmottara* holds the rules for painting as valid for sculpture also, which may either be hollow or massive. Hollow figures must have stood, among other places, on the stage, where images of gods, demons, *yakṣas*, elephants, horses, deer and birds made of clay, wood, cloth, leather or iron were placed.<sup>2</sup>

There were various types of paintings—on walls, on boards and on canvas.<sup>3</sup> When a picture is on canvas or board, it is known as *paṭa*. In *Pañcadaśī* we read the principles of painting a picture on *paṭa*. We are told of its four stages: [1] *dhauta*—to be washed, [2] *ghaṭṭita*—rubbed with rice, [3] *lāñchita*—decorated with the help of ink, [4] *rañjita*—painted with colours proper.<sup>4</sup> In the *Āryamañju-Śrīmūla-Kalpa* we get a description of a *paṭa*. A picture [*paṭa*] should be painted on new white cloth, having fringes. It should be two cubits long and one cubit broad. It may be painted on cloth, *ātasya* or the bark of a tree, which must be true and devoid of any string. It should be painted on a cloth which is not silken. Other articles on which pictures can be painted have also been described.<sup>5</sup> Pictures on canvas were sometimes in the shape of rolls, exhibiting continuous representation. Such a roll was spread out by a spy of Cāṇakya before the people in Candanadāsa's house and was exhibited by him with songs in the *Mudrārākṣasa* : 'Spy:—listen, noble sir. Employed by your noble self to note the doings of others, I entered the house of the jeweller-banker Candanadāsa, roaming with this Yama's canvas which cannot excite suspicion. There opening out the canvas I began singing songs.'<sup>6</sup>

1. Viddhaśālabhañjikā I. 33, 35, 36, 39, pp. 28-34. Poona edition 1886.

2. VD III. XLIII. 27b-39.

3. ŚR I. XLVI. 26-34, p. 247.

4. Pañcadaśī VI. 1-3, p. 21.

5. Āryamañju-Śrīmūlakalpa I. p. 131.

6. Mudrārākṣasa I. n. 68.

Wall paintings have been referred to in the *Nāṭyaśāstra*. After white-washing the walls, pictures were painted on them. They were generally of men and women. Nooses of creepers were employed. Incidents from many aspects of life were drawn.<sup>1</sup> Decoration on the stage has been referred to in chapter III.

Let us now analyse some of the important dramas with regard to the technique and details of the art of painting in ancient India. In the *Ratnāvalī*, Sāgarikā enters with a picture board and brush. She is love-sick and is engaged in painting. Susaṅgatā comes and with gentle step stands behind her and sees with joy, "how, now; she has painted our master. Noble, Sāgarikā noble: or rather, how can a royal swan find pleasure except in a tank full of lotuses? Susaṅgatā comes and forcibly takes the board. Susaṅgatā: O friend, who is this that is drawn by you here? Sāgarikā: Friend, god Anaṅga. Susaṅgatā: [ smiling ] Oh, your skill. But how is it then that the picture depicts him alone? So I too will draw and make him have Rati by his side [ takes the brush and pretending to portray Rati, paints Sāgarikā ]."<sup>2</sup> From the above it is quite clear that paintings on board, i. e., *paṭa* with human figures, were prevalent in ancient India.

In the *Mṛcchakaṭīka* Vasantasenā is seen with her gaze fixed on a portrait. The scene actually opens with this incident. "Vasantasenā: Madanikā, is this portrait of the noble Cārudatta faithful to the original? Madanikā: It must be. Vasantasenā: How can you know it? Madanikā: Since Madam's gaze is fastened on it with so much affection. Vasantasenā afterwards says to Madanikā: Just keep this picture in my bedroom, girl, and come quickly with a fan. Madanikā: As you command me, Madam (takes away the picture)."<sup>3</sup>

In act I of the *Mālavikāgnimitra* Vakulāvalikā and Kaudikā describe the circumstances in which the king saw Mālavikā. 'Vakulāvalikā, listen, the queen had gone to the

---

1. NS—KM II. 71b-74a; KSS II, 83 b-86a; GOS II, 87-89.

2. Rat II, PP. 30-33.

3. Mṛch IV. PP. 84, 87.

painting hall and was seeing a picture of the teacher on which the colours were still fresh; in the meantime the king came.

Kaumudikā—What then ?

Vakulāvalikā—Then after the customary salutation, the king sat down on the same seat with the queen, and observing Mālavikā quite close to the painted queen in the midst of her attendants, he asked the queen.' This conversation shows that picture halls and paintings were very much in vogue.

Then in act IV there is the portrait of the king, which Vakulāvalikā shows to Mālavikā.<sup>1</sup>

In act VI of the *Abhijñānaśākuntala* there is a portrait of Śakuntalā on a board drawn by the king himself. Its graceful and lovely presentation is described here. 'Vidūṣaka—Excellent, my friend. The depiction of natural state has become charming by reason of that sweet and beautiful attitude. My eye stumbles, as it were, in the prominences and depressions in the picture. I believe that out of the three ladies painted in the portrait she—who with the end of her hair dropping flowers by reason of the fillet being slackened, with a face on which drops have collected, and with the arms greatly drooping, has been drawn as if a little tired, by the side of the mango-tree, with its new grown leaves fresh with watering—is Śakuntalā. So the other two are her companions. King: you are discerning. In it there is a proof of my passion for her. On the edge of the sketch is seen the black impression of the perspired fingers; and this drop of tear fallen on her cheek is observable by reason of the swelling of the paint.'<sup>2</sup>

In the *Uttararāmacarita* the painter is said to have portrayed the life of Rāmacandra up to Sītā's purification on the wall. Lakṣmaṇa: 'victory to your highness: Sire, that painter has, according to your instructions, portrayed your life on this wall. You can see it.' ( They rise and move about ). 'Sītā: '( marking with attention ) Who are these stationed above in a compact line that seem to praise my lord ?' Lakṣmaṇa: 'These are the well-known Jṛmbhaka missiles with their mysterious

1. Māl P. 5, 72-73.

2. Śāk VI. 14-15 and Prose, PP. 151, 158-159.

charms.' Lakṣmaṇa: 'Here is the account of the events that occurred at Mithilā.' Sītā: 'Oh, here is my lord painted'. Lakṣmaṇa: 'Behold, lady, behold, here is your father with Śatānanda, son of Gotama, the priest of the Janaka family, honouring Vāsiṣṭha and others.' The scenes of Sītā's marriage, departure to the forest from Ayodhya, meeting with Guha at Sṛṅgavera, Bhāgīrathī with flowing waters, penance groves on the bank of mountain brooks, Prasravaṇa at Janasthāna with the river Godāvarī, Pañcavatī, the fight between Jaṭāyu and Rāvaṇa, lake Pampā, and of the countless achievements of Rāma and of the noble monkey and *rākṣasas*, represented on the wall, were lively and full of vigour.<sup>1</sup>

In connection with painting we have analysed the following dramas: the *Svapnavāsavadattā*, the *Mudrārākṣasa*, the *Ratnāvalī*, the *Abhijñānaśākuntala*, the *Uttararāmacarita* and we come to the conclusion that wall paintings, pictures on board and canvas were popular. In the *Ratnāvalī* and the *Abhijñānaśākuntala* pictures on board are found and in the *Mudrārākṣasa* pictures on canvas and in the *Uttararāmacarita* wall paintings are referred to. Many portraits and landscapes painted by artists of the royal and the servant class alike are mentioned in almost all the dramas referred to above.

From the above we can arrive at the following conclusions. It is certain that there was at least one curtain between the *raṅgapīṭha* and the *raṅgaśīrṣa* and possibly there were other minor curtains to partition the *Kakṣyās*. When paintings on canvas were popular curtains could easily be available. The colour of the curtain, according to some authorities, must necessarily be in harmony with the dominant sentiment of the play, in accordance with the classification of sentiments already given, but others permit the use of the red in every case.<sup>2</sup> Then the walls between the *raṅgaśīrṣa* and *nepathyagrha* might have been painted to represent the most interesting scenes of the play. Pillars and ceilings of the theatre might also be painted as we find paintings in the Ajantā caves.

1. URC Prose PP. 15, 17, 18.

2. S. M. Tagore: 'The Eight Principal Rasas of the Hindus', PP. 58-59

### D. Time of Presentation

From the *Nāṭyaśāstra* it is clear that plays were performed in the morning, afternoon and in the first part (*prahara*) of the night and also in the fourth part (*prahara*). That which is pleasing to the ear and which speaks about religion, which is pure or mixed should be represented in the morning. That which is magnificent, full of *satva* qualities and sounds of musical instruments should be represented in the afternoon. That in which the *Kaiśikī* style is employed and in which the erotic sentiment predominates and which is full of vocal and instrumental music should be represented in the first part of the night. That which is full of important events and in which the pathetic sentiment predominates should be represented in the fourth part of the night. Plays were not allowed to be presented at midnight, mid-day and at dinner time.<sup>1</sup> But if the king ordered plays could be staged without restrictions of time and space.

The time of the performance is not in many cases stated, but in a number of plays such as the *Mālatīmādhava*<sup>2</sup> and the *Karṇasundarī*<sup>3</sup> it is found that it is assumed to be the time when the sun is rising. According to Nilakaṇṭha, people avoided to see *naṭas* in the morning.<sup>4</sup> It is clear that people did not like to see plays in the morning at least during his life-time.

In the *Kirātārjunīya-vyāyoga*<sup>5</sup> and in the *Rukmiṇiharaṇa*,<sup>6</sup> the plays are stated to have been presented when the moon is rising. In the former drama the *Sthāpaka* says it is night fall which is essentially beautiful. This also happens in the *Rukmiṇiharaṇa*. The *Harivaṃśa* makes mention of a dramatic treatment ( *nāṭakīṣṭam* ) of the *Rāmāyaṇa* and the *Mahābhārata*

---

1. NS—KM XXVII, 80-84; KSS XXVII, 89-93.

2. MM Prologue P. 4.

3. Karṇasundarī I. 4; PP. 1-2.

4. Mr̥ch X. Commentary of Pṛthvīdhara P. 249.

5. Kirātārjunīya-Vyāyoga I-5: P. 2.

6. Rukmiṇiharaṇa Prologue P. 37.

performed in first part of the night.<sup>1</sup> The *Nāṭakalakṣaṇa-ratnakoṣa* tells us that a play is to be presented when the moon is rising.<sup>2</sup>

In most cases dramatic performances were held generally in the afternoon and they lasted for nearly four or five hours. While in a Greek theatre often three tragedies and a comedy were enacted the same day, in India one single, well sustained and systematically evolved drama was presented. Indian seasons allowed the necessary light throughout the day, for as a rule few plays were produced during the rainy season. The use of torches on the stage was not unknown. In the *Mṛcchakaṭīka* Cārudatta tells Maitreya: 'So let it be. I shall accompany her myself. Well, then let the torches be lighted so that we may go with confidence on the king's path.'<sup>3</sup>

From the testimony of the *Nāṭyaśāstra* and plays in general it is evident that plays were performed in day time and when the moon was rising. While scenic effect could be very easily produced at night, it is interesting to find how such effect was produced by day also. From a study of the occasions for the performance of the drama in Chapter II we found that plays were generally enacted at annual fairs in temples, at the pleasure of the poet's patron and at festivals rural or urban, public or private. On these occasions, except the dramas which were played at the pleasure of the poet's patron or king etc., there must have been holidays when people used to gather to witness plays by day. Reflections of mirrors might have been used just as lights were used at night. Sanskrit dramas had critical audience as is clear from many preludes of dramas. Bhavabhūti and Kālidāsa must have been understood by the learned people. Imagination played a great part in Sanskrit plays as in Shakespearian plays. The miracle of fire shown by the juggler in the *Ratnāvalī* must have been left to the imagination of the audience.<sup>4</sup>

---

1. Harivaṁśa II, XCIII.

2. NLR 2186; P. 91.

3. Mṛch I. Prose; P. 40.

4. Rat IV. PP. 103-106.

There was a time-limit for a play. The Sanskrit play was to be finished in a fixed time. From the testimony of the *Nāṭyaśāstra*, we understand that a play was judged by a critic ( *prāśnika* ) from the point of view of the accuracy of timing ( *nāḍikāsiddhi* ) since the time when the *jarjara* was placed in a dramatic performance by the manager ( *sūtradhāra* ).<sup>1</sup>

---

1. NS—KM XXVII. 39; KSS XXVII. 40.

## CHAPTER V

# PARAPHERNALIA

### A. Significance of Āhāryābhinaya

( *Costumes and Make-up* )

The Sanskrit word *abhinaya* is made up of the prefix *abhi*, towards, and the root *ni*, to carry. Thus it means 'representing' or 'carrying' a play to the spectators. *Abhinaya* is known to be fourfold: *āhārya* [dresses and make-up] *āṅgika* [gestures], *vācika* [words] and *sātvika* [temperament].<sup>1</sup> In this chapter we shall deal with *āhāryābhinaya* [costumes and make-up] reserving the other kinds of *abhinaya* for a later treatment.

In ancient India stage outfit and scenic arrangements were not so elaborate as in modern times. Some sort of scenery and stage machinery are referred to by Bharata. Mechanical contrivances, probably a sort of crane and pulley, worked from the sides [*mottavāraṇīs*], seem to have been used on the stage. Bharata carefully notices the process of stage carpentry [*dārukarma*] and speaks of machines [*yantras*] aiding movements to and from the stage. Lattices and windows are described mechanically constructed for the purpose.<sup>2</sup> In the *Mṛcchakaṭika* when Madanikā is sent to bring a fan and when she begins to talk with Śarvilaka, Vasantasenā says: 'Madanikā has tarried long. Where can she be? [She peeps outside through a latticed window]. What? She is standing there talking to a man.'<sup>3</sup>

The presence of several deities seated in aerial vehicles is a noteworthy feature of some of the Sanskrit plays. Now when these celestial characters are actually present on the stage and imitate aerial motions, the direction is precise, viz. 'Thus they act' [*nāṭayanti*]. In act VI of the *Uttararāmacarita* a pair of resplendent Vidyādhara in an aerial vehicle

---

1. NS—KM and KSS VIII 6-9; GOS VIII 7-10; VD III 27. 1.

2. NS—KM II 64-74; KSS II 76-86; GOS II 78-90 a.

3. Mṛch IV. p. 87.



enters the stage.<sup>1</sup> In act VI of the *Abhijñānaśākuntala*, Sānumatī, a nymph, enters the stage in a celestial car to see the doings of the king and remains there practically up to the end of the act.<sup>2</sup>

As to how these actions and vehicles should be represented in the play is all described in *āhāryābhinaya*. In *āhāryābhinaya* are included subjects such as the preparation and use of dresses and ornaments, painting of the persons of men and women, arrangement of hair and depiction of scenes. Writers on dramaturgy have treated these under four heads i.e., *pusta*—model work, *alaṅkāra*—decoration ( ornaments, garlands and dresses ), *aṅgaracanā*—painting the limbs ( colouring, hair and beard ) and *sañjīva*—living creatures ( construction of stage animals ).<sup>3</sup> In *pusta* is described how items are prepared for representing different scenes. In *alaṅkāra* the occasion when a man or a woman should wear a particular kind of ornament or dress is stated. The kind of painting a person should use on his or her body in the representation of a particular character, the kind of hair women should wear, methods of dressing the hair in different countries and use of moustaches—all these are discussed in *aṅgaracanā*. Under *sañjīva* we are told how animate objects other than human beings, should be prepared for the stage if their presence was needed in connection with the performance.

### B. Pusta ( model work )

*Pusta*, according to the dictionary of Monier Williams, means 'binding'.<sup>4</sup> An object prepared after binding different things together is called *pusta*. The *Nāṭyaśāstra* distinguishes three forms of *pusta*: *sandhima* ( joined ), *vyājima* ( indicating ) and *veṣṭita* ( wrapped ).<sup>5</sup> Different articles are joined together with the help of bamboos covered with mat, skin or cloth to make a *sandhima*. Rocks, carriages, chariots, aerial cars, horses and elephants are thus represented on the stage. When objects

1. URC VI. P. 140.

2. Śāk VI. PP. 143-169.

3. NS—KM XXI. 1-4; KSS XXIII. 1-5; VD III. 27. 2-3a.

4. M. W. Dictionary, P. 640.

5. NS—KM XXI. 5-8; KSS XXIII. 6-9.

are made to work by mechanical means the term *vyājima* is used. According to Abhinavagupta things on the stage were made to move by pulling a thread from behind the curtain.<sup>1</sup> For example, if the movement of an aerial car, animals or a chariot is to be shown, it would be done by preparing frames of objects with pieces of bamboo and then by covering them with painted cloth, palm-products(*talīya*), mats(*kaliñja*), *bheṇḍa*, bees-wax, lac and sheets of mica and be pulled from behind the curtain. Certain other things used on the stage were prepared by wrapping cloth only ( *veṣṭita* ) or by movements only, if we read *ceṣṭita* instead of *veṣṭita*.

The 'Avaloka' on the *Daśarūpa* speaks of elephants being made in this way in *Udayanacarita*.<sup>2</sup> In the *Pratijñāyugandharāyaṇa*, Yaugandharāyaṇa says to sālaka: "That, too, is a sign of an intelligent man. Well, a report has reached us that Pradyota intends to hoodwink our king by setting up a blue elephant. I only hope our master's judgment has not already been led astray. But oh, how fearful Pradyota must be of the king of the Vatsas. The inefficiency of the vast army is manifest."<sup>3</sup> To the *vyājima pusta* belongs the earthen toy cart in the *Mṛcchakatika*<sup>4</sup> and the moving chariot in the *Abhijñānaśākuntala*.<sup>5</sup> Puppets could be made to move about or dance by mechanical arrangements. A puppet impersonating Sītā is actually introduced in the *Bālarāmāyaṇa*.<sup>6</sup>

According to Abhinavagupta, when Bharata speaks of his having been instructed by Brahmā to direct the dramatic performance because of his being a sage with a hundred sons, of his having been given an umbrella, crown and throne etc., by different gods, of the appointment of certain divine beings to guard over certain parts of the theatre or certain actors

---

1. Vyājaḥ sūtrasyā karṣādirūpaḥ kṣepastena nirvṛtto vyājimaḥ. Ahh. Bh. XXI. PP. 11-12, ( MSS Saraswati Bhawan Library, Banaras ).

2. Avaloka on DR II. 58a; P. 60.

3. Pra. Y. PP. 58-59.

4. Mṛch, VI. PP. 137, 139.

5. Śāk 1. 6-9 and Prose, PP. 10-13.

6. Bālarāmāyaṇa V. PP. 239, 242-251.

and of the creation of fairies, he simply means to tell the requirements of the stage and the way to manage it.<sup>1</sup>

Here it will not be out of place to describe the seats for characters on the stage, as these are essential for the representation of different beings in a play. Gods, kings and chief queens used to sit on thrones ( lit. lion-seat ). Seats of cane were assigned to ministers, priests and their wives. The commander of the army, crown prince and the wives of the king other than the chief queen occupied seats called *mundāsana* i. e. a chair without arms. Wooden seats were meant for Brāhmaṇas. Woollen seats or carpets ( *Kālīna* ) were used by princes. Women of the household occupied seats of wood or skin. The seats for ascetics were according to the rules of the orders they belonged to. Generally those observing vows, *brahmacārīs* or *ṛṣīs* used to sit on *muṇḍāsana* or cane seat. Other characters used to sit on the ground. These rules for seats were observed among people in general or in the royal court. In one's own house one can take any seat according to one's liking.<sup>2</sup>

Different kinds of weapons were used in the presentation of plays. The *Nāṭyaśāstra* prescribes that weapons and armours should be proportionate to the stature of actors and actresses. Bharata has given the length and breadth of different weapons in *tālas* or *aṅgulas* ( measurements ). *Tāla* is a short span, measured by the thumb and middle finger. Bharata speaks of five varieties of spears: *Prāsa*, *śūla*, *tomara*, *kunta* and *bhiṇḍi*. The handle of the *prāsa* was 20 *aṅgulas* in length and its pointed blade was six *aṅgulas*. The *śūla* and *tomara* were each eight *tālas* in length, while the *kunta* ( javelin ) was of ten *tālas* and the *bhiṇḍi* of 12 *tālas*. Out of these five kinds of spears, the *prāsa*, *śūla* and *tomara* were hurled at the opponent while the *kunta* and *bhiṇḍi* were not. The *śataghñī* and *śakti* were also among weapons thrown at the opponent. Their length is stated to be eight *tālas*. The bow ( *dhanu* ) should be eight

1. NS—KM I. 26-29a; KSS I. 61-64; GOS I. 59b-62; Abh. Bh. PP. 27-28.

2. NS—KM XII. 179-189; KSS XIII. 205-217; GOS XII 214-226.

*tālas* in length and two cubits in breadth at the time of drawing. The *śara* ( arrow ) should be four *tālas* in length. The *gadā* ( mace ) and *vajra* should be of the same size as the *śara*. Bharata has further stated that there are three varieties of swords. Of these, the *asi* was 40 *aṅgulas* in length, the *Kaṁpana* made of thin pointed '*pattara*' 20 *aṅgulas* and one '*śabala*', the smallest, 16 *aṅgulas*. The '*Kheṭaka*', a kind of shield, is 30 *aṅgulas*. The *cakra* ( disc ) should be 12 *aṅgulas* and the *paṭṭisa* is of the same size as the *prāsa*. The *daṇḍa* should be 20 *aṅgulas*. The *Kaṇaya* should be made of bamboos. The *carma* ( shield ) is 16 *aṅgulas* and is for use by both hands. The *jarjara* should be made of wooden logs with knots, and the *chatra* ( umbrellas ), *cāmara* ( chowris ), *dhvaja* ( banner-staffs ), *bhṛṅgāra* ( water-jars ) should be of the same size as those made for ordinary use. The weapons must not be made of hard or heavy materials such as stone or iron, but of stiff blades of grass, bamboos, lac, skin, cloth and earth. Gestures could very well serve the purpose of hard blows and cuts. The *Nāṭyaśāstra* prescribes that no missile should be released on the stage and no weapon should pierce or strike any one. They are to be used only to make a gesture of an attack and should simply touch a spot.<sup>1</sup> The lightness of weapons made them convenient for being taken from one court theatre to another by a troupe. The basic conception was to create an illusion rather than to represent real things. Various kinds of weapons described in Sanskrit dramas can easily be represented by means of bamboos covered with cloth according to the shape and size of the weapon.

Statues as those used in the *Pratimānāṭaka*<sup>2</sup> and *Viṇā-ghoṣavatī* in the *Pratijñāyugandharāyaṇa*<sup>3</sup> could be made of earth and wood and lac. Extensive use is made of lac to effect colourful representations. In the *Bālacarita*, the discus, bow, club, conch and sword have been given human form.<sup>4</sup> Actors personat-

1. NS—KM XXI. 130b-139; 170-180; KSS XXIII. 154-163, 194-203, 212-214a.

2. *Pratimānāṭaka* III. P. 277.

3. Pra. Y. I. PP. 63-64.

4. *Bālacarita* I. P. 522 and V. PP. 550-551.

ing the five weapons must have appeared on the stage adorned with different masks.

### B. *Alaṅkāra* ( Decoration )

The second kind of *āhāryābhinaya* is *alaṅkāra* i. e. decoration of persons appearing on the stage. There are three kinds of *alaṅkāra* (decoration): [1] ornaments made of coral, diamond, silver and gold; [2] garlands made out of different kinds of flowers and wreathes and [3] costumes.<sup>1</sup> These are differently used in different parts of the body.

Kings and women of distinction freely used ornaments of all sorts for the head, ear, nose, neck, waist, wrist and ankle. They were not, however, genuine and were made of copper, mica or wax, sparkling from a distance and presenting the effect of verisimilitude. The *Nāṭyaśāstra* describes the ornaments of men and women according to the country and caste and in due consideration of place and time. It has prescribed four kinds of ornaments according to the method of wearing them. They are : *āvedhya*, *bandhanīya*, *prakṣepya* and *āropya*. *Āvedhya* includes the *kuṇḍala* [ ear-rings ] and other ornaments for the ear which are fixed in holes pierced in the skin. *Bandhanīya* includes *aṅgada* [ arm-band ] and girdles and *prakṣepya* includes *nūpura* [ anklets ] and such other ornaments. *Āropya* refers to *hemasūtra* [ gold chains ] and necklaces that are to be worn round the neck.<sup>2</sup>

Bharata prescribes the following ornaments for men: *cūḍāmaṇi* [ crest-jewel ] and *mukuta* [ crown ] for the head; *Knṇḍala* [ ear-ring ], *mocaka* [ ear-pendant ] and *kīla* [ ear-top ] for the ear; *muktāvalī*, [ pearl necklace ], *harsaka* [ a snake-shaped ornament ] and *sūtra* [ gold thread ] for the neck; *vaṭikā* and *aṅgulimudrā* [ finger-ring ] for the fingers; *hastavī* and the *valaya* [ bangle ] for the fore-arm; *rucika* [ bracelet ] and *uccitika* for the wrist; *Keyūra* [ armlet ] and *aṅgada* [ arm-band ] for the upper arm; *trisara* [ three-stringed necklace ] and *hāra* [ necklace ] for the neck and chest; *tarala* and *sūtraka*

1. NS—KM XXI. 9; KSS XXIII. 10; VD III. 27. 5b-7a.

2. NS—KM XXI. 11-13; KSS XXIII. 12-14.

[ golden thread ] for the waist; and suspended jewelled necklaces and flower-garlands for the entire body.<sup>1</sup>

Ornaments for women are also described by Bharata. Women were *pādapātra* on the *janghā* [ shanks ]; *aṅgulīyaka* [ toe-rings ] on the toes and *tilaka* on the big toes. *Nūpura*, *kinṅiṇī*, *ratnajāla* [ jewel-net ] and ringing *kaṭaka* ornaments are worn round the ankle. An additional decoration of the feet will be the lac-dye applied on them in various patterns to impart to them the natural colour of Aśoka blossoms. Ornaments named *kañcī* with a net of pearls, *mekhalā*, *raśanā* and *kalāpa* are worn round the waist. There is only one string in *kañcī*, eight strings in *mekhalā*, 16 in *raśanā* and 25 in *kalāpa*. *Hāras* were found to be of 8, 16, 32, 64, 100 strings. Women used to wear *hāraṣ* of different jewels on their bosom and round the neck. They are: *muktāvalī* [ pearl-necklace ], *vyālapaṅkti* [ snake-group ], *ratnamālikā* [ jewel-string ], *ratnāvalī* [ jewel-necklace ] and *sūtraka* [ neck-chain ]. Different kinds of ornaments mixed with jewels were worn by ladies on the bosom or the back. On the fingers they used to wear rings. *Śaṅkakalāpī* [ *hastidanti cuḍiyān* ], *kaṭaka*, *patrapūraka*, *kharjura*, *aṅśopitika* ornaments were worn by women on the wrists. *Aṅgada* [ arm-band ] and *valaya* [ bangle ] were used on the upper arm. The *varjura* and the *svecchitika* are ornaments of the fore-arm. *Tilaka* and *patralekhā* adorned their temples. *Karṇikā*, *karṇavalaya*, *karṇamudrā* entwining the ear, *dantapatra* set with jewels, *karṇapūra* and *karṇotkīlaka* [ ear-top ] were prescribed for the ears. Bunches of flowers tied to the hair dangled above their eyebrows. They used *śikhāpāśa*, *śikhājāla*, *khaṇḍapātra*, *cūḍāmaṇi* [ crest jewel ], *makarikā*, *muktājāla* [ pearl-net ], *gavākṣa* and *śīrṣajāla* [ hair-net ] as ornaments for the head. Bharata has not mentioned any ornament for the nose. It appears the reference to such ornaments is lost or ornaments for the nose came into vogue in later times. Ornaments are to be worn according to emotions and sentiments and having a consideration

of tradition, measurements of the wearer and physical form.<sup>1</sup>

The *Abhinayadarpaṇa* says bells should be made of bronze, copper or silver; they should be sweet in tone, well-shaped, dainty and tied with an indigo string with a knot between each pair of bells. Dancers should have 100 or 200 bells on each foot, or 100 for the right foot and 200 for the left.<sup>2</sup>

The use of some of these ornaments is referred to in Sanskrit dramas. For instance in the *Svapnavāsavadattā*, *karnacūlikā*, an ear ornament,<sup>3</sup> and in the *Ratnāvalī*, *nūpura*, anklets, *kiṅkiṇī-cakravāla* and *kalaka* are mentioned.<sup>4</sup>

Various sets of ornaments are prescribed for various roles. *Vidyādhari*s use pearl-studded *śikhāpuṭas* and *śikhaṇḍas*. *Yakṣis* and *apsaras* wear ornaments studded with gems. *Yakṣis* use only one *śikhā* [ top-knot ]. *Nāgis* use ornaments of the type usually worn by the divine women and have creeper of pearls and gems with points. The dresses of *siddha* women are decorated with pearls and emeralds. *Padmamaṇi* is the ornament for *gandharvis*. Ornaments for *rakṣasīs* have *indranīlamaṇi*. *Vaidūrya* and pearls go to make up the jewellery of goddesses. Dresses adorned with flowers, jewels and ornamented with *vaidūrya* are worn by monkey women of divine origin. Women belonging to the south use *kumbhīpadaka* and *vartalāṭika*. The ornaments of prostitutes vary according to their country. In *vipralambha sṅgāra* women wear white dress only and do not use any ornaments.<sup>5</sup>

Over-ornamentation on the stage is discouraged. Gold ornaments are disallowed but ornaments of lac or mica are commended. If an actor or actress is loaded with heavy ornaments he or she is liable to be exhausted. The wearers often get fatigued and may even swoon. Instead of solid gold ornaments those filled with lac and not overloaded with

---

1. NS—KM XXI, 19b-35; KSS XXIII, 21b-43.

2. AD 29-30.

3. *Svapnavāsavadattā* P. 13.

4. Rat. I, 16; II. 2 and Prose P. 45.

5. NS—KM XXI, 41-55; KSS XXIII, 49-72a.

jewels are recommended. Gods and men in general are to use ornaments according to the country and circumstances.<sup>1</sup>

*Mukūṭas* [ crowns ] are included among ornaments as they are prepared with gold and jewels. They come under the category of *pratiṣīra* [ masks ] which are to be used for gods and men according to their habitation, birth and age. *Mukūṭas* are of three kinds: *Kirīṭī*, *mastakī* and *pārśvamaulī* [or *pārśvagata*]. The *Kirīṭī mukūṭa* is the best among the *mukūṭas*. It is fitted to the head like a high—levelled cap. It is made of gold and studded with jewels. The *mastakī mukūṭa* is not as high as the *Kirīṭī mukūṭa* but is enough to cover the head. It may also be made of gold and studded with jewels. The *pārśvamaulī mukūṭa* is only as high as the forehead. It does not cover the whole head and is also called 'ardhamukūṭa'. It is made of gold. Kings usually wear crowns of the *mastakī* type. It is prescribed that gods should wear the *kirīṭī*, *mastakī* and *pārśvamaulī* crowns according to their status and age. Generals, crown-princes and writers should wear *pārśvamaulī mukūṭas*. Gods in general, gandharvas, pannagas, rākṣasas and sāmantas are to use *pārśvamaulī mukūṭas*. For vidyādhara, siddhas, cāraṇas, *mukūṭas* which could be tied to the hair are prescribed. Ministers, those in charge of harems, merchants and priests are to use *mukūṭas* covered by the foldings of the turbans [ *sāfā* ]. The *Nāṭyaśāstra* further prescribes that *mukūṭas* to be used on the stage should not be made of gold and jewels, for if they are heavy, actors will perspire, be overwhelmed and swoon. Copper-plates should, therefore, be used in making *mukūṭas*.<sup>2</sup>

It will not be out of place here if we describe briefly how openings in the *paṭī* for the mask, on which various forms of crowns are set, were made. The *paṭī* is to measure 32 *aṅgulas* or can have any measurement according to need and be prepared by using *bilva* paste on cloth. Masks should be made with ashes or husks of paddy being mixed with *bilva*-paste or some loose form of it. After getting the *paṭī* dried up holes

1. NS—KM XXI, 36-40; KSS XXIII, 44-48.

2. NS—KM XXI, 115-123, 181-187 a; KSS XXIII, 131b-140, 204-210; VD III, 27; 33-37a.



should be pierced into it. An opening six *aṅgulas* long and an *aṅgula* wide should be made for the forehead; another opening two *aṅgulas* long and one and a half *aṅgula* wide for the cheeks, two openings each three *aṅgulas* long for the ears and mouth and one of 12 *aṅgulas* for the neck.<sup>1</sup>

Ornamentation through garlands is the second kind of *alaṅkāra*. Bharata has named five ways of preparing garlands: *veṣṭita*, *vitata*, *saṅghātya*, *tepita* and *pralāmbita*.<sup>2</sup> He has not, however, given any details. The *Abhinavabhāratī* gives details about the varieties of the garland. The *veṣṭita* garland is that in which bunches are prepared by folding together green grass, leaves and flowers. Flowers are woven into garlands to make a *vitata*. The *saṅghātya* is that in which flowers are placed in a row and their stems tied with a thread in such a way that they are not visible. In the *tepita*, bunches of flowers are taken separately and a garland is prepared after tying each of them with a thread. The *pralāmbita* is a single long garland.<sup>3</sup> The stage and persons appearing on it are to be adorned with any of these garlands as needed by the situation.

Dress for the characters on the stage is the third item in *alaṅkāra*. There was a conventional stage costume prescribed and it was in keeping with the dress in ordinary life. The costume and appearance of the *naṭa* help him in his work. Dress reveals the sex and race, sect or class, social or other position of the character represented. Bharata has mentioned three kinds of dress : *suddha* [undyed or white], *vicitra* [variegated] and *malina* [dirty]. Ascetics wear garments of rags or bark; those in charge of the harem reddish [ *kaṣāya* ] jackets; warriors gay garments with weapons. *Ābhīrā* maidens wear dark blue clothes; Vidyā-

1. NS—KSS XXIII, 176-186.

2. NS—KM XXI, 10; KSS XXIII, 11 and repeated in 114.

3. Veṣṭitaṁ tṛṇaveṣṭanayābhimataṁ bahumālāveṣṭanakṛtaṁ ca vāvī-tatyāveṣṭitanyonyaśliṣṭamālāsamūhātmakam vastradhārābhāvenom̐bhitaṁ saṅghātyaṁ vṛttaṁ vāsyā cchidrāntaṁ prakṣiptasūtraṁ bahupuṣpagucch-om̐bhitaṁ vāgrandhibhitṛṇmitaṁ vā prālāmbitaṁ iti jālādiparyatavyā-rākaṁ.

( MSS. Saraswati Bhawan Library, Banaras ) Abh. Bh. XXI, P. 12,

dharis white clothes; demon women dark clothes; divine beings blue clothes. Dirty clothes indicate madness, distraction, misery or a journey. A woman whose husband has gone out also wears dirty clothes. Uncoloured or white garb is used for one engaged in worship or solemn religious service or one who is a trader [ *prāpaṇika* ]. Gods, *dānavas*, *gandharvas*, *uragas*, *yakṣas* and *rākṣasas* as well as lovers and kings normally wear gay, variegated clothes. But the costumes of the kings should be white when due to ominous appearance of any star [ *nakṣatrotpāta* ] they are engaged in any propitiatory rite. Costumes and decorations of the sages, the Jain [ *nirgrantha* ] and the Buddhist [ *śākhya* ] monks, the Tridaṇḍis and Brāhmaṇas well-versed in the Vedas [ *śrotriya* ] should be made according to the traditions of the order and respective society. Generally the dress of men and women varied according to their age and status.<sup>1</sup>

#### D. Aṅgaracanā [ Painting of the limbs ]

*Aṅgaracanā* is the third aspect of *āhāryābhinaya*. It includes dyeing of the limbs of persons appearing on the stage and their style of dressing the hair and beard.<sup>2</sup>

A keen appreciation of colours is a marked feature of the oriental play, for in the representation of great legendary heroes, divinities and mythical beings, the elements of place, time, age, rank and profession were never lost sight of. As regards painting, the *Viṣṇudharmottara* says the primary colours are of five kinds : white, yellow, black, blue and myrobalan colours.<sup>3</sup> But Bharata in the *Nāṭyaśāstra* speaks only of four primary colours: white [ *sita* ], blue [ *nīla* ], yellow [ *pīta* ] and red [ *rakta* ]. It is for the artist to mix these

1. NS—KM XXI, 100 b-114; KSS XXIII, 116-131a.

2. Keśaracanādirāsamantādhriyate poṣyate kāntiryena tadābharaṇaṁ śikhāvyālādikṣirakarma pulakādiyojanāparicchedaḥ vicitravastuyogaḥ etadveṣādīpralāmbhena kartavyādvijā ca kravyaṁ deśo anantyādiḥ avasthāraśīkādyaṣṭatreti puruṣeṣvevāṅganānāṁ rūpaparivartanasampādanāt-makaṁ varṇavartanā kartavyā nāstrīpātreṣviti yāvat.

(MSS. Saraswati Bhawan Library, Banaras) Abh Bh. XXI P. 13.

3. VD. III, 27, 7b-26.

primary colours. The colouring of things witnessed, says the *Viṣṇudharmottara*, should be true to nature. Great emphasis is laid on the thousand-fold mixture of colours left to the imagination of the artist, and on the light and dark shade of every tone. The range of colours must have been wide enough to show in as subtle a manner as possible the local colour of objects.

According to the *Nāṭyaśāstra* there are four fundamental colours: white, blue, red and yellow—from which others are developed. For instance, *pāṇḍuvarṇa* is developed by mixing white and blue; *Kapota-varṇa* by mixing white and blue; *padma-varṇa* by mixing white and red; *harita* by mixing yellow and blue; *Kaśāya* by mixing blue and red; *gaura* by mixing red and yellow. When different colours are to be developed by mixing three or more primary colours, then the strong colour should be taken in one part and the weak colours in two parts each. But when the strong colour is blue, then one part of blue and three parts of other colours should be taken. As blue is very powerful, its dominance would be noticeable in the mixture. After carefully preparing different colours and keeping in view the age, country and caste of the character, the paint should be employed in such a way that the character, whom the *naṭa* represents, should seem natural.<sup>1</sup>

Different colours are suitable for kings of different regions. They are to be either painted lotus colour [ *padma-varṇa* ], or reddish yellow [ *gaura* ] or dark blue [ *śyāma* ]. The sages should always be given the colour of plum [ *vaḍara* ]. Gay persons are to use reddish yellow [ *gaura* ]. Kirātas, Barbaras, Āndhras, Draviḍas, the people of Kāśī and Kosala, Pulindas and people of the Deccan are to be coloured brown [ *asita* ]. The Śakas, Yavanas, Pallavas, Bāhlikas and people of the North are generally to be reddish yellow [ *gaura* ]. Pañcālas, Śūrasenas, Māgadhas, Uḍhras, Aṅgas, Vaṅgas and Kaliṅgas are coloured dark blue [ *śyāma* ] as also Vaiśyas and Śūdras in general. Brāhmaṇas and Kṣatriyas are to be reddish

---

1. NS—KM XXI. 57-69a; KSS XXIII. 73b-84a.

[ *rakta* ] and Vaiśyas and Śūdras dark blue [ *śyāma* ]. Gods, Yakṣas and Apsaras are to be painted reddish yellow [ *gaura* ]; Rudra, Arka [ sun ], Druhiṇa [ Brahman ] and Skanda are to have the colour of gold. Soma, Bṛhaspati, Śukra, Varuṇa, clusters of stars, ocean, Himālaya, the Ganges when personified are to be painted white [ *śveta* ] and Aṅgāraka red [ *rakta* ]. Buddha and fire are to be painted yellow [ *pīta* ]. Nara, Nārāyaṇa, Somanāga, Vāsuki, the *daityas*, *dānavas*, *rākṣasas*, *guhnyakas* and *piśācas*, water and the sky are to be painted dark blue [ *śyāma* ]. The sick and evil-doers, those who are oppressed by evil stars or have taken shelter in penance and all family men engaged in toilsome work should be made brown [ *asita* ]. Thus mixtures of paints appropriate to several roles are suggested for people belonging to different provinces, professions and grades of society.<sup>1</sup>

The dress of actors is carefully regulated especially as regards colour which evidently was regarded as an important item in the matter of sentiments. Each *rasa* had to be painted in its expressive colour. The erotic [ *śṛṅgāra* ] was of dark blue [ *śyāma* ], the comic [ *hāṣya* ] white [ *sita* ], the pathetic [ *Karuṇa* ] ash-coloured [ *Kapota* ], the furious [ *raudra* ] red [ *rakta* ], the heroic [ *vīra* ] reddish yellow [ *gaura* ], the terrific [ *bhayānaka* ] black [ *Kṛṣṇa* ], the marvellous [ *adbhuta* ] yellow [ *pīta* ] and the repulsive [ *vibhatsa* ] blue [ *nīla* ].<sup>2</sup>

Dressing of hair is another aspect of *aṅgaracanā*. Elaborate instructions on the subject of *keśaracanā* are laid down by the *Nāṭyaśāstra* for different characters. Persons playing the role of ascetic girls are to wear only one braid [ *veṇī* ] of hair on their head. Maidens of Avantī and Gauḍa wear ringlets. The latter have the *śikhāpāśa* and the *veṇī* [ braid ]. Women of the North tie their hair high on the head. Otherwise the plaits are usual. Married women, officers of the king and men of foppish nature should have curly hair. The young women of the Ābhīras put on two braids on their head,

1. NS—KM XXI. 69b-92a; KSS XXIII. 84b-105; ŚR I. XLVI. 134-142; PP. 256-257.

2. NS—KM VI. 42-43; KSS VI. 42-43; GOS VI. 47-48.

which are covered with a piece of deep blue cloth. *Vidyādhariś*, *Takṣiś*, *Apsaras* and *Nāgiś* wear pearls and jewels. *Vidyādhariś* tie up their hair in the form of a knot at the top, decorated with strings of many pearls, while *Takṣiś* are to wear simple *śikhā*. The *nāgiś* are at once recognizable by the snake's hoods over their heads.<sup>1</sup>

*Piśācas*, mad men, *bhūtas*, ascetics and those who have not fulfilled their vows leave their hair loose. Buddhist monks [ *śākya* ], experts in *Vedic* studies [ *śrotriya* ], Jain monks [ *nirgrantha* ] and other ascetics are to have their heads shaven clean or should have curly or long hair loosely hanging down. Boys have three tufts and so also servants, if their hair is not cut short. The *Vidūṣaka* [ jester ] is bald or with the *kākapada* [ crow's foot ].<sup>2</sup>

In the *Raghuvamśa*, Kālidāsa describes the *alaka* of Indumatī as having ringlets.<sup>3</sup> The three kinds of arrangement of hair in the *Meghadūta* are named as *alaka* [ spiral or grizzled locks ], *śimanta* [ hair separated in the middle by a straight line ] and *cūḍāpāśa* [ locks tied at the back ].<sup>4</sup>

Beards come under the scope of *aṅgaracanā*. After painting the face and other limbs one should provide beards to persons according to their habitation, activity and age. Four kinds of beards are prescribed by the *Nāṭyaśāstra*. They may be shaven clean [ *śuddha* ], dark blue [ *śyāma* ], carefully trimmed [ *vicitra* ] and bushy [ *romaśa* ]. Some shave their beards and moustaches clean and this is called *śuddha śmaśru*. Some do not take care to have them clean and allow them to grow. This is called *romaśa śmaśru* [ bushy ]. Those usually shave themselves but do not get time to do so owing to some work are stated as having *śyāma śmaśru* [ dark blue ]. Fashionable persons get their beard and moustaches trimmed, and they are called *vicitra* [ carefully trimmed ].

---

1. NS—KSS XXIII. 53-56, 64-68, 71a.

2. NS—KM XXI. 124-127; KSS XXIII. 141-148, VD III. 27, 37b-43.

3. *Raghuvamśa* VIII. 53.

4. *Meghadūta* II, 71 ; see V. S. Agrawala's article in *Nāgarī Pracāriṇī Patrikā Kārtika* 1997 *Samvat*,

Ministers, priests, ascetics and persons who have consecrated themselves for any ritual should be clean shaven ( *śuddha* ). Kings, divine persons, siddhas, vidyādhara, fashionable persons, princes and persons who ordinarily live gayly wear beards carefully trimmed ( *vicitra* ). Persons in misery and those under religious penances and those who are overtaken by misfortunes wear dark blue beards ( *śyāma* ). Sages, ascetics and those engaged in sacrifices lasting a long time have bushy beard ( *romaśa* ).<sup>1</sup>

Dress, ornaments and painting have a vital role in dramas as they are used with deference to the appropriate sentiment intended to be represented according to customs of the provinces and circumstances and after taking into consideration the age and creed of the people.

### E. Sañjīva ( Living Creatures )

*Sañjīva*, the last aspect of *āhāryābhinaya*, signifies the appearance of animals on the stage and deals with the preparation of artificial animal forms for the stage. Animate objects which are generally seen on the earth are of three categories: four-footed, two-footed and with no foot.<sup>2</sup> Lions, tigers, elephants, horses and other wild animals, birds and serpents could be represented on the stage with the help of bamboos, cloth, wool, *Kaliñja*, *bheṇḍa* and *abaraka*. It is quite evident that there were contrivances to represent the ingress and egress of carriages as in the case of the *Mṛcchakaṭika*. The artificial elephant in the *Svapnavāsavadattā*, horse, deer and lion in the *Abhijñānaśākuntala* are all examples of the *sañjīva* type of *āhāryābhinaya*.

Those with many arms, many faces and deformed persons, lions, donkeys, camels, elephants and the like should be prepared with earth, wood, man covered with animal's skin according to the ingenuity of the manager of the theatre. The actor should enter with appropriate feeling, concealing

1. NS—KM XXI. 92 b-99; KSS XXIII. 106-113a; VD III. 27. 27-32.

2. NS—KM XXI. 128-130 a; KSS XXIII. 151b-153; VD III. 27. 44-45a.

his own form with colouring materials and ornaments. Thus the actor should merge himself completely into the character whose role he is playing. If a man represents an animal, he should assume the feeling of that animal and act the role with appropriate voice, gait, gestures and efforts.<sup>1</sup>

We refer to the *Ratnāvalī* to illustrate the *sañjīva* type of *āhāryābhinaya*. In Act II the cage of starling (*sārikā*) is opened by a monkey and there is a hubbub.

‘Enters *Susaṅgatā* with the cage of a starling in her hand.’ The monkey’s plight is described thus:

“( Behind the scenes )—Dragging under him the remaining part of the gold chain round his neck after it had snapped, and with the circle of small bells jingling on account of the wanton movements of the feet, this monkey here, broken loose from his stable, having crossed the gates, is entering the king’s palace, frightening the ladies, with his path followed in haste and confusion by stable keepers.

*Susaṅgatā*—O ! you who are quite at ease, what have you still to do with the picture-board ? Here is the wicked monkey fond of rice and curds. He has opened the cage of the starling and run away. *Medhāvinī* [ the sharp-talented bird ] has flown away. Come then, let us quickly follow her. She has caught the words of our conversation and might utter them before any body.”

Then the bird is described as having flown away. *Vidūṣaka* is repeating the words uttered by the starling.<sup>2</sup>

Thus a monkey and a starling are shown on the stage. A monkey could easily be shown by a man wearing a garment appropriate to a monkey. In some such way a starling also could be presented.

We may therefore assert that though there was no scenery on ancient Indian stage as in modern times, some of the scenes were shown to the audience by preparing the necessary paraphernalia with the help of bamboos, lac, cloth skin, wool, earth, bark of trees, *bheṇḍa* and *abaraka*.

1. NS—KM XXVI. 13b-19a; KSS XXXV. 9-14.

2. Rat II. 2 and prose PP. 29, 36, 41.

## CHAPTER V

# ACCESSORY ARTS

### A. Music and orchestra

*Sanḡita* comprises *gīta* [ vocal music ], *vādyā* [ instrumental music ] and *nartana* [ dancing ] and depends upon rhythm [ *gītaṁ vādyam tathā nṛtyaṁ yatastāle pratiṣṭhitam* ].<sup>1</sup> People generally consider *sanḡita* and *gīta* synonymous but there is a marked difference between the two. While *sanḡita* is *tauryatīka*, the union of song, dance and instrumental music, triple symphony, *gīta* [ vocal music ] deals with only one aspect and is a combination of *svaras* [ tones of the musical scale or gamut ].<sup>2</sup>

According to authorities on the art of music there are also two main distinctions in the theory and practice of *sanḡita*. They are recognized by the names *mārga* [ high style ] and *deśī* [ popular style ]. *Mārga sanḡita* [ gandharva or celestial music ] was employed by the celestial musicians or by sages who knew the theory of sacred music. It is not found in the world at present. *Deśī sanḡita* [ terrestrial music ] varies from country to country according to the tastes of the people of a particular region and is a source of pleasure.<sup>3</sup> The word *mārga* should not be thought to have been derived from the root *mṛg* [ to search for ] but should be traced back to *mārga* [ path ] and then the *mārga* music could accord to the ancient path i. e. classical, as opposed to music that is current in different places [ *deśī* ]. The sage, *Matanḡa* considers that the word *deśī* [ popular ] applies to all earthly music. Sound [ *dhvani* ] goes everywhere in every place and comes to the lips in the form of a 'melodious movement' [ *varṇa* ], giving rise to *deśī* [ popular ] music. Hence it is called *deśī*.<sup>4</sup>

---

1. S. R. V. 2.

2. Kallinātha's commentary on S. R. I, I. 21.

3. S. R. I. 22-24. PP. 6-7; Saḡitapārijāta 20-24, PP. 6-7; Rāgavibodha I. 6-7. PP. 8-9; Saḡitamakarandaḥ I. 3, P. 1.

4. Bṛhaddeśī 2, 11b and 12, PP. 1, 2.

'deśe deśe pravṛttosau dhvanirdeśīti sanjñitah,  
ākrāntam dhvaninā sarvaṁ jagat sthāvarajaṅgamam, dhvanistu  
dvividhaḥ prokto vyaktāvyaktavibhāgataḥ, varṇopalambhanād  
vyakto deśīmukhamupāgataḥ.



The sound of music is called 'nāda', intelligible sound, and is said to result from the union of physical breath with the fire of intellect. All music is based upon relations between sounds. According to the Indian theory, the sounds of music are first perceived as relative pitches or intervals and then from the 22 main intervals ( *śrutis* ) come the seven notes ( *svaras* ) called *śadja*, *ṛṣabha*, *gāndhāra*, *madhyama*, *pañcama*, *dhaivata* and *niṣāda*.<sup>1</sup>

Śārṅgadeva says: "Sound is first heard as an interval, a *śruti*; but the resonance that immediately follows, conveying of itself ( without an external aid ) an expression to the mind of the hearer, is called a *svara*, a musical note."<sup>2</sup> The sound that generates an expression is a *svara*, a note. The word *svara* [ note ] denotes that which shines of itself—from *rājṛ* (to shine) with the word *sva* [self] prefixed to it.<sup>3</sup> The ornaments of the notes consist in *gamakas* [ graces ]. "When in singing, a note rises from its own pitch and moves towards another so that the second sound passes like a shadow over it, it is called a *gamaka* [ grace ]."<sup>4</sup>

Authorities on music refer each note to the sound of some animal. The cry of an animal tends to be always on the same note. The sound produced by the peacock is at its highest pitch called *śadja*. *Ṛṣabha* is said to represent the sound of cātaka bird. *Gāndhāra* is the bleat of the goat. *Madhyama* is the cry of the heron. *Pañcama* is the note of the cuckoo (*kokila*). *Dhaivata* is the croaking of the frog in the rainy season and *niṣāda* the trumpeting of the elephant.<sup>5</sup>

Bharata divides *svaras* [ notes ] into four kinds according to the number of *śrutis* between them and this has remained the accepted division ever since. They are *vādī* [ sonant ],

---

1. Rāgavibodha I, 13-14. PP. 12-13; Saṅgītapārijāta 26-27. P. 9; Saṅgītamakarandaḥ I, 10-11. P. 2.

2. SR I, III. 24-26.

3. Bṛhaddeśī 63b, P. 12: rājṛ diptāviti dhātoḥ svaśabdapūrvakasya ca.

4. Saṅgītasamayāsāra 1, 47.

5. Saṅgītamakarandaḥ I. 12-15. P. 2; SR I, III. 48; Bṛhaddeśī commentary on 63. P. 13.

*saṁvādī* [consonant], *anuvādī* [assonant] and *vivādī* [dissonant].<sup>1</sup> *Vādī* [sonant] is the king of notes.<sup>2</sup> It is the most important note taken in the *rāga* (*ranjayatīti rāgaḥ* i.e. that which charms is a *rāga*). It is repeated several times in the *rāga* oftener than the rest of the notes. *Vādī* is the predominant expression of the *rāga*: its character determines the mood. It helps one to recognize a *rāga* and indicates the time of singing it. *Samvādī* [consonant] is like a minister and is a note less important than *vādī* and more important than the other notes. "The nature of the consonant (*saṁvādī*) is to reinforce the sonant (*vādī*) by which the expressiveness of the mode is engendered."<sup>3</sup> The *saṁvādī* is almost always a fifth or a fourth above the *vādī*. This corresponds with an interval of twelve or eight *śrutis*. The notes of a *rāga* excluding the *vādī* and the *saṁvādī* are called *anuvādī* and are said to be the servants in relation to the king and the minister. *Vivādī* [dissonant] notes are like enemies. This note is not natural to a *rāga* but occurs in it sometimes only accidentally. It is very difficult to use a *vivādī* note in a *rāga* without marring its beauty and hence it is left out of the *rāga* and is called the *varjya svāra* [abandoned note]. Thus the speaking note is called *vādī*, the note which converses with it is *saṁvādī*, that which increases the beauty of the *rāga* is *anuvādī*, but that which clashes with it is *vivādī*.

Our music is traditionally based on the three *grāmas* named *ṣaḍja*, *madhyama* and *gāndhāra*. *Ṣaḍja* and *madhyama* *grāmas* are found on earth while *gāndhāra* is reserved for heaven. A combination of *svāras* is called *grāma*. The three *svāras* [notes] namely *udātta* [raised], *anudātta* [not raised] and *svarita* [circumflex] of the *Veda* are not included in the *grāma*. *Ṣaḍja grāma* is the best of all the *grāmas*.<sup>4</sup>

*Rāgas* [modes] necessarily depend upon two *grāmas*

---

1. NS—KM XXVIII, 22-23, 24 and prose PP. 303-304; KSS XXVIII 19-20, 21 and prose PP. 317-318; SR I, III, 49-52, PP. 43-44.

2. Saṅgītamakarandaḥ 2-7.

3. Bṛhaddeśi commentary on 63. P. 14; yad vādisvareṇa rāgasya rāgatvaṁ janitaṁ tannirvāhakatvaṁ nāma saṁvāditvaṁ.

4. Saṅgītapārijāta 97-98. P. 28; SR I, IV, 1-2.

and are mainly produced from *ṣaḍja grāma*. *Rāga* is the basis of melody in our music. The notes which are to convey certain definite emotions or ideas must be carefully selected from the 22 intervals of the *śruti* scale and then grouped to form a mode, a *rāga*. It is defined as an arrangement of sounds, which possesses *varṇa* [ melodic movement ], furnishes gratification to the senses and is constituted by musical notes.<sup>1</sup> The term *varṇa* [ melodic movement ] refers to the act of singing and is of four kinds viz. *sthāyī* [ level ], repetition of the same sound, *āroḥī*, ascent, *avarohī*, descent, and *sañcārī*, wandering or ascent and descent combined.<sup>2</sup> The 12 notes, seven major and five minor, constitute the octave. The ascent as well as the descent taken in regular order beginning and ending with a particular note of the octave is called *mūrcchanā*.<sup>3</sup> "That which spans ( *mūrcccha* ) the scale of a mode is called *mūrcchanā*."<sup>4</sup>

According to ancient musical theory there are three important notes in the *rāga*. These are the *graha*, the *aṁśa* and the *nyāsa*. The *graha* is the starting note, the *aṁśa* the predominant and the *nyāsa* the ending note.<sup>5</sup> Today singers do not observe the rules regarding the starting or ending note of a particular *rāga* but they usually begin and end as they wish. Now *aṁśa* is considered all important and thus is the soul of the *rāga*. Śārṅgadeva identifies the *aṁśa*, the main note, with the sonant, the *vādī*. "Because it is most used during a performance, the *vādī* [sonant] is called *aṁśa* [ main note ]."<sup>6</sup> This is also supported by Abhinavagupta in the *Abhinavabhāratī*. "The *aṁśa svara* [ note ] is the same as the *vādī*."<sup>7</sup> All the characteristics of the *rāga* are embodied in its *mūrcchanā* or *ṭhāṭa*.

1. SR II. II, 1-9a, P. 155; Rāgavibodha I. I, PP. 1-2.

2. SR I, VI, 1-3, P. 65; Saṅgītapārijāta 219-220. P. 56.

3. Saṅgītapārijāta 103. P. 33.

4. Bṛhaddeśī 94. P. 22, mūrccate yena rāgo hi mūrccanetyabhisāñjita. Ārohaṇāvarohaṇakrameṇa svarasaptakam,

5. SR I, VII, 30a, 32b and 38b.

6. SR I, VII, 34.

7. Abh. Bh, on NS XXVIII, 23.

Music was an indispensable adjunct of Sanskrit plays. Theorists state that each sentiment has its appropriate music and each action its special accompaniment.<sup>1</sup> Usually the Sanskrit drama begins with music and ends with it. During the enactment of plays also there are various references to the music performed. In the *Ratnāvalī* two maids sing *dvīpadīkhaṇḍa* before the king.<sup>2</sup> In the *Mālavikāgnimitra*, Mālavikā sings and acts.<sup>3</sup> In the *Mṛcchakaṭika*, Cārudatta goes to attend a musical concert and while returning explains the beauty of the song of *Rebhila* to his associate *vidūṣaka*, Maitreya. "Really his song was impassioned, sweet, smooth, clear, and full of emotion, graceful and charming. To tell the truth, I feel that although the musical concert is over, I am as it were still listening, as I walk, to that cadence of the notes of his sweet voice; and to those well-blended notes of the lute, high-pitched when following up with the harmonious swell and fall of the sounds of the syllables ( of the song ), but low towards the close;— and to the song, sung with due regard to the pitch of sounds, graceful and repeated twice where the *rāga* (passion) required it."<sup>4</sup>

Examples from other dramas can also be cited to show what a high place music occupied in the presentation of Sanskrit plays.

There are four kinds of musical instruments in our country: stringed instruments, drums, wind instruments and cymbals—bells and gongs. According to the *Nāṭyaśāstra*, *tatam* comes under the category of stringed musical instruments, *suśira* under wind instruments and *avanaddham* and *ghanam* under instruments of percussion.<sup>5</sup> The materials of which the instruments are made are for the most part those

---

1. NS—KM XXIX, 12-13; KSS XXIX, 17 and 18; SR I, III, 60. P. 45.

2. Rat I, 13-15. P. 14.

3. Māl II, 4. P. 26.

4. Mṛch III, 4-5. P. 68.

5. NS—KM XXVIII, 1-15; XXX 1, 2; XXXI 1-4a; KSS XXVIII, 1-14; XXX, 1, 2; XXXI, 1-4.

that are easily procurable. Large gourds, bamboos, canes, reeds, jackwood, earthen ware, hides of calves, sheep and buffaloes are used.

The *Nāṭyaśāstra* points out that musicians sit in this manner: the *mārdaṅgika* facing the east between the two doors of the green room, the *pāṇavika* to his left, *gāyakas* to the south of the *raṅgapīṭha* facing the north, *gāyikās* to his front on the north facing the south, *vaiṇika* to their left and two *vaṁśikas* to their right. In all the three types of theatres, players of musical instruments occupy a place in the *raṅgaśīrṣa* between the two doors.<sup>1</sup> K. R. Pisharoti is surely wrong when he says : “The arrangement of the Athenian stage is very simple : it consisted of a round orchestra, and a low rectangular skene with a projecting Paraskenia and a low platform stage. Between the skene and the auditorium lies what is termed the Proscenium which is understood as the back wall of the stage in front of which the actors act or as pillars in front of the stage between the actors and the audience or as the stage. In these respects this agrees with our theatre, particularly in our having the *mattavāraṇī* and the *ṣaḍ-dārūka*.”<sup>2</sup>

Temples have played a great part in the preservation of musical instruments. Poses as described in the *Nāṭyaśāstra* are found sculptured on the walls of the Naṭarāja temple at Cidambaram. At Ajantā there is a painting representing the dance intended to allure Mahājanaka. The principal dancer is most artistically attired and decked with ornaments of gold and pearls. The orchestra comprises five artistes, two of them playing cymbals, one a pair of drums, another a *mṛdaṅga* and the fifth apparently a guitar. Two women playing the flute are also found in the painting.<sup>3</sup>

In our country there are nearly 400 musical instruments each with a distinct name, shape and quality of tone. The *Nāṭyaśāstra* mentions instruments such as *mṛdaṅga*, *paṇava*,

1. NS—KM XXXIV, Prose on P.429; KSS XXXIII, Prose on P.449.

2. K. R. Pisharoti's article on 'The Ancient Indian Theatre', Rajah Sir Annamalai Chettiar Commemoration Volume, Annamalai University, 1941.

3. Ajantā Cave No. 1.

*dardura*, *dundubhi*, *muraja*, *jhallarī*, *paṭaha*, *vaṁśa*, *śaṅkha* and *dakṣiṇī*.<sup>1</sup> According to the “*Mirror of Gesture*” the following accessories are called the outer life of danseuse : the drum, cymbals of a good tone—the flute, chorus, the drona, lute (*vīṇā*), the bells, and a male singer (*gāyaka*) of renown.<sup>2</sup> In the *Saṅgītamakarandaḥ* ten kinds of *vīṇā* are described and further on various instruments are mentioned.<sup>3</sup> In other treatises on music innumerable other names of instruments are mentioned.

An orchestra was organized at the Udai Shankar India Culture Centre, Almora, in 1941 exclusively with Indian instruments. Orchestras are also arranged today at representations of *kathakali* and *bharata-nāṭyam* in South India. As orchestras can be organized with Indian instruments alone in the modern age and as they help the presentation of a particular *rasa* and have a rich variety we can conclude that orchestras were similarly organized in ancient India with the help of four kinds of instruments referred to in the *Nāṭyaśāstra*.

### B. Histrionics

Now we come to *āṅgikābhinaya*, gestures or action with limbs. It is expressed in three ways—by *aṅga*, *pratyaṅga* and *upāṅga*. The head, hands, chest, sides [flanks], waist [hips] and feet are called *aṅgas*. Some writers consider the neck also as an *aṅga*. The shoulder-blades, arms, back, abdomen, thigh [calves] and shanks are called *pratyaṅgas*. Some writers add the wrists, elbows, knees and the neck also to the list of *pratyaṅgas*. The shoulders, eyes, eye-brows, cheeks, nose, jaws, lips, teeth, tongue, chin and face are called *upāṅgas*. Then there are the heels, ankles, toes and fingers. *Aṅgas*, *pratyaṅgas* and *upāṅgas* are to be used in every dance. When an *aṅga* [major limb] moves, the *pratyaṅga* and *upāṅga* also move.<sup>4</sup>

1. NS—KM XXXIV, 9-16; KSS XXXIII, 2, 10-17.

2. “*Mirror of Gesture*” P. 35, ed. 1936.

3. *Saṅgītamakarandaḥ* IV, 6-12, P. 22.

4. AD 42-49a. PP. 6-7; NS—KM VIII, 11-15; KSS VIII, 11-15; GOS VIII, 12-16.

Detailed are the directions on *āṅgikābhinaya* and here Bharata depended upon older *naṭasūtras*. The different parts of the body are described and motions and gestures and their significance assigned. The head is described as *akampita* when it is moved slowly up and down, *kampita* when the same movement is made quickly<sup>1</sup>. Each motion has a distinct significance. The glance changes according to the sentiment and the pupils move in different ways to express different sentiments and conditions.<sup>2</sup>

A series of rules are found on the motions of seven kinds of the brows<sup>3</sup>, six of the nose<sup>4</sup>, six of the cheeks<sup>5</sup>, six of the lips<sup>6</sup>, seven of the chin<sup>7</sup> and nine of the neck.<sup>8</sup> Further 24 postures of single hands, 13 of the different combined hands and 64 *nytta* hands are described.<sup>9</sup> *Mudrās*, gestures by fingers form the most important and powerful means of expression in a dance. Their richness creates a unique dramatic language and their conventionalised meanings and symbolism lend an added charm and glamour to the art of dancing. *Mudrās*, gestures by fingers set forth in the *Nāṭyaśāstra* are said to include the divine actions of celestial dancers and their application to the feelings and aspirations of human beings. We can examine the definition of one or two gestures of the hand to ascertain how they signify different objects. When the four fingers are outstretched parallel to one another and

---

1. NS—KM VIII. 16-37a; KSS VIII. 16-37a; GOS VIII. 17-40a.

2. NS—KM VIII. 38-51; KSS VIII. 38-51; GOS VIII. 41-55.

3. NS—KM VIII. 112b-122a; KSS VIII. 114-123; GOS VIII. 118b-129a.

4. NS—KM VIII. 122b-127; KSS VIII. 124-130a; GOS VIII. 129b-136a.

5. NS—KM VIII. 128-132; KSS VIII. 130b-135a; GOS VIII. 136b-141a.

6. NS—KM VIII. 133-138; KSS VIII. 135b-141a; GOS VIII. 141b-147a.

7. NS—KM VIII. 139-144; KSS VIII. 141b-147a; GOS VIII. 147b-153a.

8. NS—KM VIII. 153b-159; KSS VIII. 164-170a; GOS VIII. 170-176a.

9. NS—KM IX. 4-16; KSS IX. 4-17; GOS IX. 4-17a.

the thumb is bent, the *patākā* ( flag ) hand is formed. The hand is held against the fore-head in this manner to express blows, injuries, oppressions, gladness, or haughtiness. The same posture of the hand with the fingers separated from one another and shaken indicate the glare of heat, torrential rain or shower of flowers. When the posture of *patākā* is kept and the third finger is bent, it is called the *tripatākā* hand and signifies the bringing or giving something, or dismounting or entry.<sup>1</sup> In this manner by stating the definitions of other hands and by describing their significance it can be shown that different things are represented by different gestures of the hand in the presentation of plays.

Further directions are given regarding the chest, flanks, abdomen, hips, thighs, legs and the feet. As a matter of fact the *Nāṭyaśāstra* deals elaborately with different *cārīs*,<sup>2</sup> *maṇḍalas*<sup>3</sup> and *gatis*.<sup>4</sup> An attempt to set aright the feet, thighs, chest and abdomen is called *cārī*. Where an action is made by taking one step it is called *cārī*. As the *cārīs* connected with different limbs relate to ( *vyāyacchante* from *vyā-yam*, stretch out to ) one another they constitute a *vyāyāma* system. Where two steps are taken it becomes *karaṇa* and the combination of *karaṇas* is said to be *khaṇḍa*. Three or four *khaṇḍas* make one *maṇḍala*. *Cārī* is employed in dancing, movements, dropping of weapons and in battle. Thus *nāṭya* is dependent on *cārī*. In *nāṭya* no limb moves without the employment of *cārī*. According to the *Nāṭyaśāstra*, *cārīs* are 32 in number and are divided into two classes : earthly [ *bhauma* ] and heavenly [ *ākāśagāmī* ]. But the *Abhinayadarpaṇa* has only eight *cārīs* and they constitute only one class by themselves.<sup>5</sup> *Maṇḍalas*, according to the *Nāṭyaśāstra*, are 20 in number and are divided into two classes: earthly [ *bhauma* ] and heavenly [ *ākāśika* ], but the

1. NS—KM IX. 17b-30; KSS IX. 18-31; GOS IX. 18-32.

2. NS—KM X. 1-12; KSS XI. 1-13; GOS X. 1-13.

3. NS—KM XI. 1-5a; KSS XII 1-5; GOS XI. 1-6.

4. NS—KM XII 7b-33; KSS XIII. 8-39; GOS XII. 8-40.

5. AD 260-273. PP. 34-36.



*Abhinayadarpaṇa* gives only ten of them and does not classify them at all.<sup>1</sup> The *Nāṭyaśāstra* and the *Abhinayadarpaṇa* have no name common in their *cārīs* and *maṇḍalas*. The *nāṭyācārya* should employ *gati* [ gait ] having ascertained fully the *sthita* [ slow ], *madhya* [ medium ] and *druta laya* [ quick tempo ]. The *gati* [ gait ] of nobles should be with steadiness, that of the middle class with medium tempo, while the low class should have quick and copious gait. Different kinds of beings walk in different ways and the gait should also vary according to the situation. *Cārīs*, *maṇḍalas* and *gatis*, according to their relation to one another, are endless in number and variety. The *naṭa* has no room to be original in his gestures, for that is the business of masters [ *ācāryas* ] of the art who know the theory and practice thoroughly. It is the action, not the actor, which is essential to the dramatic art.<sup>2</sup>

An elaborate description of how animate or inanimate objects can be represented through *abhinaya*, particularly *aṅgābhinaya*, is given in one full chapter on special representation [ *citrābhinaya* ] in the *Nāṭyaśāstra*. It deals with methods of describing through bodily gestures natural phenomena such as dawn, night, twilight, day, the six seasons and the sky; mountains, oceans, stars, moonlight, heat, wind and the mid-day and evening sun, lightning; human beings and animals; objects stationed in heaven such as gods and *bhūtas*; expressions of happiness, anger, jealousy, calamity, misery, fear, intoxication, bravery and the various emotions. Different kinds of poisonous effects could be represented on the stage through bodily gestures. Let us now take some examples to show how these were represented by actors and actresses playing different roles. Cold is indicated by people of lower position by contracting their limbs, trembling, clenching their teeth, moving their lips and making a 'sī, sī' sound. Darkness is indicated by people slipping and groping their way with their hands. A person gets into a carriage

1. AD 298-308. PP. 40-41.

2. "Mirror of Gesture" by A. K. Coomaraswamy, 1917 (ed). P. 3. and 1936 (ed). P. 18.

by raising his eyes and feet and enters a palace by taking longer paces and raising the feet higher. The act of getting into water is done by raising the clothes and if the water is very deep he represents that by outstretching his hands. Joy is represented by one embracing the other's body, by smiling eyes as well as by horripilation [ *tathālpakathana* ], while anger is indicated by upturned red eyes, biting of lips, deep breathing and trembling limbs.<sup>1</sup> Each and every part of the body is important to signify some emotion or feeling. Deep significance lies in the mode in which the head is shaken, the eyes and brows are moved ; the cheeks, nose, lips, chin and neck can all be used to convey subtle themes. All this will be clear from the directions of Rāghavabhaṭṭa in his commentary on the *Abhijñānaśākuntala* for depicting the *bhramarabādhā* [ attack by the bee ], *sr̥ṅgāralajjā* [ amorous bashfulness ], *kusumāvacya* [ gathering of flowers ] and *prasādhana* or *alaṅkāra* [ wearing ornaments ].<sup>2</sup> Thus there are many themes which are indicated by means of tokens and gestures in Sanskrit plays. In reality the art of *āṅgikābhinaya* was fully developed and an object, which was not procurable, must have been represented by means of bodily gestures.

### C. Dancing

Dancing in India flourished under royal patronage and every king and chieftain had his band of musicians, court-dancers and painters. People of good family used to be well versed in these arts, and music and dancing formed an important part of their education. But dancing was not confined solely to the educated classes. Folk dances in a multitude of forms has played an important part in the communal life of the people. Indian dancing is a traditional art and as such it has fixed ends and ascertained means of operation. God Śiva in his well known aspect of *Naṭarāja* is pre-eminently the lord of dances. After the destruction of the sacrifice of Dakṣa, Śiva danced with various gesticulations to the tune of music. He imitated all the principal gods and

1. NS—KM XXV; KSS XXVI.

2. Rāghavabhaṭṭa in his commentary on Śāk PP. 24, 29, 86, 99.

assumed different postures. These dances were known as *piṇḍibandhas*.<sup>1</sup>

The position of hands, feet, waist, flanks, thighs, abdomen, back and chest are vital in dance. Sometimes motion is slow and sometimes quick. These movements are called *mātrkā*<sup>2</sup> or mothers of dance. A combination of three or four of these is a *karāṇa* or action. One hundred and eight such actions [ *Karāṇas* ]<sup>3</sup> are enumerated in the *Nāṭyaśāstra*. Different combinations of these actions are called *aṅgahāras*<sup>4</sup> or gesticulations. The *Nāṭyaśāstra* enumerates 32 such gesticulations. There are four different ways to end the dance gracefully and they are called *recakas*.<sup>5</sup> All these *recakas*, *aṅgahāras* and *piṇḍibandhas* were designed by Śiva after the destruction of the sacrifice of Dakṣa. He taught Taṇḍu the art of dancing and hence dancing has been known as *tāṇḍava*.

The temple at Cidambaram where the *tāṇḍava* is believed to have been performed is one of the most beautiful temples in India, dedicated to Śiva in his aspect of *Naṭarāja*. In the most inner enclosure is the *ṇṛtta-sabhā* or hall of dance. It consists of a stone platform with 56 stone pillars with dance poses exquisitely carved on them. This hall is at least 1,400 years old and is one of the earliest of Indian temple monuments. Towards the gateways there are 108 bas-relief panels, depicting a dance of Śiva and his consort Pārvatī. There are many fine examples of classical dance poses in the temples at Ellorā in Hyderabad, Elephanṭā near Bombay, Bhuvaneśvara near Puri on the Bay of Bengal, and in numerous temples scattered all over South India.

Delighted with the performance of the drama, the *Tripura-dāha*, Śiva ordered Taṇḍu to teach Bharata the art of dancing. Sages asked Bharata why the dance was included in a dra-

---

1. NS—KM IV. 233-242a; KSS IV. 246b-256; GOS IV. 257-266.

2. NS—KM IV. 54b-58; KSS IV. 55b-60; GOS IV. 56-60.

3. NS—KM IV. 32b-54a; KSS IV. 34-55a; GOS IV. 34-55.

4. NS—KM IV. 16b-26a; KSS IV. 18-27; GOS IV. 18-27.

5. NS—KM IV. 231b-232; KSS IV. 240-246a; GOS IV. 250b-256.

matic performance. It did not help the story nor did it produce an emotion. Acting was quite sufficient for those purposes. Bharata's explanation was this: "Dances do not help dramatic action but beautify it. They are very popular, especially on auspicious occasions."<sup>1</sup>

The *Nāṭyaśāstra* recognises two types of dance, *tāṇḍava*, the violent dance of men, invented by Śiva himself, and *lāsya*, the tender amorous dance of Pārvatī. Because of its special importance *lāsya* is carefully analysed into ten parts by the *Nāṭyaśāstra*.<sup>2</sup> It shows the essential union of song and dance. The divisions of *lāsya*, of course, appear to ignore their nature as parts of a dance, but it must be remembered that the motions of performers are essential in the performance.

We obtain a clear idea of dancing from a critical study of the first two acts of the *Mālavikāgnimitra* and first act of the *Ratnāvalī*.

The science and art of dancing are known as *abhinaya-vidyā* or *nāṭyaśāstra*. This is divided into two parts *śāstra* [ science ] and *prayoga* [ performance ] The latter is further distinguished into *kriyā* [ self-acting ] and *saṅkrānti* [ imparting lessons in dancing ].

The actual performance consists of two parts, *aṅgasauṣṭhava* [ graceful contours ] and *abhinaya* [ gesticulation, expressing sentiment ]. Graceful contours can be exhibited in a two-fold manner, through *viralanepathyā* [ thin costume ] and body control.

Then begins the real work of the dancer, Mālavikā, in the present case. She takes up a stanza of four lines, first hums the tune and afterwards sings it aloud. Thereafter she gesticulates with a view to bringing out the sentiment which permeates the piece.

*Bhāvas* form the most important feature of *abhinaya-vidyā*. The two dance masters [ *abhinayācāryas* ] Haradatta and

1. NS—KM IV. 244-248; KSS IV. 258b-263a; GOS IV. 268b-273a.

2. NS—KM XVIII. 170-181; KSS XX. 138-151; DR III. 52, 53, p. 73; SD VI. Sūtras 241-251. PP. 393-394.

Gaṇadāsa have been described as two *bhāvas* incarnate. Similarly the lesson in *abhinaya* which is imparted to Mālavikā by Gaṇadāsa has been described as *bhāvika*. Any movement or emotion difficult of representation was called *duṣprayojya* as an instance of which is given *calita*, a dance in which the dancer, while representing the sentiments, gives expression to his own feelings. The success of an actor lies in his bringing in bodily form a particular emotion. The *bhāva* becomes *śarīrī* when the *calita* was performed by Mālavikā. Parivrājikā describes it as faultless art and is full of appreciation for it.<sup>1</sup>

The maids, in the *Ratnāvalī*, dance before the king, who shows deep appreciation of their art.<sup>2</sup>

In the *Mṛcchakaṭika* also there are references to dancing. *Viṭa*: 'stop there, Vasantasenā, your steps show skill in a dance.' Saṁsthānaka calls Vasantasenā a dancing girl [*lāsikā*].<sup>3</sup>

In the *Bālacarita* there is reference to a *Hallīśaka* dance. Girls of cowherds, though naturally charming, look extremely beautiful when dressed up in garments of varied hues. Young cowherds have drums and are singing. "Dāmodara : come now, belle of the station, wood garland, crescent and gazelle, we must do this dance made for herdsmen. Girls : As you tell us, master. Saṅkaṣaṇa : Dāmaka and Meghanāda, beat the drums. Both : Right, Master [ All dance ]. Old Herdsmen : Bravo, that's good. Well sung. Well danced. I will dance a bit myself. Now I am tired."<sup>4</sup>

Thus it can be seen from dramas that dancing was very popular with spectators.

### D. Dialogue

Ancient dramatists gave great importance to dialogues and proper dramatic delivery. The *Nāṭyaśāstra* emphasizes on the choice of words in a play and calls them the body of

---

1. Māl II. 8. P. 29.

2. Rat I. 16. P. 15.

3. Mṛch I. 17. P. 15; 23. P. 17.

4. Bālacarita III, PP. 539-540.

the dramatic art [ *nāṭya* ]. *Vācikābhinaya* [ verbal representation ] mainly consists in the use of proper pronunciation, modulation, accent and rhythm.<sup>1</sup> Use of different dialects and proper forms of address to persons according to their ranks or social status are also included. These rules are very elaborate and are well adapted to bring out the lyrical qualities of a play and will be discussed in chapter VIII of this work.

The value of an instructive or entertaining dialogue was well understood in India and religious scriptures, the *Vedas*, the *Upaniṣads*, the *Samhitās*, the *Mahābhārata*, the *Tantras*, the *Purāṇas* and even the *Jātakas* or the *Baudha-ākhyānas* are in the form of conversations. In fact another name of the *Veda* is *śruti*—what was heard in conversation. The *Nāṭyaśāstra* insists on weighty dialogue and says the words employed in dramas should be suggestive, deep in meaning, approved of by the *Vedas* and acceptable to all persons.<sup>2</sup>

The dialogues between Ātreya and Vāsantī in the *Uttararāmacarita*, between Sāgarikā and Susaṅgatā in the *Ratnāvalī*, between Kaśyapa and Śakuntalā in the *Abhijñānaśākuntala*, between Bhīmsena and Draupadī in the *Veṇīsaṁhāra*, between Urvaśī and Pururavas in the *Vikramorvaśīya*, between Cāṇakya and Candanadāsa in the *Mudrārākṣasa* are lively and deep in meaning. The language of Bhāsa is very simple, natural and touching, alternating with simple figures of speech. The language of Kālidāsa is remarkably easy. Bhavabhūti in the *Uttararāmacarita* uses somewhat more difficult language. In his other two plays, and especially in the *Mālatīmādhava*, it is more elaborate and difficult. The *Mṛcchakaṭika* presents fewer difficulties than any of these dramas.

Ordinary dialogues in Sanskrit plays are for the greater part in prose, but reflections or descriptions and poetical

---

1. NS—KSS XV 1-4; GOS XIV. 1-4; Agnipurāṇa CCCXXXIX. 49b-53. P. 312.

2. NS—KM XXVII. 42-46a; KSS XXVII. 45-49a.

fancy take the form of verse. Many kinds of metre from *anuṣṭubh* to *daṇḍaka* are used by them.<sup>1</sup>

Intonation [ *Kāku* ] is change of voice under different emotions such as fear, grief and anger. *Kāku* is a word of negation which is used in a manner implying the affirmative, as in question of appeal. In such cases the intended meaning is suggested by a change of the voice. Slow [ *vilāmbitā* ] intonation is desired in the comic, the erotic and the pathetic sentiments. In the heroic, the furious and the marvellous sentiments the excited [ *dīptā* ] and high [ *uccā* ] intonations are praised. Fast [ *drutā* ] and low [ *nīcā* ] intonations have been prescribed in the terrible and the odious sentiments.<sup>2</sup> Thus the intonation should be made to follow the states [ *bhāva* ] and the sentiments [ *rasa* ].

*Vithyaṅgas*, the constituent parts of *vīthī*, are purely of the rhetorical kind. They are often mentioned in the rules of theorists and serve the purpose of enhancing the beauty of presentation of plays.<sup>3</sup>

---

1. NS—KSS XV. 37-47; GOS XIV. 42-52.

2. NS—KM XVII. 108-118a; KSS XIX. 46-58; GOS XVII. 115-129.

3. NS—KM XVIII. 156-168; KSS XX. 118-133; GOS XVIII. 113b-126a.

## CHAPTER VII

# THE TROUPE

### A. Roles of Characters ( *Bhūmika* )

We shall now deal with the types of people allowed to play roles in Sanskrit dramas. Actors were selected for their gait, speech, gestures and disposition. Divine personages were represented by persons whose physiques were well built and who spoke delightfully. Those, who were fat and tall, whose voice was deep like thunder and who had terrifying eyes, eyebrows and faces, were selected for the roles of *rākṣasas*, *dānavas* and *daityas*. The roles of princes were assumed by wise actors, of good appearance and voice and of virtuous disposition; of generals and ministers by persons who were brave, clever in conversation and possessed of clear vision; and of chamberlains and learned *śrotriya*s by persons who had pale eyes and long noses. Persons, who were slow, dwarfish, hunch-backed, of deformed noses or cheekbones, of ugly faces, badly dressed and ill-tempered, played the parts of servants. Wearied persons were represented by those who were lean and thin, while persons in normal health were represented by fat persons. The manager would, however, use his discretion to select actors keeping in view the feeling, actions and nature of the characters. The characters were represented according to their country, dress and appropriate appearance.<sup>1</sup>

In Sanskrit plays the roles were of three different qualities: *anurūpā*, similar to the nature of the person represented, *virūpā*, contrary to the nature, and *rūpānusāriṇī*. imitative by nature. *Anurūpā* is that which is represented by an actor of the same age and sex. In *virūpā* a child plays the role of an old man or an old man takes the role of a child.

---

1. NS—KM XXXV. 1-20a; KSS XXXV. 1-8.



In *rūpānusāriṇī* a man plays the part of a woman. A man's role may be played by a woman and vice versa according to the desire of the manager, but an old man or a boy should not be made to play the role of each other. When a man's role is given to a woman it should be done with great care. Thus the *Nāṭyaśāstra* expressly admits of three modes of representation: roles may be taken by persons of appropriate sex and age; roles of the old may be taken by the young and vice versa.<sup>1</sup> The assumption of women's roles by men has, curiously enough, very early evidence; for the *Mahābhāṣya* mentions the word *bhrūkum̐sa* which was used to denote a man who was personating a woman.<sup>2</sup> The *Sūtradhāra* in the *Ratnāvalī* and the *Priyadarśikā* plays the part of Vatsa, his younger brother that of Yaugandharāyaṇa in the former play<sup>3</sup> and that of Dr̥ḍhavarman in the latter<sup>4</sup>; in the *Malatīmādhava*, the *sūtradhāra* and *Pāripārśvika* assume the roles of Kāmandakī and her pupil Avalokitā, respectively.<sup>5</sup> The enactment of women's roles by men was not by any means the normal practice. The *naṭī* normally plays an important female role as in the *Karpūramāñjarī*.<sup>6</sup> In the *Kuṭṭanīmata*, where an actual representation of the first act of the *Ratnāvalī* is described, a woman is found in the role of the princess.<sup>7</sup>

Bharata states that women are delicate [ *sukumāra* ] and hence they should be represented by women alone. *Nāṭya* should be performed by women well versed in the dramaturgic *śāstra*.<sup>8</sup> Learned teachers should instruct women in terms of the *Nāṭyaśāstra* for theatrical representation was a delicate [ *sukumāra* ] subject. Roles in *śṛṅgāra* sentiment should be left to women, for they have delicate gestures and well-formed limbs.

---

1. NS—KM XXVI. 1-5; KSS XXXV. 15-20.

2. Mahābhāṣya II. P. 196.

3. Rat I. Prelude Prose P. 7.

4. PD Prelude Prose PP. 3-4.

5. MM Prastāvanā P. 12.

6. Kar. M, Prastāvanā P. 11.

7. Kuṭṭanīmata—KM 852-927. PP. 104-110.

8. NS—KM XXVI. 6-13a; KSS XXXV. 21-23a, 24b-29.

In *nāṭya*, two kinds of performances, *sukumāra* and *āviddha* are followed to present emotions and sentiments. *Nāṭaka*, *prakaraṇa*, *bhāṇa*, *vīthī* and *aṅka* are varieties of the delicate [ *sukumāra* ] type. *Āviddha* is full of war, motions and agitation. It involves too much of cutting, tearing and fighting; there is also the use of indecent language. Hence women should not take any part in it. The styles known as *sātvatī* and *ārabhaṭī* are employed in it. *Ḍima*, *Samavakāra*, *Vyāyoga* and *Īhāmṛga* are its species. Their *āviddha* performances were to be done by *devas*, *dānavas* and *rākṣasas* who were violent by nature and full of vigour.<sup>1</sup>

### B. Nāṭyācāryas

Poets, directors, stage managers, musicians, scene-designers and painters come under the category of *nāṭyācāryas*, according to the *Nāṭyaśāstra*. Among *nāṭyācāryas*, the *sūtradhāra* is the foremost as he guides actors, arranges the paraphernalia, directs the performance and above all is responsible for the successful presentation of the play. According to the *Nāṭyaśāstra*, the *sūtradhāra* should be a master of sciences and arts, know countries, and costumes and customs prevalent in them. He should be well versed in languages, the science of dramaturgy and versification. He should have good knowledge of music, musical instruments, political science, geography, astrology, anatomy, history, law and emotions and sentiments. He should be able to foresee the purport of his own exposition. These are the minimum qualifications of a *sūtradhāra*. In addition, he is a poet, has excellent memory and intellect, is grave and generous. He should be in good health, sweet-tempered, self-controlled, of a forgiving nature, righteous, not avaricious, truthful and impartial.<sup>2</sup>

The *Sūtradhāra*, the chief actor, whose name denotes that he was thought of as an architect conversant with histrionics, is occasionally styled head of the troupe. He is essentially the instructor of the actors and his designation

1. NS—KM XXVI, 20-25; KSS XXXV. 23b-24a, 30-36.

2. NS—KM XXIV, 93-100; KSS XXXV. 45-52.

can be taken to mean a professor. In the *Uttararāmacarita*, Bharata is called *tauryatrika sūtradhāra*, professor of the three kinds of *saṅgīta* [instrumental music, song and dance].<sup>1</sup> Thus the *sūtradhāra* was an important dramatic personage, controlling the whole company, assuming different roles, sometimes arranging the scenes, sometimes directing the actors and sometimes himself taking an important role in the plays.

According to the dramatic treatises, the *sūtradhāra* had two associates, the *sthāpaka* and the *pāriṣāsvika*. In his attributes the *sthāpaka* resembles the *sūtradhāra*. Immediately after the preliminaries, another person, similar to the *sūtradhāra* in appearance and qualities is to enter and introduce the play, a function which gives him the designation of the introducer [ *sthāpaka* ].<sup>2</sup> He does not, however, figure in any of the extant dramas and so the duties assigned by the treatises to the *sthāpaka* must have all been performed by the *sūtradhāra* himself.

According to the *Nāṭyaśāstra*, the *pāriṣāsvika*'s qualities and qualifications are second only to those of the *sūtradhāra*. He is of middle type, of good form, intelligent and an expert in the performance of his duties. He has full knowledge of instruments. He is an attendant of the *sūtradhāra*. He appears in the prologues of many plays and acts the parts of persons of rank. He receives the *sūtradhāra*'s orders, passes them on to other actors and directs the chorus.<sup>3</sup>

The *Nāṭyaśāstra* also refers to some *ācāryas* expert in preparing materials required for the stage and proficient in directing actors and actresses. Many types of artisans seem to have been necessary in the presentation of plays.<sup>4</sup>

There is the *mukūṭakara* who makes crowns [ *mukūṭas* ] for the characters with the help of different materials as stated in chapter V of this book. He prepares various kinds of head-dresses also. The *ābharaṇakṛt* prepares ornaments.

---

1. URC IV. P. 119.

2. NS—KM V. 149-154; KSS V. 163-168; GOS V. 168b-169a, 172b-177a.

3. NS—KM XXIV. 101b-102a; KSS XXXV. 53.

4. NS—KM XXXV. 26-27, 31-37; KSS XXXV. 72-73, 77-84.

The *mālyakṛt* makes garlands. The *veṣakara* prepares dresses. The *citrakara* paints pictures. The *rajaka* dyes the dresses. The *kāruka* prepares things out of lac, stone, iron and wood. He is an artisan who prepares different items of stage paraphernalia. The *kuśilava* is an expert in the arrangement of musical instruments and also in playing them. The *nāṭyakāra* leads the characters in a play by directing them in the representation of feelings. The *naṭa* is the performer of *nāṭya* and an expert in using the four kinds of musical instruments. He is called *naṭa* because he represents and imitates the actions of men. He is an expert in the representation of sentiments, feelings and courage. The *nāṭakīyā* is a beautiful woman who can sing and has the capacity to rouse sentiments. She is familiar with the different kinds of musical instruments and has knowledge of rhythm and tune. The *taurika* is the head of warriors and trumpeters, an expert in blowing all musical instruments. Thus artisans are named according to the duties they are called upon to perform.

### C. Actors and Actresses

There is a great variety of characters, male and female, introduced in Sanskrit plays. Kings, ministers, high officials and attendants often figured very prominently. Actors and actresses were, however, classified according to their qualifications into superior [ *uttama* ] medium [ *madhyama* ] and third rate actors [ *adhama* ].<sup>1</sup> The principal parts in any drama were, however, a few; the king, the *vidūṣaka*, the parasite, the heroine and her companion were stock types. Theorists give detailed instructions about persons appearing on the stage.

Heroes were [ *nāyaka*, *netṛ* ] of different kinds according to their qualities. They were light-hearted [ *lalita* ], calm [ *śānta* ], exalted [ *udāṭṭa* ] or vehement [ *uddhata* ].<sup>2</sup> The self-controlled and light-hearted hero, *dhīralalita*, was free from anxiety, fond of the arts, happy and gentle. The hero in the

---

1. NS—KM XXIV. 85-92; KSS XXIV. 1-8.

2. NS—KM XXIV. 3-5; KSS XXXIV. 17-19; DR II. 1-6a, PP. 35-38; SD III. 35-38. PP. 90-91.

*Ratnāvalī* is an instance of the *dhīralalita* hero. The self-controlled and calm hero, *dhīraśānta*, is a Brāhmaṇa or possessed of the generic qualities of a hero. The heroes in the *Mālatīmādhava* and the *Mṛcchakaṭika* are instances in point. The self-controlled and exalted hero, *dhīrodatta*, is of great excellence, exceedingly serious, forbearing, not boastful, resolute, assertive and purposeful. The heroes in the *Mahānāṭaka* and the *Abhijñānaśākuntala* are instances of this type. The self-controlled and vehement hero, *dhīroddhata*, is dominated by pride and jealousy, devoted to witchcraft and deceit, self-assertive, fickle, irascible and boastful. Examples of this type are rarely found. Various other types of heroes are described, but as they serve no purpose in the actual presentation of Sanskrit plays we do not go into a detailed study of their characteristics.

Sometimes the hero has an antagonist, and he is the *pratīnāyaka*. He is avaricious, stubborn, criminal and vicious like the *dhīroddhata* hero. He is always painted as passionate and evil-minded.<sup>1</sup> Rāvaṇa, the opponent of Rāma, and Duryodhana, the opponent of Yudhiṣṭhira, are *pratīnāyakas*.

Among the pleasure companions [*narmasaciva*, *narmasuhṛd*] of the hero is the *pīṭhamarda* [he who rubs his sides]. He is devoted to the hero and is the hero of an episode [ *patākā*, *prāsaṅgika-itivṛtta* ].<sup>2</sup> Sugrīva in the Rāma dramas and Makaranda in the *Mālatīmādhava* belong to this class.

According to the *Nāṭyaśāstra*, *Viṭa*, parasite, is familiar with the ways of courtesans, sweet-tempered, impartial, poetic, able to argue, eloquent and clever. He is amiable in society and versed in arts.<sup>3</sup> Vātsyāyana says that the *viṭa* is a character who squanders away his resources. He is married.<sup>4</sup> In dramas, especially in the *Mṛcchakaṭika*, *viṭa* plays a great part. In the *bhāṇas*, however, the actor appears as a

1. DR II, 9b. P. 40. SD III, 137. P. 149.

2. SD III, 47. P. 96. DR II, 8. P. 40.

3. NS—KM XXIV. 102b-104; KSS XXXV. 54-55; DR II, L 9. P. 40; SD III, 49. P. 79.

4. Kāmasūtra 45. P. 56.

*vīṭa* and the role can be taken to have been borrowed directly from the popular stage.

*Vidūṣaka*, the joker, is the most important stock character in Sanskrit plays. He is a Brāhmaṇa and is described bald-headed, hunch-backed, dwarfish, has protruding teeth, a distorted mouth and yellow eyes. He is dressed in rags and skin. He is fond of quarrels and takes pleasure in eating and drinking.<sup>1</sup> His external appearance, dress and gait are meant to evoke laughter. Moreover, he is the faithful companion and friend of the hero, who calls him a comrade [ *vayasya* ] and seeks his help in all difficulties, on account of which he often appears very dexterous.

The *Śakāra* is an old, popular character and is the brother-in-law of the king. He is irritated without any reason and again appeased, wears gorgeous clothes and jewels, gladly brags of his high connections, but throughout shows himself as ignorant and contemptible. He pronounces *śa* for *sa* and speaks *māgadhi*.<sup>2</sup>

To the next circle of the hero's acquaintances belongs the slave *ceṭa*. According to the *Nāṭyaśāstra*, the *ceṭa* is quarrelsome, talkative, physically deformed and knows well whom to respect and whom not.<sup>3</sup>

To the more distant or outer circle [ *bāhya* ] of acquaintances belong the commander-in-chief [ *senāpati* ], the successor to the throne [ *kumāra* ], the different ministers [ *mantrin*, *saciva*, *amātya* ], the judges [ *prāḍvivāka* ], messengers to distant places [ *dūta* ] and the court priest [ *purohita* ].<sup>4</sup>

Detailed instructions on the different types of heroines [ *nāyikā* ], their qualities, situations and relation to the hero are available. They may be divine women [ *divyā* ], queens

1. NS—KM XII. 121-122, XXIV. 106; KSS XIII. 136-137, XXXV. 57; GOS XII. 137b-139a; DR II. 9. P. 40; SD III. 50. P. 98.

2. NS—KM XXIV. 105; KSS XXXV. 56; DR II. 44b-45a, P. 56; SD III. 52-53. PP. 99-100.

3. NS—KM XXIV. 107; KSS XXXV. 58.

4. NS—KM XXIV. 59b-61a; KSS XXXIV 67-68.

[ *nṛpaṇatnī* ], women of good family [ *kulastrī* ], or courtesans [ *gaṇikā* ]. In their relation to the hero, they may belong to him [ *svīyā* ], to another [ *anyā* ] or to all ( *sādhāraṇī* ).<sup>1</sup> The *svīyā* type of heroine is found in the *Uttararāmacarita*—Sītā, the wife of the hero, Rāma. An *anyā* heroine is either a maiden or a married woman. A married woman should never figure in the principal sentiment, but love for a maiden could be represented in connection with the principal or the subordinate sentiments. An example of the *anyā* type is found in the *Ratnāvalī* and the *Mālatīmādhava* in the love of Vatsarāja for Sāgarikā and Mādhava for Mālatī. In the *sādhāraṇastṛī* type falls the courtesan. The *Mṛcchakaṭika* refers to a distinct class of very highly accomplished *gaṇikās* or courtesans, and Vasantasenā, a dancing girl, is introduced as an accomplished heroine with admirable traits of character.

Next to the heroines come their friends, step-sisters, maids and members of the harem. The *Nāṭyaśāstra* describes them as constituting the inner circle [ *ābhyantragana* ].<sup>2</sup> To this class belongs the principal queen [ *mahādevī* ], the second queen [ *dovī* ] and old woman [ *vrddhā* ]. In addition to these, are woman body guards [ *sañcārikā* sometimes called *yavanī* or greek maidens ], women waiting on the king [ *anucārikā* ] the heroine's personal maids [ *paricārikā* ] and the door-keeper [ *pratihārī* ].

There is a third category of roles called *napuṃsaka* [ neuter ]. Bharata includes in this class learned and skilled Brāhmaṇas [ *snātaka* ] chamberlains [ *kañcukīya*, *kañcukin* ] and eunuchs [ *varṣadhara*, *nirmuṇḍa*, *aupasthāyika* ].<sup>3</sup>

#### D. Spectators and judges

Sanskrit dramas demanded the full attention of a cultured audience. It is expressly asserted, as in the dramas of Kālidāsa, Harṣa, Bhavabhūti and Viśākhadatta, that

---

1. NS—KM XXIV. 6b-9; KSS XXXIV. 24-25; DR II. 15-23a. PP. 42-48; SD III. 68-85. PP. 106-120.

2. NS—KM XXIV. 15-17; KSS XXXIV. 29-31.

3. NS—KM XXIV. 50-52; KSS XXXIV. 61-62.

spectators are critical and experienced. In the *Mālavikāgnimitra* the stage manager says : 'I am asked by the learned audience to represent on the occasion of the spring festival the play named '*Mālavikāgnimitra*'. Then on the question whether the *Mālavikāgnimitra* should be played the manager says : 'The wise accept one or the other after examination, while the judgment of a fool is led by the experience of others'. Thus the *Mālavikāgnimitra* requires the audience to be learned and critical.<sup>1</sup>

In the *Ratnāvalī* the stage manager says : 'Ah. I am quite sure, the minds of all the spectators have been won over or are favourably disposed towards us. For, Śrīharṣa is an eminent poet and this audience here is ever disposed to appreciate merit ; the story of Vatsarāja is an attractive one in the world, and we are masters of the histrionic art. Each of these circumstances leads to the attainment of the desired object. What to say then when there is a combination of all advantages through my accumulated luck.'<sup>2</sup> Here also the audience is supposed to be critical as with that quality alone the merits of a play can be judged.

There is no need to quote any example from Bhavabhūti's dramas. He was a great stylist and had a wonderful command over language. The poetry of his dramas could only be appreciated by a learned and critical audience.<sup>3</sup>

In the *Mudrārākṣasa*, the manager says : 'Really I have very great pleasure in acting before an assembly capable of appreciating the merits of poems. Do you ask why? Grain sown by even a fool will thrive if it falls on good soil. The growth of paddy in clusters does not depend on the skill of the sower.'<sup>4</sup> So in this drama, too, the audience has a high standard and is critical and able to appreciate merits. Thus dramas themselves show that the spectators [ *sabhāṣad* ] were appreciative of the dramatic art.

---

1. Māl I. 2 and prose PP. 2-3.

2. Rat I. 5. P. 5.

3. MM IX. 17. P. 184; URC I. 27. P. 27.

4. Mudrārākṣasa I. 3. P. 7.



The *Nāṭyaśāstra* requires that the ideal spectator has keen susceptibility and excellent judgment with ability to feel the emotions of characters as depicted by actors. He should be attentive, an expert in handling the four kinds of instruments, have a knowledge of dresses, dialects, gestures and metres. He should be well versed in the *śāstras* and arts and should be religious by temperament. Thus he should have keen intelligence, a capacity to examine and weigh the merits of the performance and participate in the pleasures and sorrows depicted on the stage.

In an assembly [*parīṣad* or *saṁśad*] there may be very few who fulfil all these conditions. The spectators can be good, medium and indifferent. They appreciate only that art, dress, action, speech or movement which is intelligible to them. Youths enjoy passionate scenes; religious-minded persons take pleasure in scenes dealing with salvation. The brave delight in the representation of the *vibhatsa* and *raudra* sentiments and of battles. The old are interested in religious stories and *purāṇas*. Boys, fools and women take pleasure in comic scenes.<sup>1</sup> Thus different spectators derive pleasure from different scenes according to their age, country and circumstances.

The *Abhinayadarpaṇa* characterises the audience as a *kalpavṛkṣa*—the tree that answers all wishes. The *vedas* are its branches, *śāstras* its flowers and scholars the bees adorning it.<sup>2</sup>

There was a very elaborate arrangement for judging in every detail the success of a performance. According to the *Abhinayadarpaṇa*, the *sabhāpati* or chief of the audience should be wealthy, intelligent, discriminating, an expert in giving awards, versed in music, versatile, celebrated, having pleasing qualities, well acquainted with gestures expressive of desires and moods, without envy or malice, well disposed to people; possessed of righteous conduct, kind, patient, disciplined, versed in arts and proficient in *abhinaya*. His functions are to make pronouncements on the merit of a performance and

---

1. NS—KM XXVII. 47-60a; KSS XXVII. 50-63a.

2. AD 19. P. 3.

to distribute rewards to the *sūtradhāra* or leader of the troupe of dancers, musicians and actors.<sup>1</sup> The definition of a *sabdhāpati* is also given in the *Śaṅgītaratnākara*.<sup>2</sup>

The *sabdhāpati* has advisers. They speak in a dignified manner, have a desire for fame, understand moods [ *bhāvas* ] and are able to distinguish between merits and demerits. They are versed in arts and polity and are themselves scholars. They can distinguish a dialect from another and possess poetic faculty.<sup>3</sup>

The success of a drama depends on the judgment of the critic [ *prāśnika* ] who has necessarily to be qualified for the delicate task of judging the merit of the performance. The *Nāṭyaśāstra* gives ten kinds of critics [ *prāśnikas* ]: an expert in sacrifice [ *yajñavit* ], an actor [ *nartaka* ], a prosodist [ *chandovit* ], a grammarian [ *śabdavit* ], a king [ *rājan* ], an expert in archery [ *iṣvastravit* ], a painter [ *citravit* ], a courtesan [ *veśyā* ], a musician [ *gandharva* ] and an officer of the king [ *rājasevaka* ]. When there is a conflict of opinion among spectators, that of the *prāśnika* is listened to.

A critic [ *prāśnika* ] is an expert in his own province—an expert in sacrifices, a judge in matters of sacrifice, an actor in acting, a prosodist in complicated metres, a grammarian in lengthy speeches, a king in connection with dignity, in dealing with the female apartments and royal roles, an archer in the excellence of the position of the body or general deportment, a painter in judging the manner of salute and dress, a courtesan in representation of passionate scenes, a musician in musical notes and rhythm and an officer of the king in matters of servitude or courteous demeanour.<sup>4</sup>

---

1. AD 17.

2. SR VII. 1345-1350.

3. AD 18.

4. NS—KM XXVII. 60b-61; KSS XXVII. 63b-68a. The text of NS is corrupt here. Abh. Bh. and KM do not speak much about the definition of *prāśnikas*. Only KSS gives details. Here in verse 64 of KSS there should be *śabdavit* in place of *chedvit* and here *rājan* should also be enumerated in the list of ten *prāśnikas*. In verse 66 there should be *iṣvastravit* in place of *iṣṭavāk*.

We can have a clear idea of the critic [*prōṣṇika*] if we closely study the *Mālavikāgnimitra* and the *calita* dance scene performed in the *saṅgītaśālā* of king Agnimitra. There is a discussion as to who, Hardatta or Gaṇadāsa, was the better dance master. Parivrājikā was made the judge. She had a keen insight into gestures and other aspects of representation. She faithfully appreciated the merits of the dance of Mālavikā. She said: 'All was faultless and in accordance with the rules of the dramatic science. Her limbs, eloquent with expression properly conveyed the sense, and the movement of her feet was perfect in timing. She exactly represented the sentiment. The movement of her fingers was gentle. In the successive development of acting one feeling gave place to another still the interest remained just the same.'<sup>1</sup> Critics like Parivrājikā, who could judge every detail of the representation critically and minutely, were to be found witnessing Sanskrit plays.

#### E. Social Position of Actors and Actresses

We come now to the social position of actors and actresses. The mythological account given by Bharata says that the actors, in a comic vein, made fun of certain holy sages and were cursed with the loss of their status, which, thereafter, came to that of *sūdras*. King Nahuṣa, of epic fame, was the first to establish a theatre on earth, compelling the heavenly nymphs and songsters to come down to the mortal world where they married and mixed with mortals.<sup>2</sup> The story of the curse on actors shows that at the time of Bharata actors as a class had become notorious [*nirbrahmaṇa*] and their unclean habits [*sūdrācāra*] were detested and shunned by refined society [*nirāhuta*]. When they died, their death was unmourned [*aśoca*].

In the *Rāmāyaṇa*, an actor, *śailūṣa*, is found handing over his wife to another.<sup>3</sup>

---

1. Māl II, prose and 8, PP. 24 and 29.

2. NS—KM XXXVI, 28-35, XXXVII. 14-18a; KSS XXXVI, 29-37a, 60b-64.

3. Rāmāyaṇa II. 30. 8.

The *Arthaśāstra* enjoins that pleasure houses or *nāṭyaśālās* for *naṭas*, *nartakas*, instrumentalists and reciters of stories and actors should not be built in the heart of villages, lest their plays should hinder the work of the residents of the place. The *Kuśilava* is described as a *sūdra* to be banished. The *Arthaśāstra* mentions *Kuśilavas* with *rūpājīvas* in connection with song and music.<sup>1</sup>

Manu seems to have been aware of the influence which the stage exerted on people and he was vehement in denouncing the profession of actors. In fact, he prohibited Brāhmaṇas from becoming actors. Manu imposes only a minor penalty on illicit connections with the wives of actors because they were themselves willing to hand over their wives to others for profit. Manu speaks of the professions of *naṭas*, athletes [ *bhalla* ] and boxers [ *malla* ] as the lowest means of livelihood and says *kuśilavas* should be avoided.<sup>2</sup> According to Manu and yājñavalkya the testimony of a *kuśilava* is not valid and no Brāhmaṇa should accept food from stage artists<sup>3</sup>—a fact attested by the *sūtradhāra* in the prologue to the *Mṛcchakaṭika*, who says he can find none in ujjain to accept his hospitality.<sup>4</sup>

The law book of Viṣṇu treats actors as *āyogava*, a mixed caste, representing the fruit of alliances, improper and undesirable, between *sūdras* and daughters of *vaiśyas*.<sup>5</sup>

That wives of actors who served as actresses were of low morals is illustrated in the *Mahābhāṣya*. It says, the women of *naṭas* mix with different persons as vowels with consonants.<sup>6</sup>

The reputation of actors and actresses was low and uncomplementary. Actresses were considered to be leading an immoral life and lexicographers characterised actors as living on the price of their wives' honour [ *jāyājīva* and *rūpājīva* ].

1. AS I. ii. 1. P. 114, AS I. i. 3. P. 29, AS I. ii. 27. PP. 305-306.

2. Manusmṛti VIII. 362. P. 330, XII. 45. P. 475, X. 22. P. 401.

3. Manusmṛti IV. 214-215. P. 170, VIII. 65. P. 280; Yājñavalkya-smṛti II. V. 70-71. PP. 667-668, I. VI. 160b and 161. P. 237.

4. Mṛch I. PP. 9-10.

5. Viṣṇusmṛti XVI. 3, 8. P. 45.

6. Mahābhāṣya III. P. 7.

On the other hand, however, actors enjoyed the friendship of great kings and eminent dramatists. Traces of a brighter side of the profession are found and this doubtless can be connected with the gradual elevation of the art from humble origins to the rank of refined poetry.

Bharata ranks as a *muni* or holy sage. As he is the originator of the dramatic art, actors are called *Bharataputras* or sons of Bharata. Almost everything connected with drama or the stage is named after him. The oldest and most authoritative treatise on dramaturgy, the *Nāṭyaśāstra*, is ascribed to Bharata. The *apsarā* Urvaśī, a nymph, plays a scenic role in heaven before Bharata.

An actress was often, if not necessarily, one of the courtesans. In the *Mṛcchakaṭīka*, Vasantasenā is skilled in acting and has in her house maidens learning the art. Vasantasenā is emancipated from her profession of courtesanship and allowed to marry Cārudatta, a learned Brāhmaṇa, by king Śarvilaka thus : 'Noble Vasantasenā, the king is pleased to confer on you the title of wife.'<sup>1</sup>

Actors are mentioned as welcome guests of princes and intimate friends of poets of status. Bāṇa enumerates actors and actresses among his friends in the *Harṣacarita*.<sup>2</sup> Bhartṛhari refers to their friendship with kings.<sup>3</sup>

Girls belonging to the higher order of the society, like Mālavikā, were instructed in the art of representation. Mālavikā was made a present of to the queen by her brother, Vīrasena, deeming her fit to be initiated in fine arts.<sup>4</sup>

In the *Ratnāvalī*, the manager was treated with great respect by kings and requested to act the drama, in the following words: 'Manager, enough of prolixity. Today, on the occasion of the spring festival, called with great respect by the multitude of kings who have come here from various regions and who depend on the lotus-like feet of our king, the illustrious Śrīharṣa, I was told that the *Ratnāvalī* should be enacted on

---

1. Mṛch X. P. 252.

2. Harṣacarita I. P. 19.

3. Bhartṛhari 'subhāṣitatriṣaṭi'. Vairāgyaśatakaṁ iii. 56.

4. Māl I. P. 9.

the stage.' Here the words 'great respect' signify that actors were held in high respect by kings.<sup>1</sup>

Bhavabhūti in the preludes to two of his dramas asserts his friendship with actors.<sup>2</sup> Men, who could effectively declaim the stanzas of Bhavabhūti, must have had both education and culture of a high degree and must have been very different from acrobats and jugglers, dancers and others, whose humble occupations account for the censures of law books and the *Arthaśāstra*. When we think that Bharata, the first teacher of the art of acting and the theatre-director of the stage of the gods, is subsequently designated a *muni* and that in later days men and women belonging to the higher strata of the society appeared on the stage, the conclusion is warranted that respect for the position of actors and their profession was gradually rising.

---

1. Rat I. P. 5.

2. MM Prelude Prose P. 8; Mahāvīracarita Prelude Prose P.8.

## CHAPTER VIII

# CONVENTIONS

### A. Pūrvaraṅga

Bharata devotes one entire chapter of the *Nāṭyaśāstra* to describing preliminaries of a play [ *pūrvaraṅga* ]. According to him *pūrvaraṅga* bears this name because ceremonies connected with it are performed at the beginning of the presentation of play on the stage.<sup>1</sup> According to the *Sāhityadarpaṇa*, the term *pūrvaraṅga* is significant as it includes that which the actor does before the play is presented in order to remove all hindrances.<sup>2</sup> The *Avaloka* on the *Daśarūpa*, on the other hand, explains the word as derived from *rañj*, to satisfy, and says the name owes its origin to the fact that it satisfies one beforehand.<sup>3</sup>

According to Bharata the *pūrvaraṅga* has 20 different constituent parts. Out of these the first nine are to be performed behind the curtain and the rest on the stage.<sup>4</sup>

*Pratyāhāra*, bringing in of the musical instruments [ *kutapa* ]; *avataraṇa*, placing of singers [ *gāyaka* ]; *ārambhā*, beginning of the rehearsal song of the chorus; *āśrāvāḥā*, tuning of instruments which are played upon by striking [ *ātodya* ]; *vaktrapāṇi*, tuning of the wind instruments [ *vādya* ]; *parighaṭṭanā*, tuning of the stringed instruments [ *tantrī* ]; *saṃghoṭanā*, meant for rehearsing the use of different hand poses for indicating the time-beat; *mārgāsārīta*, playing together of different instruments; *āsārīta*, entrance and practice of the dancing girls;—All these are done behind the curtain.

The parts of the *Pūrvaraṅga* to be played on the stage are mentioned below. First comes *gīta*, song in praise of gods

---

1. NS—KM, KSS, GOS V. 7.

2. SD VI. Sūtra 10. P. 293.

3. *Avaloka* on DR III. 2. P. 63.

4. NS—KM V. 17-30; KSS V. 17-30a; GOS V. 17-30.

and then *utthāpana*, song on the setting up of the banner of Indra [*jarjara*]. Here the *sūtradhāra* appears, followed by two *pāripārśvikas* who carry a water jug [*bhṛṅgāra*] and the banner of Indra. The *sūtradhāra* strews flowers, brings in Indra's banner and cleanses himself with the water of the jug. After this, is performed *parivartana*, stalking round the stage with praise of the guardians of the world [*dikpālāstuti*] and adoration of Indra's banner [*jarjarapūjā*]. *Nāndī*, praise or a benediction is next recited by the *sūtradhāra* in a middling tone. It consists of 12 or 8 *pādas* and after each *pāda*, both the *pāripārśvikas* say *evamastu* [so be it]. Then follow *vardhamāna*, an increasing intensity of *tāṇḍava* [manly dance]; *śuṣkāvakṛṣṭa*, an introduction in which the *sūtradhāra* recites some verses in a sonorous voice; the *jarjaraśloka*s, in praise of the god whose worship is being celebrated, or in praise of a king or of Brahmā; *raṅgadvāra*, when the play [*abhinaya*] begins, the *sūtradhāra* recites a new verse and bows before Indra's banner [*jarjara*]; *cārī*, different paces and gestures with an erotic sense; *mahācārī*, similar paces, but more impetuous in degree; *trigata*, conversation between the *sūtradhāra*, the *vidūṣaka* and a *pāripārśvika* in which the *vidūṣaka* speaks all kinds of nonsense; *prarocanā*, announcement of the contents.

According to Bharata these are the constituent parts of a regular *pūrvaraṅga* or a *calurasra pūrvaraṅga*. The *tryasra pūrvaraṅga* is similar but shortened, while in the *citra* [variegated] *pūrvaraṅga* strewing of flowers and dance of the gods etc. are added.<sup>1</sup>

The *pūrvaraṅga* is not a part of the drama proper. Bharata issues a note of warning that there should be some limit to the dance, song and instrumental music introduced so that the audience may not lose patience.<sup>2</sup>

Bhāsa's dramas, the earliest specimen of Sanskrit play, begin with the direction, '*nāndyante tataḥ praviṣati sūtradhāraḥ*'

1. NS—KM V. 139-144; KSS V. 158b-160a, 152-155; GOS V. 155-161.

2. NS—KM V. 146-148, I. 23; KSS V. 160b-162, 158a, I. 57; GOS V. 164b-167a, I. 56b-57a.



[ i. e. after the introductory music is over, the stage manager enters ]. This is certainly an old specimen of introduction, according to which the *nāndī* did not form part of the drama proper. In Bhāsa's dramas there are no *prarocanās* or intimations of the contents.

The well established form of beginning in later dramas shows that the practice had become gradually different, as the *nāndī* and the *prarocanā* were incorporated in the drama proper and were composed by the author of the drama. The *pūrvaraṅga* was greatly shortened by its inclusion as a constituent part of the drama, but its principal parts, including dancing, singing and instrumental music were retained. The usual saying *alam ativistareṇa*—enough of formalities—and similar remarks in the beginning of dramas point to this fact. The *Sāhitya-darpaṇa* remarks that in all cases the *nāndī* must be retained.<sup>1</sup>

After Bhāsa almost all Sanskrit plays begin with the *nāndī*. This is followed by the prelude, *prastāvanā*. This formality of the *pūrvaraṅga* is observed in every kind of drama. Hence it is dealt with here in some detail.

The *Nāṭyaśāstra* prescribes that the *nāndī* should have words invoking blessings [ *āśīrvacana* ]. It should have eight or twelve feet [ *pādas* ], should be poetically beautiful and should be holy or approved by gods.

The *nāndī* should be in honour of gods, Brāhmaṇas, the king, or it should please these persons. There must be two *pāriṣārvikas* by the side of the *sūtradhāra*. While the *sūtradhāra* recites the *nāndī* in a middle tone, the *pāriṣārvikas* say *evamastu* [so be it] at the end of every foot [ *pāda* ]. There is also a note that by the proper execution of the *nāndī*, *candra* [ moon ] is pleased.<sup>2</sup>

According to the *Abhinayadarpaṇa*, after many kinds of charming tunes have been performed in honour of Gaṇapati, the god of the *muraja* drum and other gods, the dancing girl

1. SD VI. sūtra 10. P. 293.

2. NS—KM V. 50b. 98-104a. KSS V. 51a. 106-112; GOS V. 50b, 109-115a.

should have the permission of her preceptor to begin dressing herself suitably. Then to destroy evils, to protect living creatures, to please gods, to bring edification to the spectators, welfare to the leader of the *naṭa* group, protection to the dancing girl and to make the teaching of her preceptor fruitful, she begins offering flowers to gods.<sup>1</sup>

According to the Ādibharata, in addition to Bharata's *āśīrvacana* [ words of blessings ], the *nāndī* should include salutation [ *namaskriyā* ]; it should suggest the plot of the play [ *kāvyaṛthasūcaka* ] and should have eight or ten *pādas*.<sup>2</sup>

In the *Agnipurāṇa*, we find that the *nāndī* is one of the 22 divisions of the *pūrvaraṅga*. It adds to the words *āśīrvacana*, of Bharata, prayers to elders and benedictions of cow, Brāhmaṇa and King etc. [ *gobrāhmaṇanṛpādi* ].<sup>3</sup>

Abhinavagupta has discussed the various characteristics of the *nāndī* and has clarified the meanings of certain terms used by Bharata in this connection. He explains the word *nitya* as suggesting the daily recital of the *nāndī* i. e. the *nāndī* should be recited every day the drama is performed, unlike some other items of the *pūrvaraṅga*, which may not be practised daily. According to Bharata, the *nāndī* should be in honour of a god, Brāhmaṇa and king. To this, Abhinavagupta has added that it should also be in honour of a *prekṣāpati* i. e. the guest of honour. He adds a note that this *nāndī* is called *prarocanā* when it occurs as an element of *bhāratīvṛtti*.<sup>4</sup>

In the *Daśarūpa*, we find that the *nāndī* should please the audience and that the verses must be sweet.<sup>5</sup> In the *Nāṭakalakṣaṇaratnakoṣa*, it is stated that the *nāndī* is to be introduced by the stage manager.<sup>6</sup>

In the *Nāṭyaśāstra* there is an illustration of the *nāndī* as given by Bharata. The authors of the *Nāṭyadarpaṇa* tell us that

1. AD 31-34. PP. 4-5.

2. Ādibharata as quoted by Rāghavabhaṭṭa in his commentary on Śāk. P. 4.

3. Agnipurāṇa CCCXXXVIII. 8-9.

4. Abh. Bh. I. P. 219.

5. DR III. 4a. P. 63.

6. NLR LL. 1089-1100, PP. 46 and 47.

the *nāndī* should have six or eight *pādas* and add the terms *Sarasvatī*, *kavi* and *guṇotkirtana* [ praises of merit ] to Bharata's list. The *nāndī* is supposed to remove obstacles in the way of the performance of a play. The *Nāṭyadarpaṇa* also says that the *nāndī* may be composed by the poet or the troupe manager and that it may be recited by the *sūtradhāra*, *sthāpaka* or *pāriparśvikas*.<sup>1</sup>

According to the *Bhāvaṇṇaprakāśana*, the *nāndī* is derived from Nandi, the bull of Śiva. The dance of the bull in a particular form became worthy of representation. Its worship in that form is called *nāndī*. It is also known as *nāndī* because it delights the audience. In this context the word *nāndī* is derived from *nand*, to please. There must also be the word *candra* [ moon ] or its synonym in the *nāndī* verse or the poet, at any rate, should indicate or suggest it. The *sūtradhāra* should recite it in a tone neither high nor low [ *madhya svara* ] and there should be eight or twelve *pādas* or sentences.<sup>2</sup>

In the definition of the *nāndī*, the *Pratāparudrīya* adds the words direct or indirect suggestion of the plot to the words of Ādibharata and others [ *kāvyaṛthasūcaka* ]. The *nāndī*, according to it, may have eight, twelve, eighteen or twentytwo *pādas*.<sup>3</sup> The *Rasārṇavasudhākara* gives the same description as the *Pratāparudrīya* with a difference in the number of *pādas*. According to the *Rasārṇavasudhākara*, there may be eight, ten or twelve *pādas*.<sup>4</sup>

The *Sāhityadarpaṇa* quotes the *Nāṭyaśāstra* and adds that the *nāndī* should have words signifying auspicious objects like *śaṅkha* [ conch ], *candra* [ moon ], *abja*, *koka* and *kairava* [ different kinds of lotuses ] and should contain eight or twelve *pādas*.<sup>5</sup>

In the commentary on the *Abhijñānaśākuntala*, Rāghava-bhaṭṭa has quoted definitions of the *nāndī* as given in most of

1. ND IV. PP. 192-193.

2. BP VII, LL. 19-22. P. 196, LL. 1-14. P. 197.

3. PR 34 and following prose PP. 87-88.

4. RS III. 137-138 and examples PP. 265-266.

5. SD VI. II. P. 293.

the works on dramaturgy and has added one more definition according to which the *nāndī* is composed of poems which please the audience, poets and actors. Here, too, the *nāndī* is derived from *nand*, to please.<sup>1</sup>

Thus the *nāndī* should have the following characteristics. It should include *āśīrvacana*, *namaskriyā*, *kāvyaṛthasūcana*; should be in beautiful verse; *vedanirmita*; should be in honour of gods, Brāhmaṇas, kings, *sabhāpati*, audience, actors; should be recited every day the drama is performed; should have six, eight, twelve, eighteen or twentytwo *pādas*; the *sūtradhāra* should recite *nāndī* in a tone neither high nor low and two *pāripārsvikas* should stand on his sides and utter the word *evamastu* [ so be it ] at the end of every *pāda*; the moon is pleased by a proper recital of the *nāndī*; it should contain words like *candra*, *śaṅkha*, *abja*, *koka*, *kairava* or their synonyms; should contain *guṇotkīrtana*; it is derivable from *nand*; it should be accompanied by offerings of flowers; and be composed by a poet or stage manager.

### B. Religious Ceremonies

The entire edifice of the Sanskrit play has a fundamental religious basis. The *Nāṭyaśāstra* was spoken of as the fifth *veda* and Bharata, who wrote it, was regarded as the stage manager of the gods. He is said to have received a revelation of the dramatic art from Brahmā, the creator, who entered into meditation and from the depths of the divine thought brought forth the arts of drama, music and dance for the joy of the universe. According to the *Nāṭyaśāstra*, the *Nāṭyaveda* aimed at the attainment of the four *puruṣārthas* or objects of human pursuit, namely *dharma* [ ethical and spiritual development of the individual ], *artha* [ social and civic life and the acquisition of wealth ], *kāma* [ conjugal love and sensual pleasure of environment ] and *mokṣa* [ attainment of salvation ].<sup>2</sup>

Bharata pays great attention to the forms and ceremonies for worshipping the presiding deities of the theatre. They

1. Rāghavabhaṭṭa's commentary on Śāk I. P. 4.

2. NS—KM, KSS, GOS I. 14.

are : *Candra* [ moon god ], *Lokapālas* [ guardians of the world ], *Mārutas*, *Mitra*, *Agni* [ fire god ], *Varuṇa*, *Ādityas*, *Rudras*, *Bhūtas*, *Apsarasa*, *Yakṣiṇya*, the Ocean god, *Kṛtānta*, *Nāgarāja*, the Rod of Yama, *Niyati*, *Mṛtyu*, *Indra*, *Vidyut* [ lightning ], *Yakṣas*, *Piśācas*, *Guhyakas*, *Vajra*, powerful *Ārjara*, *Brahmā*, *Viṣṇu*, *Śiva*, *Kārtikeya*, *Sarasvati* and *Oṃkāra*. The above-mentioned deities should be worshipped with *bali* [ offerings ] and sacrifices.<sup>1</sup>

Offerings, sacrifices, *mantras*, herbs, recitation and food [ *bhakṣya* ] should be offered on the *nāṭyamaṇḍapa*. The show should not begin before the offerings are made. If this rule is disregarded, the knowledge of the performer becomes futile and he goes to the nether world. So the stage manager should make the offerings with all ardour. If no worship is offered the dancer or financier, whoever he may be, is degraded. According to the dramaturgic treatises, he who makes offerings gets the desired object and goes to heaven.<sup>2</sup>

Most elaborate forms of worship are prescribed in connection with the erection of the theatre. *Brāhmaṇas* are to be fed at every turn, sometimes with rich and sometimes with ordinary food. In the *puṣya* constellation, a white thread, strong enough to measure the building, should be laid round the theatre. If the thread is broken into two pieces, the death of the proprietor is indicated; if it is broken into three, a political disorder will occur in the land, and if it is broken into four, the master of the dramatic art will perish. To avoid these, measurement of the theatre should be done on an auspicious day and *Brāhmaṇas* propitiated. Deformed and ugly persons should on no account be employed in any work concerning the building. Monks and mendicants should not be allowed to approach the building.

Bharata gives the correct invocation to be used when laying the foundation of the theatre thus : 'Oh pillar ! as the *Himālayas* are immovably fixed on the ground, be thou even like them.' In the *Rohiṇī* or *Śravaṇa* constellation the

---

1. NS—KM I. 49-64a; KSS I. 83b-98; GOS I. 82b-97.

2. NS—KM I. 87-93; KSS I. 119-125; GOS I. 125-131.

pillars should be laid and the director of the theatre should observe fast for three days. Jewels, cows and clothes should be distributed in charity.

While erecting the *mattavāraṇīs*, garlands, clothes and perfumes should be given away in charity. Offerings liked by *bhūtas* should be given to the different castes [ *varṇas* ]. Milk should be offered under the pillars of the *mattavāraṇīs*. Food—rice mixed with pulses—should be given to Brāhmaṇas.

When constructing the *raṅgaśīrṣa*, jewels and precious stones were laid underneath this [ *raṅgaśīrṣa* ] by expert builders. On the eastern side of the *raṅgaśīrṣa* diamond is to be kept ; lapis lazuli on the south ; emerald on the west, coral in the north and gold in the centre.<sup>1</sup>

Bharata devotes the third chapter of the *Nāṭyaśāstra* to a detailed description of the worship of the gods of the stage. When construction of the theatre is over, cows should live there for a week and Brāhmaṇas recite *mantras*. The director is to be initiated and after a three-day fast should salute with folded hands prominent gods, divine beings, *rājaraṣis*, *munis*, and dramatic obstacles and success.

Of the varied aspects of the preliminaries, special importance seems to have been attached to the praise of the world's guardians [ *dikpālāstuti* ] and reverence to Indra's banner. *Ājara* or the setting up of the flag-staff of Indra is the most important of the sacred rites on the stage. The flag-staff is erected in the stage in the evening after the *mantras* have been chanted the day preceding the festivity. On the day of the festivity, all the deities and the flag-staff are worshipped. Brahmā, Śiva, Viṣṇu, Kārtikeya and the three great serpents Śeṣa, Vāsuki and Takṣaka are supposed to preside in the five knots of the flag-staff. The first part of the staff is wrapped in white linen, the second in blue, the third in yellow, the fourth in red and the fifth in multi-

---

1. NS—KM II. 30b-35, 38-57a, 62b-63; KSS II. 28b-34a, 36b-56a, 62-69a, 74b-75; GOS II. 33b-39a, 41b-61a, 67-74a, 79b-80.

coloured cloth. Different deities are invoked with different *mantras* according to the *Nāṭyaśāstra*.<sup>1</sup>

### C. Dialects

The atmosphere in Sanskrit plays is characteristically romantic, but a curious element of realism is introduced by the use of many dialects, according to the status of various characters. The gods, most of the Brāhmaṇas and princes spoke pure Sanskrit and female characters *Prākṛta*. The audience, which could follow the minute variations of dialects, enjoyed this introduction of realism. Dramas like the *Dūtavākya*, where pure Sanskrit is used, or like the *Karpūramañjarī*, where pure *Prākṛta* is used, are indeed very rare.

The use of specific dialects for characters seems to be determined on the strength of a rule of Viśvanātha, who, in the *Sāhityadarpaṇa* says : *Yaddeśam nīcapātram tu taddēśyam tasya bhāṣitam*.<sup>2</sup> But it is not always correct to say that because a character speaks *Śaurasenī* he or she must be the native of Śūrasena country. The dialect of a character appears to have been fixed by convention, and although in the *Mṛcchakaṭīka* this rule is observed with fair rigidity, one cannot say that it is universal.

According to theorists, Sanskrit is the language of members of the higher castes such as kings, Brāhmaṇas, learned men, ministers and generals. Occasionally the senior queen, female ascetics and members of the harem also speak Sanskrit.<sup>3</sup> Such is the case with some allegorical female characters in the *Prabodhacandrodaya*<sup>4</sup> and similar other dramas. Sanskrit should also be used when people speak on war and peace, on omens and similar subjects. In the

---

1. NS—KM III. 1-15; 31b-32a, 65-67a, 74, 81-83, 93; KSS III. 1-16, 33b-34a, 75-77a, 84, 92-94, 104; GOS III. 1-17a, 34, 75b-77, 84b-85a, 92b-95a, 104b-105a,

2. SD VI. 168 Sūtra. P. 366.

3. NS—KM XVII. 31, 36b-42a; KSS XVIII. 29b-30a, 34b-40a; GOS XVII. 32b-33a, 38-43; DR II. 64. P. 61; SD VI. Sūtra 168. P. 365.

4. Prabodhacandrodaya V. PP. 167-168.

*Pañcarātra*, Bṛhannālā actually turns from *Prākṛta* to Sanskrit to describe a fight.<sup>1</sup> Women, children and men in low stations speak *Prākṛta*.<sup>2</sup>

The rules laid down by Bharata for the use of *Prākṛta* dialects in the Sanskrit plays are simple. According to him, —and Sāgaranandin<sup>3</sup> supports him,—the main *Prākṛta* dialect to be used in dramas must be *Śaurasenī*. However, he allows latitude to writers to use other dialects as the dramatic form of poetic composition draws its characters from different countries. Bharata enumerates seven principal *Prākṛta* dialects for use in dramas. They are : *Māgadhi*, *Avantijā*, *Prācyā*, *Śaurasenī*, *Ardhamāgadhi*, *Bāhlikā* and *Dākṣiṇātyā*. He gives also a list of sub-dialects [ *vibhāṣās* ] such as *Śākārī*, *Ābhīrī*, *Cāṇḍālī*, *Śābarī*, *Drāviḍī*, *Audrī* and *Vānaukasī*.<sup>4</sup> *Mahārāṣṭrī* has not been mentioned by Bharata nor by Sāgaranandin but by Viśvanātha in the *Sāhityadarpaṇa* which is a late work belonging to about 1380 A.D.<sup>5</sup> *Mahārāṣṭrī* has in fact no place in Sanskrit dramas and in early days its use seems to be restricted to poetic compositions only.

The principal *Prākṛta* dialect used in the dramas was *Śaurasenī*, both for prose and verse. It could be used by anybody in the drama. It was famous as the popular dialect of the Doab of the Yamunā and Gaṅgā. According to theorists, it is the language of the heroine, her friends and attendants and generally of women of good families. It is also spoken by ordinary men.

The *Vidūṣaka* and others spoke *Prācyā*, which was hardly different from *Śaurasenī*, while rogues employed *Avantijā*.

*Ardhamāgadhi* was spoken by slaves [ *ceṭas* ], sons of kings [ *rājaputras* ] and masters of guilds [ *śreṣṭhins* ].

1. *Pañcarātra* II. 29-32; P 400.

2. NS—KM XVII. 32; KSS XVIII. 33b-34a; GOS XVIII. 30b-31a.

3. NLR LL. 2148-2157. P. 90.

4. NS—KM XVII. 46-55; KSS XVIII. 44-54a; GOS XVII. 47b-56; SD VI. 168. PP. 365-366.

5. SD VI. 168 sūtra. P. 365.



*Māgadhi* was spoken by inmates of the royal harem, by diggers of subterranean entrances, inn-keepers and watchmen. It was occasionally used by the hero while in difficulty for self-protection. According to the *Daśarūpa*, *Māgadhi* and *Paiśāci* were the languages of the low people.<sup>1</sup>

Bharata says *Dākṣiṇātyā* should be spoken by warriors, police officers and gamesters. *Bāhlikā*, according to the same source, is the native speech of the Khasas who belong to the north.

Coming to the use of sub-dialects or *vibhāṣas*, *Śākārī* was assigned to the *Śākāra* and the Śakas and other groups of the same nature, and *Cāṇḍālī* to the Pulkasas and the like. *Ābhīrī* or *Śābarī* was prescribed for those who lived in places where elephants, horses, goats, sheep, camels or cows were kept. *Drāviḍī* was the speech prescribed for forest-dwellers and the like. It has been observed that *Ābhīrī* and *Drāviḍī* dialects are not available in any extant dramas. Generally cowherds, outcastes and foresters used their own forms of speech. Even mischievous imps had their appropriate jargon and *Piśācas* or goblins, when introduced on the stage, spoke a dialect of *Prākṛta* known as *Paiśāci*.

The commentary of Pṛthvidhara on the *Mṛcchakaṭika* has shown vividly the *Prākṛta* dialects used in dramas<sup>2</sup> and has particularly pointed out that *Mṛcchakaṭika* uses four principal *Prākṛta* dialects and three sub-dialects—*Śaurasenī*, *Āvantī* or *Avantijā*, *Prācyā*, *Māgadhi*, *Śākārī*, *Cāṇḍālī* and *Ḍhakkī*.

#### D. Injunctions and Prohibitions

We now proceed to examine some of the peculiar but important injunctions and prohibitions laid down by dramaturgic treatises to be observed on the stage.

In order to maintain an idealistic atmosphere not only was a tragic end forbidden but other important and far-reaching restrictions were imposed. Propriety and decorum

---

1. DR 65-66. PP. 61-62.

2. The commentary of Pṛthvidhara on *Mṛch* PP. 1-2.

were emphasized. Grim realism was not to be presented, for this would not exalt the mind. Painful, disgusting and debasing scenes were to be avoided. Long journeys, murders, fights, revolts in kingdoms, sieges, eating, bathing, kissing, embracing, loosening the *nīvi* and pressing of breasts were not to be represented on the stage.<sup>1</sup>

The older dramatists, however, acted with greater freedom. Thus in the *Ūrubhaṅga* of Bhāsa, Duryodhana dies on the stage<sup>2</sup> and in the *Mṛcchakaṭika*, Vasantasenā is strangled by Śakāra.<sup>3</sup> The injunctions apparently came to be strictly adhered to in later times.

The Sanskrit drama does not entirely exclude tragedy. It excludes the direct representation of death as an incident and insists on a happy ending. It recognizes some form of tragedy in its pathetic sentiment [ *karuṇarasa* ] and love in separation [ *vipralambha sṛṅgāra* ]; the tragic interest is almost central in some plays. In the *Mṛcchakaṭika* and the *Abhijñāna-śākuntala*, for instance, the tragedy does not indeed occur at the end but earlier, and in the *Uttararāmacarita*, where the tragic element prevails throughout, it occurs in an intensive form at the beginning of the play. Thus the foremost characteristic feature of Sanskrit plays is the total absence of the distinction between tragedy and comedy. It is a mixed composition in which joy and sorrow, happiness and misery, seriousness and levity are mixed, and in which good and evil, right and wrong, truth and falsehood are blended. But towards the end harmony is always restored and order succeeds disorder, tranquillity agitation and the mind of the spectator is made peaceful by the happy termination of the story.

Only sweet and exalted sentiments and emotions are to be presented on the stage but minute details of the subject that are deficient in sentiments and unsuitable are to be reported. Things that are not to be represented on the stage

---

1. NS—KM XXII. 279-283; KSS XXIV. 285-289.

2. *Ūrubhaṅga* I. 35. P. 498.

3. *Mṛch* VIII. Prose P. 183.

and events that extend over a long time are to be related in inter-acts called *arthopakṣepakas*.

Five kinds of inter-acts are distinguished : *viṣkambhaka*, *praveśaka*, *cūlikā*, *aṅkāvatāra* and *aṅkamukha*.<sup>1</sup>

The *viṣkambha* or *viṣkambhaka* relates, at the beginning of an act, events which are happening or which have happened. When a longer interval has elapsed between two acts or important events have happened, the new act is introduced with a *viṣkambhaka*. The *Nāṭyaśāstra* lays down that it should be introduced in the first of the five joints [ *sandhi* ]. This practice is not always followed in dramas. What matters is the kind of persons appearing on the stage. These are either the people of the middle class, in which case the *viṣkambhaka* is called pure [ *śuddha* ] and is in Sanskrit, or persons appear with people of a lower status in the mixed *viṣkambhaka* [ *saṅkīrṇa* ] with *Prākṛta* as the language.

The *praveśaka* in relation to the *nāṭaka* and the *prakaraṇa* is to occupy a place between two acts. It should not consist of the exploits of the superior and the middling characters and there should be no exalted speech in it. Its language should be *Prākṛta*.

Voices behind the curtain which relate facts constitute *cūlikā*.

The remaining two *arthopakṣepakas* are of a somewhat different kind. The *aṅkāvatāra* comes between two acts or within an act and relates to the purpose of the germ [ *bīja* ]. Bharata explains an *aṅkamukha* as a preceding allusion to the beginning of an act when this act is separated [ *viśliṣṭa* ] from it. The *Daśarūpa* calls it *aṅkāśya* and explains it as an announcement of the beginning of an act at the close of the preceding one when the matter of the following act is not an immediate continuation of the earlier one.<sup>2</sup> The *Sāhityadarpaṇa* observes, however, that some authorities take it as an *aṅkāvatāra* and

1. NS—KM XIX. 104-111; KSS XXI. 108-116.

2. DR I, 58-63 a.

explains *anīkamukha* as an allusion to the entire following contents of a piece inside an act.<sup>1</sup>

According to the dramatic rules [*nāṭyadharmā*] some parts of the matter in hand are to be heard by all persons present on the stage while other parts are not expected to be so heard. The former is known as 'aloud' [*prakāśa*] and the latter 'aside' [*svagata*]. An 'aside' is also called *ātmagata*. The adverbial forms *ātmagata* and *svagata* occur frequently in stage directions. Other forms of addresses are personal address [*janānta* or *janāntika*] and that spoken in confidence [*apavārita*]. Personal address is mutual conversation in the presence of other persons who are excluded with a gesture by the hand with three fingers raised [*tripataka*]. A confidential speech [*apavārita*] is a secret shared by a person turning round to another and is meant to be heard only by the person addressed. Then there are imaginary conversations [*ākāśabhāṣita*]. When an actor says "What do you say" without the presence of any other actor and appears as if he hears the answer, it is called the *ākāśabhāṣita*.<sup>2</sup> This device is frequently employed in a monologue play [*Bhāṇa*].

The *Nāṭyaśāstra* prescribes a set of words for calling the different characters according to their position. The words are given in the following : Gods, great sages, persons well versed in different *vedas* and priests were called by men and women alike as '*bhagavan*' [holy one]. Kings were called by Brāhmaṇas at their pleasure by their names. A Brāhmaṇa was usually called '*arya*' [noble one]; a king, '*mahārāja*' [great king]; a teacher, *ācārya* [professor]; and an old person, '*tata*' [father]. A minister was called '*amātya*' [councillor] or '*saciva*' [minister] by a Brāhmaṇa and '*arya*' [sir] by others. Persons of equal status were called by their names. The lord of a chariot was addressed by the charioteer as '*āyusman*' [long-lived one] and an ascetic, '*sādho*' [blessed one]. A pupil or a son was addressed as '*vatsa*' [child],

1. SD VI, Sūtras 36-42, PP. 311-313.

2. SD VI, Sūtra 161, P. 361; DR I, 63b-67.

'*putraka*' [ son ], '*tāta*' [ a term of endearment ] or by the name of his *gotra* by father or preceptor. A king was called '*deva*' [ lord ] by servants and people in general, and as '*bhaṭṭā*' [ *Pṛākṛta* form of *bhartā* ] [ sire ] by members of his harem and '*rājan*' [ king ] by *ṛṣis* [ sages ]. The *vidūṣaka* was called *vayasya* [ friend ] by the king. A husband was addressed as '*āryaputra*' [ noble one's son ] by his wife in her youth. Wives of king were called '*bhaṭṭinī*' [ mistress ], '*svāminī*', [ madam ] and '*devī*' [ lady ] by members of the harem according to their status. A salve girl was called '*hañje*' [ hey child ] and a courtesan '*ajjukā*'; an old woman '*attā*' and the wife '*priye*' [ my dear ] in an erotic sentiment. These conventions were faithfully followed in Sanskrit plays.<sup>1</sup>

Sanskrit dramas are often very long. There are Sanskrit dramas like the *Bālarāmāyaṇa* of Rājaśekhara which are equal in volume to three dramas of Shakespeare. Dramas are usually divided into acts. The common word for an act is *aṅka*; only in the sub-class, *saṭṭaka*, the act is called *javanikāntara*. According to Bharata, an *aṅka* is *rūḍhiśabda* i. e. he knows no etymology.<sup>2</sup> The *Avaloka* on the *Daśarūpa* says that the *aṅka* signifies the mother's lap, because the act helps the development of the theme.<sup>3</sup>

The number of acts varies according to the kind of drama. In the principal classes there are at least five and at the most ten acts. In each act the hero must appear, and the number of persons present on the stage should not be too many. Three or four was considered to be a convenient number. This number was, however, often exceeded. Further, a subject treated in one act should not spread over more than one day. Different matters may be pressed together in one act. Every one should leave the stage at the end of an act.<sup>4</sup>

---

1. NS—KM XVII. 64-91; KSS XIX. 1-29 a; GOS XVII. 65-94 a.

2. NS—KM XVIII. 14; KSS XX. 14; GOS XVIII. 14.

3. *Avaloka* on DR III. 30b-31a. P. 70.

4. DR III. 36b-38. P. 71; NLR LL. 295-304.

The Sanskrit drama lays the greatest importance on the successful portrayal of sentiments and does not insist on quick movement of action. There are very few dramas in Sanskrit which cannot maintain the interest in their action. Ancient rhetoricians held that a dramatist should set before him the creation of sentiment [ *rasodbhāvana* ] as his chief object.<sup>1</sup> Besides the major plot, Sanskrit critics welcome the development of subsidiary incidents and situations. The fundamental 'unity of action' is to be observed, it is true, but only in the Shakespearian sense.

The 'unity of time' was ignored both in theory and practice, but so far as the drama as a whole was concerned, a sense of dramatic propriety demanded that an act should be arranged with a single purpose exemplified by the doings of a single day. Accordingly an act by itself created its own allusion. But between acts many years may elapse; in the *Abhijñānaśākuntala*, Bharata's growth from birth to boyhood is described<sup>2</sup> and in the *Uttararāmacarita* no less than 12 years pass between the first and second acts.<sup>3</sup> Time may slide over 12 or 16 years and the audience may learn of it from the chorus or a short dialogue.

Similarly, the 'unity of place' is not observed. In an act the place is practically the same except for small distances which are suggested by means of some brisk movement on the stage. But change of locality sometimes occurs within the same act, as for example, when a journey through air in a celestial car is performed. Generally in the subsequent act, the scene may open at any other place, even in a celestial region. The concluding stages of a long journey are symbolically represented so that the audience travels and reaches the destination in its imagination and then stays for the act in that locality. The idea of the locality is often picturesquely

---

1. NS—KM VI. Prose P. 62; KSS VI. Prose P. 71; GOS VI. Prose PP. 274-289.

2. Śāk VII. P. 185.

URG II. P. 52.

suggested by means of exquisite poetic descriptions. In plays such as the *Ratnāvalī*, where a royal intrigue is presented, all the acts are confined to the several chambers or gardens of the palace itself. But such a restriction is voluntary on the part of the dramatist and is not imposed on him by the strict rules of dramaturgy.

# CHAPTER IX

## NATURE AND TYPES OF DRAMA

### A. Nṛtta, Nṛtya and Nāṭya

Sanskrit dramaturgists have very early distinguished between the art of histrionics [ *nāṭya* ] and the art of dancing [ *nṛtya* or *nṛtta* ]. As some types of drama are based on *nṛtya* and others on *nāṭya*, it is essential for us to understand clearly these terms before we study the forms of drama and their actual presentation.

*Nṛtta* and *nṛtya* are derived from *nṛt* and *nāṭya* from *naṭ*.<sup>1</sup> There is reference to *nṛt* in the *Rgveda*,<sup>2</sup> while the earliest use of *naṭ* is found in Pāṇini,<sup>3</sup> proving thereby that *nṛt* was an earlier form. *Naṭ* is found to have been used in the senses of dancing and acting.<sup>4</sup> *Nāṭya*, too, has been assigned both these senses in certain works. That *nāṭya* had both these senses of dancing and acting is also seen in the *Mālavikāgnimitra*. It speaks of a *nāṭya* called *chalika*, *chalita* or *calita* which was acted to the accompaniment of dance by Mālavikā. It was certainly not a drama, nor was it a mere *nṛtya* type. As there is express mention of acting according to the prevalent sentiment [ *yathārasamabhinayati* ] after the stanza recited by Mālavikā, it is obvious that it was a type which involved *abhinaya*, and this was the technical nature of *nṛtya*. It seems:

1. Pāṇini IV. 3. 129; V. S. Apte 'Practical Sanskrit English Dictionary.' PP. 534 and 540 : 'naṭ ac iti naṭaḥ'; 'naṭasyedaṁ kṛtyaṁ syaṁ iti nāṭyaṁ.'

2. *Rgveda* X. 18. 3, 29. 2; VIII. 24. 9.

3. Pāṇini IV. 3. 110-111.

4. Siddhānta Kaumudī Tihanta P. 444. 'Naṭa nṛttau. Itthamev pūrvamapi paṭhitam. Tatrāyaṁ vivekaḥ. Pūrvam paṭhitasya nāṭyamaṭhaḥ. Yatkāriṣu naṭavyapadeśaḥ.'



that Kālidāsa recognized the principle that *bhāva* [ emotion ] was at the root of 'nṛtya' as he called two ācāryas, Gaṇadāsa and Haradatta, *bhāvas* incarnate. Thus also *calita* was a nṛtya type. *Nāṭya* here refers to nṛtya.<sup>1</sup> The *Malavikāgnimitra* also recognizes *nāṭya* in the sense of drama. In it *nāṭya* is characterized as a composition in which *lokacarita* [ ways of the world ] are seen and which necessarily refers to the drama proper, rather than to an ordinary nṛtya.<sup>2</sup> The same is the nature of *nāṭya* as used in the *Nāṭakalakṣaṇaratnakosa*.<sup>3</sup> The *Bhāvaṇa* alone describes nṛtta as *rasāśrayam* [ dependent on sentiment ], thus equating it with *nāṭya*.<sup>4</sup>

But in order to understand clearly the import of these terms, we shall have to keep in mind the subtle distinction between *bhāva* and *rasa*. The *Daśarūpa*, after defining nṛtya and nṛtta, adds : 'ādyam padārthābhinayo mārgo deśi tathā param' i. e. the former, a representation of an object, is called 'high style' [ *mārga* ], and the latter 'popular style' [ *deśi* ]. Similar meaning is attached to the words nṛtya and nṛtta in the *Saṅgitaratnākara*, the *Pratāparudriya* and the *Siddhānta Kaumudī*.<sup>5</sup> This clearly makes nṛtya a more evolved form of nṛtta. Nṛtta is the original form of entertainment on which nṛtya was an improvement. Thus nṛtta involved *tāla* [rhythm] and *laya* [tune] only and not *bhāva* [emotion] while nṛtya was essentially connected with *bhāva* [emotion], and producing *bhāva* [emotion] in the minds of the audience is an art far more advanced than mere 'gātravikṣepa' [bodily movement]. Nṛtta, thus, is dance, while nṛtya is mimetic art.

According to the *Nāṭyaśāstra*, nṛtta had no purpose other than delighting people.<sup>6</sup> Abhinavagupta gives the following

1. Māl II. Prose P. 24.

2. Māl I. 4. P. 7.

3. NLR LL. 266-268. P. 12.

4. BP VII. LL. 7-12. P. 181.

5. DR I, 7-9; SR VII. 3b, 17b. 28, 29; PR Nāṭakaprakaraṇa. 1-2, prose PP. 72-73; Siddhāntakaumudī Tiṇanta P. 444.

6. NS—KM IV. 244 to 248; KSS IV. 258b-263a; GOS IV. 268b-273a.

divisions of *nṛtta* : *maṣṇa* [ tender ], *uddhata* [ voilent ], *maṣṇamiśra* [ tender but mixed ], *uddhatamiśra* [ voilent but mixed ], that which includes harmonious motions of hands and feet as in 'recakas and aṅgaḥāras', that which includes music leading to *abhinaya* and that which follows music and *vādyatāla* [ rhythm of musical instrument ] with harmonious motion of the limbs. It will be seen that the first four divisions are based on a principle distinct from the one on which the last three are based. These three can be resolved into two types, one which has pure 'gātravikṣepa' [ bodily movement ] and in which hands and feet are moved in harmony with *bhāṇḍavādyā* [ play on a musical instrument ] and the second which includes *abhinaya*, with harmonious motions of limbs to the tune of music. These two types of *nṛtta* are further taken as distinct from *nāṭya* as is clear from a passage of the *Abhinavabhāratī*<sup>1</sup> which says that the first type, which is *nṛtta*, was quite distinct from *nāṭya* and the second type, which is *nṛtya* was useful in *nāṭya*. Thus both these are distinct from *nāṭya*.

Abhinavagupta says that the *abhinaya* required in *nṛtta-kāvyas* is distinct from the *abhinaya* required in *nāṭya*. In *nṛttakāvyas*, *nartakī*, a female dancer, resorts to *aṅgavyāpāra* [movement of limbs] by proper gesticulation, movement of eyes etc.; but all this is to attract the king in whose presence she dances. Thus the *abhinaya* of a *nartakī* excites the king's passion, but the *abhinaya* of a *naṭa* is to personate somebody and thus he has to show feelings, as experienced by another person and make them manifest on the stage by visible representation. A *nartakī* does not play any role and has nothing to represent visibly. All that she has to do is to attract the king's heart by personal appeal, as it were, through her gestures. She does not put on the dress of any other person. Thus *āhāryābhinaya* is almost absent in her case. Abhinavagupta says his second variety of *nṛtta* is a sort of *abhinaya* but it can produce only

1. Abh. Bh. I. PP. 182-184. 'Prathama bheda laukike svatantranṛtte deṇātātoṣaṇāḍau vā Dvītiyaḥ pūrvaraṅgaavidhau pariśiṣṭanṛttalakṣyatayā.'

*bhāva* [emotion], not *rasa* [sentiment] which would be evoked only by *nāṭya*, and is, therefore, distinct from this second variety of *nṛtta*.<sup>1</sup> Abhinavagupta does not use the term *nṛtya* but signifies both *nṛtta* and *nṛtya* of the *Daśarūpa* by the use of *nṛtta*.

From the point of view of evolution, first comes *nṛtta*, then *nṛtya* and last *nāṭya*. *Nṛtta* is mere dance, *nṛtya* has gestures added to it, while *nāṭya* has speech too. *Nāṭya* incorporated all the three items—dance, music and speech—which are so essential for the successful presentation of a play.

### B. Major Types of Drama [ *Rūpakas* ]

Bharata was conversant with ten kinds of *rūpakas*, and his divisions and descriptions remained authoritative for later theorists.<sup>2</sup> In course of time, they started all kinds of novelties, leading to further divisions and sub-divisions. They have not, however, attempted to alter anything of the ten *rūpakas* described by Bharata. The novel creations have been classified as sub-classes. The *Daśarūpa* gives details about *nāṭikā* for the first time. The *Bhāvaprakāśana* gives an elaborate description of 20 minor kinds of dramas which are styled *uparūpakas*. The *Sāhityadarpaṇa* describes 18 kinds of dramas which are designated as *uparūpakas*. The *Agnipurāṇa* mentions 17 minor kinds of dramas in addition to the ten *rūpakas*.<sup>3</sup> But the recognition of *uparūpakas* signifies that later dramas which did not fit in with Bharata's description of *rūpakas* were treated and systematised as new kinds of drama. With the exception of the so-called *nāṭikā* and *troṭaka*, these sub-classes have exercised no apparent influence upon dramatic literature.

The chief point of distinction between *rūpaka* and *uparūpaka* is that an *uparūpaka* mainly deals with bodily gestures and music, which occupy a secondary position in *rūpaka*. Thus *upa-*

1. Abh, Bh, I. PP. 177-178.

2. NS—KM XVIII. 1-3a; KSS XX 1-3a; GOS XVIII 1-3a.

3. DR III. PP. 72-73; BP IX. PP. 255-268; SD VI. sūtras 281-299. PP. 412-420; Agnīpurāṇa CCCXXXVIII. 1-7.

*rūpaka* places greater emphasis on *kāyābhinaya* [bodily gestures] while *rūpaka* requires *sātvika* temperament and other *abhinayas*. The *Bhāvaprakāśana* very clearly says that *rūpakas* were *rasātmaka* [dependent on sentiment] and *uparūpakas* were *bhāvaśātmaka* [dependent on emotion]. It calls *uparūpakas* as *nṛtyabhedaḥ* [species of *nṛtya*] and *rūpakas* as *nāṭyabhedaḥ* [species of *nāṭya*]. The distinction that *nāṭya* is *vākyaarth-abhinayaśātmaka* and *nṛtya* is *padārthābhinayaśātmaka* also points to the same principle.<sup>1</sup>

Now we shall first describe the major types of drama [*rūpakas*] and then the minor types [*uparūpakas*] as given in the dramaturgic treatises.

*Nāṭaka* : According to Bharata, when the peculiarities of society were sought to be connected with certain gestures or when the actions of gods, ṛṣis, kings or of the members of a society were copied, they came to be called a *nāṭaka*. All *vṛttis* should be in their proper place in a *nāṭaka*. According to the *Daśarūpa*, in a *nāṭaka* the hero should be endowed with attractive qualities of the type known as the self-controlled and exalted [*dhīrodātta*] and should be glorious, desirous of winning fame, very energetic, a preserver of the three *vedas* [*trayī*], a ruler of the world, of renowned lineage, a royal seer or a god. The incident for which he is renowned should be made the principal subject of a play. The subject matter should contain the five elements of action corresponding to the five dramatic stages and should be divided into five junctures [*sandhis*], and these junctures should again be divided into 64 sub-divisions. The *patākā*, *prakarī* and *viṣkambhaka* should be employed. One sentiment, either the heroic or the erotic, is to be made the principal sentiment, all others being made subordinate. The marvellous sentiment should be employed only towards the end.<sup>2</sup>

1. BP VII. LL. 7-8. P. 180, LL. 7-8 P. 181; VIII LL. 11-12. p. 221, LL. 7-9. P. 255.

2. NS—KM XIX. 118, 123, XVIII. 10-12; KSS XXI. 123, 128, XX. 10-12; GOS XVIII. 10-12; DR III. 22b-27, 33b-34a. PP. 69-71; SD VI. sūtra 6. PP. 388-389; PR Nāṭaka-prakaraṇa 32-33. P. 87; NLR. 12-53. PP. 1-3.

*Prakarāṇa* : In the *prakarāṇa* class all the *vyttis* can be employed. According to the *Daśarūpa*, the action should be invented and should take place on the earth. A minister, a *Brāhmaṇa*, or a merchant, of the type known as self-controlled and calm [ *dhīraprasānta* ], undergoing misfortunes and having virtues, the search for pleasure and wealth being his chief objects in life, should be the hero. The remaining features such as junctures, introductory scenes and sentiments are as in the *nāṭaka*. In a *prakarāṇa*, the heroine may be of two kinds : the high-born wife of the hero or a courtesan. In some plays, there is only the high-born woman; in some plays, only the courtesan; and in some, both. High-born women remain indoors, the courtesan outside, and the two should never meet. Because of these varieties of heroine the *prakarāṇa* is of three kinds : *śuddha*, with the wife as heroine; *vikṛta*, with the courtesan; and *saṅkīrṇa*, with both. This mixed variety [ *saṅkīrṇa* ] abounds in rogues.<sup>1</sup>

*Samavakāra* : In the *samavakāra* class also the contents are borrowed from well known [ *prakhyāta* ] legends of gods and demons. It is to consist of three acts presenting the three kinds of deception, the three kinds of excitements or the three kinds of love. The first act should last for 12 *nāḍikās*; the second, for four; and the third, for two; a *nāḍikā* being equivalent to 24 minutes. This kind of drama is called *samavakāra* because various themes are scattered about [ *samavakīryante* ] in it. It may have as many as twelve characters.<sup>2</sup>

*Īhāmṛga* : In the *īhāmṛga* dramas the story is of a mixed type—partly legendary and partly invented. It is divided into four acts with three junctures. The hero and the opponent of the hero may either be human or divine, without restriction;

---

1. NS—KM XVIII. 93-47; KSS XX. 49-53; GOS XVIII. 45-49; DR III. 39-42. PP. 71-72; SD VI. sūtras 253-254. PP. 396-397; PR Nāṭakaprakarāṇa 35. P. 88.

2. NS—KM XVIII. 109-123a; KSS XX. 65b-81a; GOS XVIII. 62b-77a; DR III. 62b-68a. P. 75; SD VI. sūtras 257-258. PP. 399-400; PR Nāṭakaprakarāṇa 46-49. PP. 90-91.

they should be renowned persons and of the type known as self-controlled and vehement, the latter committing improper acts by mistake. There are scenes of wrath but the characters are prevented from dashing into battle by some artifice.<sup>1</sup> The *ihāmṛga*, according to the commentary on the *Daśarūpa*, owes its name to the fact that in it a maiden, who is as difficult to be obtained as a gazelle, is demanded.<sup>2</sup>

*Ḍima*: In the *ḍima* the subject must be well known and all the styles may be employed in it except the gay style. Its heroes, 16 in number, should be gods and *gandharvas*, all of them vehement. It contains all the sentiments except the comic and erotic.<sup>3</sup> According to the commentary on the *Daśarūpa*, the name *ḍima* is equivalent to *saṁghāta* 'injuring', inasmuch as the heroes always come to blows among themselves.<sup>4</sup> It is also to include incidents such as an earthquake, fall of meteors, an eclipse of the sun or the moon, battle, personal combat, challenge and angry conflict.

*Vyāyoga* : To the old popular stage also belongs the *vyāyoga* which derives its name from the fact that in it many men disagree with one another [ *vyāyujyante* ]. The plot does not last for more than one day, and there is a lot of fighting and dissention, in which, however, women play no part. It is a one-act play.<sup>5</sup>

*Aṅka* : An *aṅka* or *utsṛṣṭikāṅka* is a one-act drama. The plot in it is usually to be well known, but it may

---

1. C. O. Haas: 'The *Daśarūpa*' A treatise on Hindu Dramaturgy by Dhanañjaya. P. 105.

2. NS—KM XVIII. 123b-128; KSS XX. 81b-86; GOS XVIII. 77b-82; DR III. 72b-75. p. 76; SD VI. sūtra 260. P. 401; PR *Nāṭaka-prakaraṇa* 52-53. p. 92.

3. C. O. Haas. 'The *Daśarūpa*' A treatise on Hindu Dramaturgy by Dhanañjaya. pp. 100-101.

4. NS—KM XVIII. 130-134; KSS XX. 88-92; GOS XVIII. 84-88; DR III. 57-60a. p. 74; SD VI. sūtras 25a. PP. 400-401; PR *Nāṭaka-prakaraṇa* 42-44. p. 90.

5. NS—KM XVIII. 135-138a; KSS XX. 94-97a; GOS XVIII. 90-93a; DR III. 60b-62a. p. 75; SD VI. sūtra 256. P. 398; PR *Nāṭaka-prakaraṇa* 45. P. 90.

sometimes be otherwise. It relates to one's fall and is to be furnished with male characters other than those who are divine. It abounds in the pathetic sentiment and treats of women's lamentations and despondent utterances at a time after battles and violent fighting have ceased to rage. Small plays inserted into dramas are often designated *aṅkas*.<sup>1</sup>

*Prahasana* : The *prahasana* [ farcical comedy ] has been borrowed from the popular stage. The poet takes the plot from every day life and surrounds it with all kinds of illusions, wordy disputes and dissensions between rogues and worthless persons. There are two kinds of *prahasana*, the pure [ *śuddha* ] and the mixed [ *saṅkirṇa* ]. In the *śuddha* type, Śaiva *gurus* [ *bhagavat* ], Brāhmaṇas and persons belonging to various strata of society appear, each one speaking his special dialect or devoting himself to his special calling. In the *saṅkirṇa prahasana*, courtesans, slaves, eunuchs, parasites [ *viṭa* ] and rogues [ *dhūrtas* ] appear. According to the *Daśarūpa* and the *Sāhityadarpaṇa*, there is yet a third kind of *prahasana*, the distorted type [ *vikṛta* ], where eunuchs and chamberlains appear as gallants.<sup>2</sup>

*Bhāṇa* : The *bhāṇa* has also a popular origin. The piece is acted by a single actor who appears as a man of the world and indeed as the principal *viṭa*. For this purpose he describes partly his own adventures and partly those of others. He uses the monologue [ *ākāśabhaṣita* ] and pretends to see and hear others. He acts, speaks, asks questions and answers on behalf of the imaginary persons. He makes suitable gestures. It is clear that the *bhāṇa* has developed from the pantomime or the musical dance and this explains why *lāṣya* is employed in it. It is also a one-act play.<sup>3</sup>

---

1. NS—KM XVIII. 138b-145; KSS XX. 97b-104; GOS XVIII. 93b-100; DR III. 70b-72a. P. 76; SD VI. sūtra 261. P. 402; PR Nāṭaka-prakaraṇa 51. p. 92.

2. NS—KM XVIII. 146-151a; KSS XX 106-111a; GOS XVIII. 101-107a; DR III. 54-56. P. 74; SD VI. sūtras 276-280. PP. 410-412; PR Nāṭakaprakaraṇa. 38-41. P. 89.

3. NS—KM XVIII. 151b-154; KSS XX. 111b-115a; GOS XVIII. 107b-111a; DR III. 49-51. P. 73; SD VI. sūtra 255. P. 397; PR Nāṭaka-prakaraṇa, 36-37. P. 89.

*Vīthī*: Similar to the *bhāṇa* was the one-act *vīthī*. The *vīthī* was acted by two players. The *Sāhityadarpaṇa* remarks that according to the opinion of an anonymous authority, three actors may also appear, one playing the role of a person placed high in life [*uttama*], another of the middle rank [*madhyama*] and a third one of the lowly [*adhama*]. In all cases the conversations are with imaginary persons [*ākāśabhāṣita*].<sup>1</sup>

### C. Minor Types [Uparupakas]

*Nāṭika*: Bharata refers at one place in the *Nāṭyaśāstra* to a kind of play called the *nāṭī* or *nāṭikā*. In *nāṭikā*, according to the *Daśarūpa*, the plot is taken from the *prakaraṇa*, and the hero, who is a renowned king and of the self-controlled and light-hearted type, from the *nāṭaka*; the principal sentiment is the erotic, with its various characteristics. The heroine is near the hero because of her connection with the harem. Through her hearing and seeing him, a newly awakened passion arises in the hero in regular stages. The hero is apprehensive of the queen. The *nāṭikā* contains the four sub-divisions of the gay style [*kaiśikī*] which are represented by the four acts.<sup>2</sup>

*Troṭaka*: The *troṭaka* has five, seven, eight or nine acts. It deals with gods and men and in each act the *vidūṣaka* appears. The tenth *aṅga* of the *garbhasandhi* is called *toṭaka* or *troṭaka* and this word signifies 'confused, excited speech.' We also hear of a dance called *troṭaka*.<sup>3</sup>

*Goṣṭhī*: The *goṣṭhī* is a one-act drama in which nine or ten ordinary men and five or six women appear.<sup>4</sup>

*Saṭṭaka*: The *Saṭṭaka* is nothing but a *nāṭikā* entirely written in *Prākṛta* without *viṣkamabhaka* or *praveśaka*. The acts are

1. NS—KM XVIII. 155; KSS XX. 115b-117; GOS XVIII. 111b-113a; DR III. 68b-70a. PP. 75-76; SD VI. sūtra 262-263. PP. 403-404; PR Nāṭakaprakaraṇa 50. P. 91.

2. NS—KM XVIII. 106; KSS XX. 62-63; GOS XVIII. 57; DR III. 43-48. PP. 72-73; SD VI. sūtra 281. P. 412.

3. NS—KM XIX. 82; KSS XXI. 89; DR I. 40-41. P. 19; SD VI. sūtra 282. P. 413, sūtra 105. P. 338.

4. NS—KM SD VI. 283. P. 413.



not called *aṅkas* but *javanikāntaras*. Like the *tṛotaka*, the *saṭṭaka* also employs a specified kind of dance.<sup>1</sup>

*Nāṭyarāsaka*: The *nāṭyarāsaka* is likewise a one-act piece with changing time and rhythm [*bahutālalayasthiti*].<sup>2</sup> As far as we can judge, it is a kind of ballet and pantomime.

*Prasthāna*: The *prasthāna* or *prasthānaka* has two acts. The *Avaloka* on the *Daśarūpa* says that the *prasthāna* is a kind of imitative dance [*nṛtyabheda*].<sup>3</sup>

*Ullāpya*: The *ullāpya* is a one-act piece. It is full of fighting and *asragīta*, i. e. background music played from behind the stage with reference to the plot.<sup>4</sup>

*Kāvya*: The *kāvya* contains one-act and is a comedy (*hāsyā*). Different kinds of songs such as *khaṇḍamātrā*, *dvīpadikā* and *bhagnatāla* are prescribed for it. There are amorous speeches. According to the *Avaloka* on the *Daśarūpa*, the *kāvya* is a kind of imitative dance and is an inter-play of song and dance.<sup>5</sup>

*Preṅkhaṇa*: In the one-act *Preṅkhaṇa*, there is no *sūtradhāra*. The *nāndī* and *prarocanā* are sung behind the curtain (*nepathye*).<sup>6</sup>

*Rāsaka*: The *rāsaka* is a one-act piece in which five persons appear. The *Avaloka* on the *Daśarūpa* says that it is a kind of *nṛtya*, with a piece consisting of singing and dancing.<sup>7</sup>

*Samlāpaka*: The *samlāpaka* has one, three or four acts.<sup>8</sup>

*Śrīgadita*: It has one-act. The name *śrīgadita* is assigned to it because the word *śrī* often comes up and because the goddess Śrī appears singing and reciting. According to the

1. SD VI. 284. P. 413.

2. SD VI. 285. P. 414.

3. SD VI. 286. P. 414; Avaloka on DR 8. P. 2.

4. SD VI. 287. P. 415.

5. SD VI. 288 P. 415; Avaloka on DR 8 P. 2.

6. SD VI. 289 P. 416.

7. SD VI. 290 P. 416; Avaloka on DR 8 P. 2.

8. SD VI. 291 PP. 416-417.

*Avaloka* on the *Daśarūpa*, *śrīgadita* is a kind of mimic dance.<sup>1</sup>

*Śilpaka*: The *śilpaka* has four acts in which all the *vṛttis* are allowed and the comic sentiment is excluded. Descriptions of burning grounds [ *śmaśāna* ] and similar things are found in it. Probably it was a kind of pantomime.<sup>2</sup>

*Vilāsikā* : This species of one-act drama is also called *vinayikā* by some writers. Others call it *durmallikā*.<sup>3</sup>

*Durmallī* : The *durmallī* has four acts. The first act lasts for three *nāḍikās* and the *viṭa* appears in it. The second, in which the *vidūṣaka* appears, lasts for five *nāḍikās*, and the third, with the *pīṭhamarda*, lasts for six *nāḍikās*. The fourth is that in which citizens appear for ten *nāḍikās*.<sup>4</sup>

*Prakaraṇikā* : The *prakaraṇikā* is a *nāṭikā* with the hero and heroine drawn from the rank of *sārthavaḥas*.<sup>5</sup>

*Hallīśa* : The *hallīśa* has one act, with the *kaiśikīvṛtti* predominating in it. There is plenty of music and dancing in it.<sup>6</sup>

*Bhāṇikā* : The *bhāṇikā* is a one-act piece. According to the *Avaloka* on the *Daśarūpa*, *bhāṇī* is a kind of musical dance.<sup>7</sup>

The *Abhijñānaśākuntala* and the *Veṇīsaṃhāra* are specimens of *nāṭakas*; the *Mṛcchakaṭika* and the *Mālatīmādhava*, of *prakaraṇa*; the *Pañcarātra* of Bhāsa and the *Samudramanthana* in the *Rūpakaṣaṭkaṃ*, of *Samavakāra*; and the *Rukmiṇīharana* of *ihāmṛga*. The *Tripuradāha* is a *ḍima*, the *Kirātārjunīya* a *vyāyoga* and the *Hāsyacūḍāmaṇi* a *prahasana*. *Bhāṇas* are preserved in the collection known as the *Caturbhāṇi*. The *Ratnāvalī* and the *Priyadarśikā* are *nāṭikās* and the *Vikramorvaśīya* is a *troṭaka*. There are not many examples of *uparūpakas* except *nāṭikās* and *troṭakas*.

1. SD VI, 292 P. 417; *Avaloka* on DR 8 P. 2.

2. SD VI, 294, PP. 417-418.

3. SD VI, 295, P. 418.

4. SD VI, 296, P. 419.

5. SD VI, 297, P. 419.

6. SD VI, 298, P. 420.

7. SD VI, 299, P. 420; *Avaloka* on DR 8, P. 2.

It is needless to trace the gradual development of *upā-rūpakas* and *rūpakas*, because the earliest dramas of Bhāsa and Kālidāsa are in a developed form and we can only suppose that there must have been a large number of dramas, major or minor, in earlier times. These dramas do create an impression that they had already reached the highest stage of dramatic perfection.

# CHAPTER X

## PRESENTATION OF PLAYS

### A. Actual Performance

The *Nāṭyaśāstra* presupposes the existence of a large number of dramas enacted in very early times such as 'The Fall of the Asuras,' 'Churning of the Nectar from the Sea' and 'Burning of the Three Cities.'<sup>1</sup>

Aśvaghoṣa wrote the *Śāriputraprakaraṇa*, portions of which are available in manuscript. The drama was, it is doubtless, intended for religious edification. Its style is simple. It is probable that it was enacted before the public so as to propagate the Buddhist faith. But it cannot definitely be proved.

The discovery of 13 dramas written by Bhāsa went a great way to prove the high pitch of perfection the Indian stage had reached in ancient days. One cannot but agree with Dr. Winternitz when he says that 'Kālidāsa and Bhavabhūti may be greater poets, greater masters of language than the author of these plays, but I know in the whole of Sanskrit literature no drama that could compare as a stage play with any of the 13 plays ascribed to Bhāsa.'<sup>2</sup> Indeed those dramas are the works of a genius who was thoroughly conversant with the technique of the stage and who, it is apparent, knew what actual stage representation is.

The scenes, in which Santuṣṭa, Maitreya, Vasantaka, Śakāra, Sudhākara Madhyama are presented, show that these plays contain sufficient humour essential for a play meant for the stage.

---

1. NS—KM I. 22, IV. 1-10; KSS I. 56, IV. 1-11; GOS I. 55b-56a, IV. 1-11.

2. Winternitz : 'Some Problems of Indian Literature', chapter on *Bhāsa*. P. 129.

Now coming to the dramas of Kālidāsa, we find that the *Malavikāgnimitra* was performed at a spring festival in Vidiṣā. The *Vikramorvaśīya* is found in two recensions. The difference between the two versions comes into bold relief in act IV. While the North Indian version contains a series of *apabhraṃśa* verses and directions on the method in which they should be sung and represented, all this is wanting in the South Indian recension. This *nāṭaka* was also meant for the stage. The *Abhijñānaśākuntala* is the last and the best work of Kālidāsa. It has been translated into almost all the European languages and has been staged in various parts of Europe and India. Even today the *Abhijñānaśākuntala* is staged in all parts of India.<sup>1</sup>

Further the *Avadānaśataka* says that a *nāṭaka* was performed at the bidding of Krakucchanda in the city of Śobhāvatī by a troupe of actors. The director undertook the role of the Buddha and members of the troupe, the roles of monks.<sup>2</sup>

Itsing, who visited India in the last quarter of the seventh century, relates that “king Śilāditya versified the story of the Bodhisattva Jīmūtavāhana, who surrendered himself for a *Nāga*. This version was set to music. He had it performed by a band accompanied by dancing and acting, and thus popularised it in his time.”<sup>3</sup> This might refer to the *Nāgānanda*.

In the *kuṭṭanīmata* of Dāmodaragupta, actual performance of the first act of the *Ratnāvalī* has been described in detail.<sup>4</sup>

There are plays within plays as in the *Priyadarśikā*. Queen Vāsavadattā desires to have a play represented in which her own meeting with Udayana in Ujjain is represented.<sup>5</sup>

1. Māl Prelude I. prose P. 2; Vik Prelude I. 2. P. 3; Śāk. Prologue I. P. 8.

2. Avadānaśataka II. 75. PP. 29-30; Keith : ‘Sanskrit Drama’ P. 43.

3. Itsing : A record of the Buddhist Religion as practised in India and the Malay Archipelago ( A. D. 671-695 ), Translated by J. Takakusa. Oxford, PP. 163-164.

4. Kuṭṭanīmata III, KM edition 852-927, pp. 104-110; Bombay, edition 875-928. pp. 336-368.

5. PD III, pp. 30-43.

Bhavabhūti is known today for his three plays, the *Mahāvīracarita* [ or usually called *Vīracarita* ], the *Malatīmādhava* and the *Uttararāmacarita*. The *Mahāvīracarita* opens with the sentence : 'The audience orders that a drama with certain specified qualities be staged. Later it is stated that the poet is a friend of the actors.' Similarly in the *Malatīmādhava*, it is said that the audience orders the *sūtradhāra* to stage a drama, possessing certain characteristic qualities and the poet entrusts his work to actors out of his spontaneous friendship with them. In the *Uttararāmacarita*, no reference is made to the poet's friendship with actors and the *sūtradhāra* starts requesting the audience to listen to what he has to say.<sup>1</sup>

Rājaśekhara's dramas were meant to be acted. He won fame in the court of the Pratihāras of Kānyakubja. In the *Karpūramañjarī*, which is apparently his first drama, produced at the request of his wife, Avantisundarī, and not at the bidding of the king, his patron, he relates that he bore the title of 'Bālakavi' 'Kavirāja.' He calls himself the teacher of Nirbhayarāja. Nirbhayarāja was Mahendrapāla of Kanauj whose inscriptions dated from 893 A.D.-907 A.D. are available. The *Bālarāmāyaṇa* was produced at his behest, and the unfinished *Bālabhārata* was intended for representation at the court of Mahendrapāla's successor, king Mahipāla, whose inscriptions date from 914 A.D.-917 A.D. References are also available for the staging of the *Viddhaśālabhañjikā*, the fourth drama of Rājaśekhara.<sup>2</sup>

In the *Anargharāghava*, the actor declares that he has come to exhibit a drama superior to that played by a rival and asserts that the dearest desire of a player is to satisfy the public and win back the favour he has lost. This also shows that *nāṭakas* were sometimes enacted in a spirit of competition.<sup>3</sup>

1. *Mahāvīracarita* I. Prologue 2-3 and prose pp. 6-8; MM Prologue prose pp. 8 and 10; URC prelude prose p. 3.

2. Kar, M. I. *Prastāvanā* 11-12. P. 10; *Bālarāmāyaṇa* Prologue PP. 2 and 5; *Bālabhārata* Prologue P. 2; *Viddhaśālabhañjikā* Prologue PP. 4-5.

3. AR Prologue Prose and 3-4. PP. 6-10.

There are more popular dramas, the plots of which are loosely constructed out of well known stories from the *Mahābhārata* or the *Purāṇas*. A dramatist has composed speeches in beautiful verses, the rest being left to the actors on the stage to extemporise. The *Mahānāṭaka* is an instance in point.

The *Dūtāṅgada* of Subhaṭa appears to be the oldest among the later shadow plays. It was represented in honour of Kumārapāladeva on March 7, 1243, and certainly on the orders of the Cālukya lord Tribhuvanapāla in Gujarat.<sup>1</sup> It contains only one act and treats the same subject as is contained in the seventh act of the *Mahānāṭaka*. This shows that portions of plays like the *Mahānāṭaka* were represented on the stage in one form or the other.

Kṛṣṇamiśra, author of the *Prabodhacandrodaya*, says in the introduction to his *nāṭaka* that it was produced at the request of Gopāla in the court of king Kīrtivarman whom Gopāla had reinstated in his kingdom, after the Cedi king Karna, who had driven him out, had been conquered.<sup>2</sup>

In South India even now Sanskrit plays are acted. Bhāsa's dramas, the *Abhijñānaśākuntala*, the *Nāgānanda*, the *Subhadrā Dhanañjaya*, the *Tapti-svayamvara*, the *Mahānāṭaka*, the *Bhagavadajju* and the *Mattavilāsa* are very popular there.

### B. Portrayal of Sentiment [ Rasa ]

Sanskrit plays insist on the portrayal of specific sentiments on the stage, and we should, therefore, clearly understand how each of the sentiments was represented. The eight sentiments found in the Sanskrit dramas are the erotic, the comic, the pathetic, the furious, the heroic, the terrific, the repulsive and the marvellous.

The erotic sentiment [*śṛṅgāra rasa*] has two aspects; it may be in union or in separation. In union it should be represented with joy in the eyes and face, smiles and sweet words, equanimity and rejoicing and pleasant movements of the limbs. In separation it should be accompanied by self-disparagement,

1. *Dūtāṅgada* of Subhaṭa I. P. 2.

2. *Prabodhacandrodaya* Prologue 3 and prose PP. 10-14.

debility, apprehension, envy, weariness, painful reflection, longing, drowsiness, sleep, dreaming, wakening, sickness, derangement, swoons, stupefaction and death.

The comic sentiment [ *hāsya rasa* ] is produced by strange dresses, ornaments, impudence, fickleness, roguery, senseless drivels, ridicule, description of people's defects etc., and is represented by the movement of the lips, teeth, nose and cheeks, by fully expanded or contracted glances, perspiration, grimaces and by keeping the hands on the hips.

The pathetic sentiment [ *karuṇa rasa* ] is represented through tears, lamentation, drying up of the mouth, change of colour, trembling, sighs and loss of memory.

The furious sentiment [ *raudra rasa* ] is shown in bloodshot eyes, perspiration, frowning, gnashing of teeth and biting of lips, blowing of cheeks, wringing of hands, hurling various weapons, cutting asunder the head, the trunk and the arms.

The heroic sentiment [ *vīra rasa* ] is represented by calmness, patience, prowess, pride, enthusiasm, influence, masterfulness and by words expressive of challenge.

The terrific sentiment [ *bhayanaka rasa* ] is represented by the trembling of hands and feet, restless eyes, change of colour and voice, stupefaction, contraction of limbs, palpitation of the heart and by parched lips, palate and throat.

The repulsive sentiment [ *bībhatsa rasa* ] is represented by contortions of the face and eyes, the covering up of the nose and lowering of the head followed by uncertain steps.

The marvellous sentiment [ *adbhuta rasa* ] is represented by eyes opened wide, restless glances, horripilation, perspiration, joy, repeated appreciative exclamations, cries of 'hā, hā' and agitation of fingers or toes.<sup>1</sup>

---

1. NS—KM VI. 15 verse; Prose PP. 63-64; 48 verse; Prose P. 64-67; 68, 72, 74 verses; Prose P. 68; 76 verse; KSS VI. 15 verse; Prose P. 73; 48 verse; Prose PP. 74-77; 68, 72, 74 verses; Prose P. 78; 76 verse; GOS VI. 16 verse; Prose PP. 301-310; 55 verse; Prose PP. 313-314, 318, 320-321, 325, 327; 84, 89, 93 verses; Prose P. 96 verse. See 'English translation of NS chapter VI.' in the NS of Bharata chapter VI, by Subodhacandra Mukerji 1926.



The *Abhijñānaśākuntala*, the *Uttararāmacarita* and the *Veṅṭsaṁhāra* mainly depict the erotic, pathetic and heroic sentiments, respectively. If a *nāṭakamaṇḍalī* wants to have the desired effect upon the public, it should employ actors and actresses wearing appropriate dresses, make-up and acting according to these directions.

### C. Success

There are certain factors indicative of the success of the presentation of Sanskrit plays. *Siddhi* [success] was of two kinds—*Mānuṣī* [human] and *daivikī* [divine] depending on speech, temperament and gestures, and relating to various emotions and sentiments. *Mānuṣī siddhi* [human success] has ten features, and the *daivikī siddhi* [divine success] two; and such features consist mostly of various temperaments expressed vocally [*vāṇmayī*] and physically [*śārīrī*]. *Vāṇmayī siddhi* [vocal success] is of eight kinds : *smita* [smile], *ardhahāsyā* [ordinary laughter] *atihāsyā* [excessive laughter], *sādhukāra* [well done], *ahokāra* [how wonderful], *kaṣṭa* [how pathetic], *pravṛddhanāda* [tumultuous applause] and *avakruṣṭa* [swelling uproar].

A remark or acting through words of double meaning which produces a smile from spectators comes under *smita*. *Ardhahāsyā* is a situation in which one laughs ordinarily. If a joker with his intelligence makes a king weep when he is happy or makes him laugh when he is sad, the spectators laugh heartily. This *siddhi* is called *atihāsyā siddhi*. When the dialogue is fine, the spectators say 'sādhū', 'sādhū' [well done]. This is *sādhukāra siddhi*. A wonderful scene or event that evokes from the spectators the spontaneous exclamation, 'aho' [how wonderful] comes under *ahokāra siddhi*. When a pathetic scene is exquisitely presented the hearts of the spectators melt and they say : *hā kaṣṭam, hā kaṣṭam* [how pathetic]. This is *kaṣṭa siddhi*. When a very wonderful scene is presented, spectators not only exclaim 'aho' [how wonderful] but shout 'bravo, bravo.' This is *pravṛddhanāda siddhi*. When a character rebukes or blames another, spectators also sometimes

the despised and they give expression to their hatred by swelling uproar. This is *avakruṣṭa* or *sādhikṣepa siddhi*.

*Śārīrī siddhi* [physical success] is said to occur when the hair of spectators stand on ends and they rise on account of excessive delight or begin to crack their fingers. This *siddhi* is of two kinds. The first kind follows dialogues exciting wonder or enthusiasm and the second, scenes of quarrels and excitement when spectators become one with the *naṭa* [actor]. If the conduct of the spectators becomes one with the conduct of the actors representing different emotions and sentiments the play may be pronounced to be a really good play.

The *daivikī siddhi* [divine success] is obtained when an actor identifies himself with a character whom he is impersonating and when there are no obstacles, no noise, no unusual occurrence in the course of the presentation of a play and the auditorium is full. Obstacles may arise from four sources—from the fault of actors, from an enemy, from gods and lastly from portentous calamity. When an actor assumes a role contrary to his nature or acts contrary to the way in which he should play a certain role or recites a speech of another character by mistake, or does not know the use of artificial objects prepared according to the method described in the *ahāryābhinaya*, or other things being good speaks in a peculiar tone, obstacles are said to arise from the fault of the *naṭa*. Sometimes singers and instrumentalists commit mistakes in singing or tuning the instruments, sometimes the dramatist makes mistakes in the production of the *nāṭya*. These obstacles may also be included in the first category. When a play is on, some enemies of the actor raise voices of hatred such as 'fie upon thee' or shout very loudly so that the actor's voice cannot be heard, or clap sharply, or throw cowdung or stones at him and thus create obstacles, it is an attack from the enemies. Obstacles arising from the gods are : strong wind, fire, rains, fear from an elephant or a serpent, stroke of lightning, appearance of ants, insects and

ferocious animals. Obstacles resulting from portents [*autpatika*] are those due to earthquake, storm, falling of meteors and the like. The two kinds of obstacles, which cannot be remedied in the representation of a play, are faults due to a natural calamity and the running out of water from the *nāḍika*.

It is understood that in ancient India time was measured by a water vessel of a particular size with a well-defined tube [*nāḍikā*] at its bottom.

The *siddhis* [successes] and *ghātas* [obstacles] are carefully noted before a troupe is declared successful and the proficiency of a *nāṭakamaṇḍalī* conceded. The merits and defects of *nāṭakamaṇḍalīs* were recorded by *siddhilekhakas* [recorders of successes and obstacles]. *Siddhilekhakas* were experts in discriminating the *siddhis* [successes] and obstacles and they were not all of the same age. Their experience was wide and varied. It was on the recommendation of *siddhilekhakas*, who observed the performance of every actor of every company and the *siddhis* and obstacles, that the question of offering the *patākā* [banner], a kind of trophy, to a *nāṭakamaṇḍalī* was decided. If there was no agreement among *siddhilekhakas* as to which troupe should receive the *patākā* [banner] the opinion of *prāśnikas* [critics] was taken. *Prāśnikas* were considered arbitrators [*pañca*]. If after taking the opinion of *prāśnikas* two *nāṭakamaṇḍalīs* were considered to be equal in merit, the king, whose judgment was final, was asked to award the *patāka* [banner]. If, however, the king also could not come to a decision, the *nāṭakamaṇḍalīs* were both awarded *patākās* [banners].<sup>1</sup>

Thus we find that the dramatic art was highly developed in ancient India and that the Sanskrit dramas were actually played on the stage and there was a competition between the *nāṭakamaṇḍalīs* in the successful portrayal of their dramatic art which mainly constituted the depiction of a particular

---

1. NS—KM XXVII. 1-41, 62-67; KSS XXVII. 1-44, 73-79.

*rasa* [sentiment] in the minds of spectators and there was a sufficiently large number of *siddhilekhakas* and *prāśnikas* who would judge their merits and give the *patākā* [banner] to the victorious *nāṭakamaṇḍalī*.

# DRAMATIC PRACTICE TODAY



# **CHAPTER XI**

## **MODERN THEATRES**

### **Introduction**

A national theatre is a crying need in free India. With the attainment of independence attempts are being made to Indianize the administration and education. The feeling is growing that fine arts such as music, dancing, painting and above all dramatic art as presented in the theatre should have State patronage and should be developed on national lines based on the technique observed on the ancient Indian stage but modified according to the needs of our times. Even if we cannot fail to observe that the modern Indian theatre is profoundly influenced by the West, we must not forget that India had a great national theatre of her own in the past. The modern Indian stage can certainly be remodelled on the lines of the stage in ancient India to suit the native genius of the country.

The development of the stage during the last century incorporating features from the provincial theatres, from the primitive Tamil theatre to the most artistic one of Bengal—reveals a great variety of culture. But a fundamental unity is found in the midst of this great diversity. Mythological heroes have commanded reverence throughout the country. Love of the emotional, the imaginative and the idealistic rather than of the intellectual and the purely realistic is a national trend. Sanskrit plays are today seldom performed except in University colleges or in the temples of the South. The stage in these centres comprises a raised platform in a room or an open space.

We shall now examine stage conditions, both primitive and modern, prevailing in the several indigenous theatres before suggesting how a modern stage should be remodelled for India.

### A. The Folk Tradition.

Before taking up the different theatres of today, it will not be out of place here if we first examine the exact nature of the various types of popular entertainments prevailing in several parts of India in the medieval period. The degraded forms of folk amusements of the period which consisted in haphazard incidents, loose spectacular representations of the life and deeds of Rāma, Kṛṣṇa, etc., were the lineal descendants of the most ancient types, *bhāṇa* and *prahasana*, which were marked by extreme indelicacy and sensuality, in spite of a certain satirical aim. The *bhāṇa* and *prahasana* came into greater prominence after the eleventh century A. D. when the classical drama declined in importance.

In South India, the *Bhāgavatam* is one of the most ancient folk-plays prevalent. The amours and exploits of Śrīkṛṣṇa, dramatic stories of saints like Rāmadāsa, popular ballads such as that of Desinga Raja are represented on the stage of the Telugu-speaking districts of the Madras Presidency. We can have a fairly good idea of a country drama in the South when we see the representations of the 'Kathākālī' of the Malabar district. *Nalataṅgi* is one of the most ancient and fascinating stories acted on the stage for centuries in the Tamil country. Many other medieval stories with a pathetic appeal are also popular in Madras villages.

*Yātrās* are popular in Bengal and are like "sacred operas frequently produced in connection with the religious processions of the Kṛṣṇaites."<sup>1</sup> Some *yātrā* troupes specialized in the life story of Rāma. *Yātrā* is a procession in celebration of a particular festival of a deity and also a holy pilgrimage on foot or in bullock-carts in which people entertained themselves with crude performances representing the glory of a particular deity. *Yātrāvalās* were formerly in the habit of extemporizing music and dialogues of plays to suit particular festivals and supplied the links of the story by means of the descriptive and narrative passages. In modern *Yātrās* though secular

---

1. Dr P. Guhathakurta; 'Bengali Drama', London, 1930 p. 4.



themes are admitted yet their religious character and essentially poetic or musical structure continue to exist. During the *Gambhīrā* festivals many devotees put on different masks and play various parts to please Śiva. *Baḍā Tamāṣā*, 'the great show' is done on the third day of this festival which extends over five days. In contrast with these rural mask dances, the *yātrā* has some remarkable characteristics. Only male performers take part in it and the performances are done on the bare ground without any scenic representation. Only a long piece of cloth separates the stage from the green room.

*Laṭita* is the most popular type of medieval play in Maharashtra. It is generally connected with a dramatic representation of *Daśāvatāram* [the ten incarnations of Viṣṇu]. It is religious in character and is often enacted during *Navarātra*. The whole story is described in action and the play is performed in inns or temple halls with the help of a curtain or two. Besides *Laṭita*, several stories of a romantic nature like that of *Kaca-Devayānī* or *Dāmājipanta*, exhibiting the gradual growth of a secular element based on realistic farce and contemporary satire, are dramatized for village performances.

The *Bhavāi* is popular in Gujarat. The performance consists of a series of unconnected individual personations of not more than three characters in each scene and exhibits some popular tale. Its origin is essentially religious and Gaṇapati appears on the stage in the beginning but as the play advances it becomes secular in character. "It is performed in open spaces, in streets and such other public places as courtyards of temples and the like. No stage is required, no scenery, only a poor curtain, occasionally held by two men at each end; a few torches, and a chorus of two or three men helped by crude musical instruments."<sup>1</sup> Besides *Bhavāi* there are several other folk amusements such as singing parties chanting hymns of the glories of the goddess Ambā or the amours of Kṛṣṇa and Rādhā having the element of musical dialogue; then, there is the *Harikathā* where the story-teller narrates a story in a

---

1. Sir William Ridgeway : "The Dramas and Dramatic Dances of Non-European Races" Cambridge, 1915, p. 199.

theatrical manner situated in the centre of the audience; sometimes the whole story of the epics is represented extempore; and occasionally rope dancing and many athletic feats are performed.

The institution of the *Rasadhārīs* of Muttra and its surroundings is an old one and even today it is alive. During *Śrāvaṇa*, *Rāsadhārī* companies are very busy in such sacred spots as Brindaban but the rest of the year they mostly travel in different parts of the country. They present the dramatic performances on the theme of Kṛṣṇa's exploits.

The *Rāmalīlā* is performed, in Upper India, on the occasion of the *Durgāpūjā*. Dresses and masks are used appropriate to the different situations and characters. Extracts from the whole *Rāmāyaṇa* are read through in the course of nearly 20 days and the suitable incidents are simultaneously exhibited.

The devotional medieval romances of Gopichand, Puran and Hakikat are extremely popular with Punjabis. The *Nava-tanki* performers of the western U. P. also exhibit these shows which are quite popular.

The modern Indian stage in its process of evolution has absorbed the cultural richness of the classical drama, the folk traditions of the medieval times and above all the influence of the West.<sup>1</sup> Now we shall take up the different vernacular theatres one by one.

### B. The Madras Theatre

In 1890, Krishnamacharya of Bellary founded the first amateur dramatic society in South India, the "Sarasa Vinodinī Sabhā." After some time college students started another amateur dramatic institution, "The Sugun Vilās Sabhā." Several improvements of great importance were introduced. In 1898, the 'Museum Theatre' was constructed and 'Kanaiyā and Company' was started. High class gentry began to visit theatres for the first time. Later on, a Boys' company [ Bāla Vinoda Nāṭakasabhā ] and a Women's troupe [ Bālāmaṇī company ], were formed.

---

1. See "The Indian Theatre" by R. K. Yajnik for the influence of European Theatres on the Modern Indian stage.

The Madras theatre in fact includes the Tamil, Telugu and Kanarese theatres. The Tamil theatre still indulges in medieval practices—plaintive songs and acrobatic feats—to arouse enthusiasm. The professional companies in Tamilnad still take up mostly mythological themes like *Daśavatāram* and enact them in spectacular settings, dazzling scenery and costumes borrowed from the Parsi stage. Though the actors are not educated and cultured yet they are superb in depicting indigenous arts of Dravidian dances and songs.

The Telugu stage is, on the other hand, developing more rapidly, while going through the mythological, bookish, historical and social types of productions. The main surviving folk forms of Andhra current here were as follows : *Burrakathās*, consisting of bardic recitals and folk songs; *Harikathā*, used for the narration of stories from the epics and the *Purāṇas*; *Veedhi Bhāgavatam*, open theatre performances—The Andhra open-air stage having a technique like the *Kathākālī* of Malabar, the open-air play *Teruvukk-Kootu* in Tamilnad; and also *Tolu Bommalāṭalu*, play by moving leather dolls like the puppet show in North India. Many efforts were made regarding theatrical activities in Andhra from 1910 onwards and *nāṭakamaṇḍalīs* and theatre halls were established in Tinnevely, Bellary, Guntur and Rajahmundry. Effort was made to enact one-act plays. But in spite of all these activities no permanent theatre could be established in Andhra.

The Kanarese theatre is making remarkable progress in Bangalore and some noteworthy companies are coming into existence in Mysore. Besides *Paurāṇic* plays, musical recitals and social farces, some tragedies and translations of Marathi plays have also been staged.

There are already a number of pioneers of theatre who have begun to mould a new tradition out of the old. A great deal of the dance drama perfected by Uday Shankar, as well as the shadow plays he created after he had revived interest in the dances of India, are cases in point. 'The Rhythm of life' was, for instance, an amalgam of motifs taken from the rich storehouse of peoples' memory and transformed through

organization which Shankar had borrowed from Europe. Similarly Rukmini Devi Arundale has established the Kalākṣetra for revival and propagation of Bharata Nāṭyam in Adyar, Madras.

### C. The Bengal Theatre

Bengal has a regional theatre which has gone far ahead in realizing the ideal of a true synthesis of old and new forms, without, of course, actually reviving the old folk theatre. After producing several Shakespearian tragedies and other English plays and making certain odd experiments, Bengal staged the first original play, a social tragedy, *Kulīnakulasarvasva*, in March, 1857, at the house of Babu Jayaram Bysack of Churruckdanga Street, Calcutta. Scenic representation, which is now in vogue in Bengal, started from this date.

A Bengali version of the *Ratnāvalī* of Śrī Harṣa was staged at the first permanent theatre which was constructed in the country residence of Rājā Pratap Chandra Singh and Rājā Issur Chandra Singh of Paikpara, at Belgachia, on July 31, 1858. It was played to the accompaniment of a national orchestra organized on the model of the English theatre. In a spirit of competition, several private theatres were constructed by other landlords for invited friends.

Disappointed by the fact that private theatres catered only to the privileged classes, Girishchandra Ghosh, an eminent dramatist and the originator of the Bengali theatre, expressed the idea of a public theatre in strong language for the middle class run by amateurs. To fulfil his idea he struggled hard for several years and in the beginning acted in the manner of *yātravālās*, having at his disposal a very small number of theatrical accessories. By and by he won laurels in difficult roles and at last succeeded in establishing a regular theatre in 1872 which is today known as "The National Theatre of Bengal." In this theatre which was meant for general public, actors were kept on salary and the audience got entry by tickets. Girish directed the course of several kinds of plays, including *Paurāṇic* plays like, '*Harīścandra*,' historical plays like '*Pratāpa*' and '*Śivaji*' and social tragedies.

Actresses were introduced in "The Bengal Theatre" for the first time in 1873. At Calcutta 'The Great National Theatre' was built the same year on the style of the European 'Lewis Theatre.'

Then Dvijendralal Ray got unique success in the theatrical activities by introducing realistic types of plays on the stage. Next we come to Rabindranath Tagore who consciously evolved a highly developed, technically efficient style of his own in dramatic writing which owed much to the folk culture of Bengal. His plays were not so much successful on the stage as those of Dvijendralal Ray, because his dramas were highly poetic and symbolic. In 1944 was produced a play "Homœopathy" written by Manoranjan Bhattacharya, a professional actor and a dramatist of renown.

It was the Bengal famine which shook the whole country that produced the greatest spirit of theatrical activity in Bengal. Under the stress of this exigency was produced a play '*Navanna*' [New Harvest] written by Bijon Bhattacharya and produced by the author in collaboration with Shambu Mitra. The theme of the play, which is in four acts, is the life of a Bengali peasant during the harrowing days of famine when three million died of starvation and disease.

The Bengali stage is highly artistic. The repertory system is followed. Its distinguishing feature is that all feminine roles are played by women. Not only this, but young girls are also employed to play the roles of boys. The novel use of song and dance is another special feature of the Calcutta stage.

#### **D. The Marathi Theatre.**

Like the Bengali theatre, the Marathi theatre began mainly under British influence, but soon emancipated itself from it and established a considerable repertoire which is good as literature as well as for purposes of the theatre. The Marathi theatre arose in 1843 when Vishnudas Bhawe of Sangli brought out the first Marathi drama named *Sitā Svayamvara* on the stage. Using amorous and tragic themes, he wrote a number of plays which reformed the old medieval performance.

Then the professional Bhave company came into existence. The year 1880-81 is a great landmark in the history of Maharashtra. Musical dramas were enacted on the Marathi stage that year. The *Abhijñānaśakuntala* translated in Marathi by Kirloskar, a famous dramatist, was enacted for the first time in October, 1880. Kirloskar also wrote original plays 'Subhadra' and 'Rāmarājyaviyoga'. He himself appeared in the role of stage manager on the stage. After Kirloskar comes Dewal who is famous not only for musical dramas but also for prose dramas. With his help the Kirloskar Nāṭakamaṇḍalī, which came into existence in Kirloskar's time, came to the forefront. From 1895 Kolhatkar dominated the Marathi stage. His drama named 'Vīratanaṇya' is very famous. Its plot is imaginary and its style is in the manner of Western dramatists like Shakespeare. In 1921, the Maharashtra Nāṭaka Maṇḍalī staged a drama named 'Māyecāpūta.' Several companies such as Aryoddharaka company in Poona, the Maharashtra company and the Shahunagaravasi company came into being. Historical plays were written. Next comes Ram Ganesh Gadkari. He wrote mostly social dramas which were quite suitable for stage and highly appreciated by the public. Varerkar dominated the Marathi stage from 1925 to 1935 and wrote social plays in a realistic style. As a leading dramatist, Varerkar gave a tremendous lead to the younger groups which had been re-creating the Maharashtra village theatre through the *Powada* [songs in praise of brave people], and the *Tamāśā* [vulgar plays performed by low class people]. Varerkar became the president of a *nāṭakamaṇḍalī* of Bombay named Sahakārī Manoranjana Maṇḍala. In this company the actors were mostly labourers and so plays written by them were also staged, after Varerkar assumed presidentship of the company. In 1930-31, the *nāṭakamaṇḍalī* of Hirabai Barodkar on behalf of Nūtana Saṅgīta Vidyālaya was established. In 1941 Rangdekar came on the Marathi stage and his influence is still found on it. He attempted to write action plays of modern type. In 1945 Atre came to the forefront of the Marathi stage. He has a unique art of giving excessive

pleasure, though sometimes of a third-rate order, to the audience.

Marathi stage festivals were observed with great pomp and grandeur in 1943, 1944, 1945 and 1947. It was proposed to build a grand theatre hall in Bombay with the money obtained in the festivals.

The modern Marathi stage of Poona has no *kavi* attached to it. Companies request renowned dramatists to write plays for them or playwrights allow competent companies to produce their plays for a royalty. Boys are rarely employed in adult companies on the Marathi stage. However, several juvenile companies, with all their members under 18, are formed. They play light comedies with great success. Women now come on the stage with men. In 1930-31 Hirabai Barodkar *Nāṭakamaṇḍalī* employed women to play female parts for the first time. There are, however, some companies of actresses.

Scenes and costumes in Marathi theatre lack splendour. It concentrates its effort on natural acting and scientific music. It follows the system of alternating serious scenes with light ones. We cannot but remark that gradually religious inspiration is being lost and growth of a secular element based on realistic farce and contemporary satire is noticed in Marathi productions. Further, there is found excessive use of songs on the Marathi stage.

### **E. The Parsi and the Gujarati Theatre.**

The original Bombay theatre was erected on the old Bombay Green [Elphinstone Circle] by the money received through subscriptions in 1770. In 1842 Jagannath Shankerseth built a private theatre which was available for European and Indian productions at a certain daily rent. Later rival companies came into existence and by studying the history of the 'Sanglikar' [of Bhawe], 'Altekar' and other companies, we come to the conclusion that they were competing with each other on professional lines. In these performances most of the incidents and situations of the ancient epics and legends were employed but numerous

gorgeous curtains began to be used in the Parsi style and some English farcical devices were introduced. An English version of the *Ahhijñānaśākuntala* was staged by the Kālidāsa Elphinstone Society of Bombay. After this, historical and social plays began to be presented on the stage from about 1890.

The professional Parsi theatre came into existence in 1870. Seth Pestanji Framji established an Original Theatrical company in Bombay. Khurshedji, Bandiwala, Kawasji Khatau, Sohrabji and Jahangirji were the principal actors of this company. After the death of Framji this company was broken up and almost all the actors opened different companies in Bombay, Delhi and Calcutta.

The Parsis took up both Gujarati drama and the stage. They had a practical bent of mind and so put commercial success based on this formula "give the public what it wants" above artistic achievement. The Alfred, Madan and Balliwala and some other companies carried the theatrical activities of the Parsis for more than half a century.

Here the manager employed the services of a poet [ *kavi* ] and an expert musician. Young boys were generally selected in professional companies for their gifts of song and handsome features. Three stock types could be distinguished in each company : the joker, romantic lovers and the hero's antagonist. Women were discouraged on the stage. Under the Western influence, Balliwala made an experiment in introducing women such as Gohar, Mary Fenton and Munnibai on the Bombay stage. Plays continued to be produced throughout the year.

There was a spirit of competition among companies. Repertory system was followed by all the companies and effort was made to add new plays to the old stock. A drop curtain with gorgeous paintings of mythological characters was used. The play began with a song sung in chorus. The auditorium was decorated profusely with brilliant electric lights. Painted curtains suggested the locality of the setting. Startling changes of scenes were accompanied by the thunder of gun-shots. Characters mostly entered and left the stage by side openings



The language used on the stage was graceful, pointed and sweet Urdu. Here also the system of alternating serious scenes with light ones was in vogue.

Grand dresses and colourful curtains were given more importance in the Parsi theatre than the plot, dialogue and acting. A dramatic company was considered to be good or bad for its curtains and arrangement of scenes. From the point of view of Parsi stage-craft the highest success in the presentation of plays was considered in the arrangement of wonder-striking scenes such as running of railway line, flying aeroplane, cutting the head of a person clearly on the stage. The Parsi theatrical companies did not attach much importance to the realization of sentiment and it was found that the aggrieved actress sang songs in the midst of most tragic scenes. So Parsi theatres, whose sole purpose was to give the public what it wanted, however crude it might be, became purposeless as soon as the talkies were introduced in India. The commercial stage started decaying and the film and the talkie sealed its fate.

The real Gujarati theatre arose in 1861 when Rana-chodbhai, having a repulsion against the plays of *Bhavāi maṇḍalīs* which used to show coarse *khyāla* moving from village to village, began to render and adapt the Sanskrit pieces in Gujarati. After some time he wrote a popular play called '*Hariścandra*' and then a social tragedy. Later there arose 'the Bombay Gujarati Company' of Dayashanker, 'the Morbi Company' of Vaghaji Oza and 'The Deshi Company' of Dahyabhai. It was Dahyabhai who gave the modern Gujarati stage its form. The Gujarati middle class is mainly commercial and so Gujaratis after a short while began to ape Parsi modes of representation.

Now efforts are being made to improve the theatrical activities in Gujarat. Women have begun to appear on the Gujarati stage. 'The Naṭa Maṇḍala', inaugurated by the Gujarat Vidyā Sabhā, Ahmedabad, and directed by Jayashanker [ Sundarī ] and Dina Gandhi presents '*Menā Gurjarī*' and other Gujarati folk plays in a marvellous manner. The

'*Menā Gurjarī*' is a dance-drama in which the whole story is presented through dances, and there is background music from the beginning up to the end. Such plays cater to the needs of people of good taste.

Now K. M. Munshi has written certain plays which attack corrupt social practices in the country and are imbued with artistic taste. Some of them have been enacted also on the Gujarati Stage. C. C. Mehta, who is a highly talented Gujarati dramatist, has evolved a new technique and his play on the life of the railway workers, '*Āg Garī*', has become very popular. Such efforts of Munshi and Mehta not only can improve the standard of Gujarati theatre but also, it is hoped, will bring new life to the theatrical activities of the country as a whole.

By the above study of the theatrical activities in the country we find a fundamental distinction between the Parsi and Gujarati companies on the one hand and the Marathi and Bengali troupes on the other. While the former guard the manuscripts of the plays and mostly do not publish them, the latter respect the authors and realize the dignity of plays as literature. The Marathi and Bengali companies do not thrust extra comical stuff or farcical songs like the Parsi companies. The Marathi and Bengali plays are artistic wholes. The professional theatre in South India is several decades behind the western Indian and Bengali theatres. Hindu mythological plays are still staged there.

### F. The Hindi Theatre

The Hindi theatre, a later development, has been influenced by touring Parsi companies and it has been developing in U P. after the appearance of the dramatist, Bhāratendu Harish Chandra. During the Muslim rule in India the main places of dramatic shows were temples and monasteries where on the occasion of festivals people used to entertain themselves mostly by the performance of *Rāmalīlā* and *Kṛṣṇalīlā*. Wajid Ali Shah, Nawab of Oudh, was very fond of these *rāsamaṇḍalīs* and pātronised many of them in his court. He himself used

to act as Kṛṣṇa while the prostitutes of his court took part of *gopīs* adorned with ornaments and gaudy dresses. One of his French courtiers arranged songs and dances in the performance of *Rasalīlā* on the model of French opera. Hundreds of male and female musicians and dancers of the Shah's court could participate in the performance. In such attempts we can see the influence of the European stage on the Hindi stage. At the command of the Nawab, an attempt towards presenting new type of theatre was made in 1853 by Imanat who wrote his play '*Indra Sabhā*' and enacted it at his court with the Nawab in the main role. Thus the Hindi or Hindustani stage has begun mainly under foreign influence and somewhat under the influence of the court-stage patronised by the Nawab. Later, it has been influenced by the Parsi stage.

There is no doubt that effort was made to translate the Sanskrit dramas such as the *Karpūramañjarī*, the *Dhanañjaya Vijaya* and the *Mudrārākṣasa*. Bhāratendu Harish Chandra wrote some dramas on the model of Sanskrit dramas. Thus the Hindi stage went towards the West while the drama looked towards the East i. e. India.

Bhāratendu considers *Jānakī Maṅgala* to be the first acted drama in Hindi. In 1868 this play was enacted in a Banaras theatre by the effort of Aishvaryā Narayan Singh. This drama is not to be found now.

Bhāratendu himself was an expert in the art of representation and his influence was so great that even in his life-time many of his dramas were enacted on the stage. The dramas of Bhāratendu were a success, because he himself was an actor. Also the dramas of Madhav Shukla, Jagannath Prasad Chaturvedi and Badri Nath Bhatta were liked by all, because all of them had intimate relation with the stage. Shukla and Chaturvedi were themselves successful actors.

With the disappearance of the Parsi theatre, there was no stage properly speaking in North India. Literary dramas began to be written under such circumstances. They were first published, but when staged were not successful. The dramas of Jai Shankar Prasad are instances in point. His

dramas, except *Dhruvasvāminī*, were not fit to be staged. The dramas, *Tilottamā* and *Candrahāsa* of Maithili Sharan Gupta, *Karbalā* and *Prema kī Vēdī* of Prem Chand are not suitable for staging. The dramas, *Vikramāditya*, *Devatā* and *Alakā* written by Sitaram Chaturvedi have been successfully staged in Banaras from time to time.

Up to this time there is no permanent regular Hindi theatre existing in any part of the country, and whenever Hindi dramas are staged, a temporary stage is erected with the help of bamboos and some curtains or they are performed in meeting places or cinema halls. Hindi plays are enacted in big towns such as Patna, Allahabad, Lucknow, Delhi, Indore, Gwalior, Jaipur, Jubbulpore, Nagpur and Meerut on such temporary stages.

By far the greatest contribution to the Hindi stage has surely been made in recent years by the actor-producer, Prithviraj, who started his Prithvi Theatre in 1945 in Bombay. The circumstances, under which theatrical activities are going on in India, are not very favourable as Prithviraj, a superb actor and director, is not able to establish a permanent theatre in Bombay for showing his plays. He gives only three morning shows at the Opera House over the week-end.

Prithvi Theatre has its own individual characteristics. It does not dazzle the eyes of the spectators like the Parsi theatre but on the other hand is marked with simplicity and naturalness. Prithviraj has worked upon certain memories of his village life as it was found in the *Rāsa* of North West India and uniting several motifs of the folk play [*Navatankī* etc.], has produced two plays, *Dīvāra* and *Paṭhāna* dealing with a contemporary theme, communalism. So far the Prithviraj repertory consists of six plays—*Divāra*, *Paṭhāna*, *Gaddāra*, *Śakuntalā*, *Āhuti* and *Kalākāra*. Now the special features of each of these plays will be dealt with in brief.

The aim of the play *‘Dīvāra’* is to break down the wall of hatred and misunderstanding that keep apart brothers, neigh-

hours and communities. The play begins with a chorus, the refrain of which is "*Hama ek the, hama ek haim hama ek rahenge*" [ i. e., we were one, we are one and we shall remain one ]. Prithviraj appears in three roles in '*Divāra*'.

The message of his play '*Paṭhāna*' is for Hindu-Muslim unity, which is very essential for India. It deals with the story of two families—one Muslim and the other Hindu, living on the frontier. The Muslim Khan sacrifices the life of his only son to save the life of the son of his former Hindu friend, who was murdered in a tribal feud. Prithviraj has tried to introduce into it at one place the principle of modulation of voice [ *svara-vaicitrya* ]. Some six or seven characters speak in such a lovely manner that ascent or descent of all the seven *svaras* is heard in order.

'*Gaddāra*', a political drama, treats the events between 1921-1947 A. D. In this drama, a nationalist Muslim in his weak moments turns to be a Muslim Leaguer but as soon as good sense prevails, he wavers and begins to express his former loyalties to India as a whole. On this he is killed by his co-religionists as a traitor to their cause. This drama has been much criticized by Pakistanis.

'*Śakuntalā*' as staged by Prithvi Theatre in Hindi is based on the Sanskrit play '*Abhijñānaśākuntala*' of Kālidāsa. This version, though not very excellent, can be called on the whole a stage success.

'*Āhuti*' is a tragic play depicting the life of an abducted girl at the time of partition of India in 1947. A girl of Rawalpindi, who was betrothed before partition, was abducted by a Pakistani in partition days and was restored to her people by a friendly Muslim. The father of the boy, who with his family found his way to Bombay, refused to disgrace his family by bringing into it an abducted girl. The girl puts an end to her life. Her death turns the lover mad, and he also dies.

'*Kalakara*' is an artistic play and shows that a human being can undertake most hazardous and wonderful work and even can climb the highest peak of a mountain in order to

achieve his object. The painter and the priest, who are prominent characters in the play, describe their own thoughts on the present civilization and society reflecting the opposite sides of life.

Prithviraj has done a real service to the country by bringing life and vigour to the Hindi stage. He has, in fact, been faithful as an artist by introducing changes according to the needs of the modern age, which wants maximum enjoyment in minimum time. Prithviraj shows only those plays which have been written specially for the Prithvi Theatre and which usually last for two hours and a half. While presenting his plays, he does not use curtains except the drop scene. The settings in his plays are simple and natural. The whole play '*Paṭhāna*' is arranged only in one setting which gives the idea of completeness and nowhere unnaturalness is found. '*Dīvāra*' is also enacted in one setting except the last scene which requires a slight change. Two settings are, of course, required in '*Kalākāra*.' Thus the theatrical performances of Prithviraj are very simple, natural and timely, and have a great appeal to the minds of the cultured.

### G. Idea of a National Theatre

In spite of the fact that modern Indian theatres have made considerable progress, none of the theatres in India is perfect nor has any of them the capacity of answering the demands for a national theatre. Some of the lines on which the foundation of a national theatre can be based are here suggested.

There is no lack of inspiration in the remnants of the broken tradition of our theatre. Though India cannot gain much by reviving the formalism of the ancient theatre, it is likely that it will gain enormously by inquiring into its old craft of comedy, tragedy, farce and the morality plays. A constant return to folk feeling, which is rooted in the real life of our people, can bring a genuine sense of reality to the Indian stage today. The *Rāsa*, the *Navāṭankī*, the *Rāmalīlā*, the

*Kṛṣṇalīla*, the enactment of the victory of the Pāṇḍavas over the Kauravas, the Muharram, the Holi as well as the several harvest dance dramas are the apotheosis of the old drama survivals which are an important reservoir of energy, from which a new living art of the theatre can be made.

It may be suggested here that alongside with the creation of new plays, effort should be made to stage the plays of Bhāsa, Kālidāsa, Bhavabhūti, Tagore, Prasad etc., in the different provincial languages and Hindi. The arrangement should be made for their translation, abridgment and the modification of their language. Really talented and cultured people, who can understand and appreciate dramatic art and who have genuine love for self-sacrifice, should be asked to make arrangements for the establishment of a national theatre in India.

A fundamental unity must be maintained in the direction of the stage-craft followed in different theatres. This can be done by relying on the ideals and culture of the country as a whole. On the ancient stage, feminine roles were generally played by women, but this tradition was discontinued after the Muslim conquest on account of the insecurity of the times and the *pardah* system. The practice must again be revived in order to bring realism in character representation. The orthodox Indian notions of propriety and decorum must be maintained. In the *Abhijñānaśākuntala*, Duṣyanta brings his lips close to his beloved but does not kiss her on the stage. Western life as reflected in European productions in India was perfectly natural in its place, but when it was foolishly aped on the Indian stage, it was bound to result in demoralizing our theatre. The conventional intrigues between lovers and married women common in many French plays, which are being freely followed on the Indian stage, should altogether be stopped.

Preparation of a correct colour-scheme is essential. If colours are prepared according to the *Nāṭyaśāstra* and the *Viṣṇudharmottara*, a high degree of success in the presentation of plays may be attained. The hair, beards, ornaments and dresses described

in Sanskrit dramaturgic books are suitable for plays in any Indian language. Though modern means of representing objects can be used, the ancient Indian methods should not be entirely overlooked.

Construction of the stage cannot be so crude now as in ancient times, but the ancient technique may be revived to suit modern conditions. The use of curtains and wings should be elaborately developed. Music, dancing and histrionics for the modern stage should be employed on the models of ancient India. A great number of songs are generally introduced in all possible contexts—fighting heroes and dying heroines sang on the Parsi stage—and the beauty of native music is marred by the introduction of European tunes to the accompaniment of the Indian musical instruments. This combination of Indian and European music should be discarded. The practice of introducing everywhere European patterns of music, dialogue and dancing should also be abandoned.

India's truly national theatre must be a place, where purely Indian dramas whose object is to produce *rasa* in the minds of the spectators are performed, where a highly developed colour scheme is employed, where the hair, dress and other equipment follow the pattern of Indian life, where classical music, dance and histrionics are encouraged, in short where the ideals of Indian society are maintained. To achieve the above ideal the Government of India should encourage dramatists, dancers and musicians of worth and reputation. They should also help in the establishment of a truly Indian theatre where all kinds of plays, whether in Sanskrit or any modern Indian language, may be performed according to the requirements of the day.



## CHAPTER XII

### EPILOGUE

The origin and development of Sanskrit plays have been detailed in this work only as an introduction to the elaborate description of the subjects connected with the actual presentation of plays on the stage. The Sanskrit drama is religious in character and Indian in origin. The Sanskrit drama or *nāṭya* is evolved from *nṛtta* and *nṛtya* and means a representation of situations. Conventions, which were observed on the ancient Indian stage, were peculiar and, as such, had no connection with the practices of the stage prevalent in other countries. The Sanskrit dramas were written partly in Sanskrit and partly in the different *Prākṛta* dialects. An idealistic atmosphere was maintained on the stage. Not only was a tragic end forbidden, but other important restrictions were also imposed. Propriety and decorum were emphasized and the dramatist had to observe the 'decencies' of the stage. Things as should not be represented and events as extended over a long time, were related in inter-acts, the so-called *arthopakṣepakas*. A certain set of words was used on the stage for calling the different characters. The unities of time and place were not observed in most of the plays and the unity of action was observed in the sense that everything, which was shown on the stage, gave expression to that sentiment for the depiction of which the drama was written. The entire edifice of the Sanskrit play has got a fundamental religious basis. The play begins and ends with benedictions in the form of *nāṇḍī* and *bharatavākya*. The actual performance of the play was preceded by preliminaries, the essential aim of which was to secure the favour of the gods for its successful representation. Thus Sanskrit drama with its novel peculiarities and having religious tinge in the course of its beginning, development and conclusion, is purely of Indian origin and is national in character.

Various theories have been advanced by European scholars

to explain the origin of Sanskrit drama, but they all fall to the ground as they deal with only individual aspects of Indian drama and do not treat it as a whole. The object of Sanskrit plays is to bring satisfaction to the audience by evoking *rasa*, the transcendental pleasure in its mind. It is a novel aspect which is not found in the dramas of any other country. Plays were enacted during fairs, in temples, at general festivals in different seasons, at the pleasure of the poet's patron or before the learned assembly and at village festivals and ceremonies.

The possible correct measurements and the construction of different parts of the theatre are given in this work after interpreting and harmonizing the conflicting texts of the *Nāṭyaśāstra* with the help of the commentary written by Abhinavagupta. It has been shown very carefully that in ancient India plays were enacted in the *saṅgītaśālā* of the palace, in the courtyard of the temple and in open spaces in villages. Spectators in the palace theatre consisted of kings, courtiers, learned Brāhmaṇas and high State officials, in the temple theatre, of devotees, learned Brāhmaṇas and the general public; while public theatres were meant for village people and the public. Bharata's description of theatres, their construction, size and shape, position of the stage, orchestra, auditorium and of elaborate practices to be performed in the form of preliminaries and religious ceremonies continuing for many days in connection with presentation of Sanskrit plays, all support the view that theatres were of a permanent nature, but as we do not find an archaeological evidence of a permanent theatre we cannot be definite about this. It is certain that there were theatres for the general public built on a temporary basis, as the main spectators were the populace in such playhouses. Though nine types, or even 18 types, of theatres can possibly be determined according to space and time, yet, broadly speaking, for practical purposes the theatre was of three types i.e. *vikṛṣṭa* (rectangular), *caturasra* [ square in form ] and *tryasra* (triangular). In it the stage was double-storeyed and it was

divided into *kakṣyās*. Most probably it did not jut out into the auditorium in any case. The decorations on it were to be in harmony with oriental splendour, colour and brilliance. Regarding the four main pillars in the auditorium it is noteworthy that no pillar was to be in the centre and that the four were dedicated to the four castes, the lowest included. This reveals, curiously enough, a partially democratic basis of Indian theatrical art, four colours being associated with the four castes, white, red, yellow and blue respectively. There were other columns, too, perhaps for those not included in caste system. Galleries were to be formed one behind the other. The seats in the auditorium were to be arranged in the manner of a ladder to ensure visibility. They were to be made of wood and bricks, one and a half feet higher above the ground. There were at least three doors in a theatre, but there could be as many as six doors: two from *nepathyagrha* leading into *raṅgaśīrṣa*, one in the auditorium, one by which the *naṭa* enters with his wife, two others existing on the southern and northern sides of *raṅgaṭīṭha*. As to the roof of the theatre it is quite possible that there were theatres of both kinds—open-air theatre where there was no roof and theatre where there was possibly a roof.

Special attention has been given in outlining the methods of arrangement of scenes and preparation of various kinds of stage paraphernalia. It is clearly proved that the curtain was not imported from Greece or elsewhere outside India and was definitely of Indian origin and was called by the name of *yavanikā*, *javanikā* or probably *yamanikā*. There was only one curtain and it was drawn aside and not removed or rolled up. However, there might possibly be minor curtains also which could be used for making divisions i. e. *kakṣyās* on the stage. Something has also been said about Indian painting in order to show that the curtain must have been coloured according to the *rasa* of the drama to be enacted. Four different timings of representation of Sanskrit plays are mentioned which exclude meal timings and midnight hours. However, the plays could be performed at any time by the order of the patron or the king.

Animals and other objects which were exhibited on the stage were either made up of bamboos covered with cloth or made up of cloth alone, and in some cases their motion was shown through mechanical means. Weapons and other hard substances were prepared from shellac, mica, cloth, clay etc., and thus were handy. *Alaṅkāra*, comprising dresses, garlands and ornaments, and *aṅgaracanā*, including colouring of the body, hair and beards, were peculiarly prepared and employed on the stage having due regard to country, age and above all to the main sentiment of the play.

Those objects which could not be represented on the stage by means of materials suggested above due to the absence of the materials or otherwise, were shown through mimicry. The science of histrionics was so much developed and so highly valued as to be taught to high born ladies as an accomplishment. Gestures and movements were not realistic and were often made with reference to imaginary objects. For instance, a gesture might show that a bee was worrying a maiden, though no actual bee would be visible. A particular movement of the body might show a person ascending to or descending from a palace which might not actually be represented on the stage. The code of gestures and movements prescribed for the different limbs was binding on the *naṭa* [actor]. The *naṭa* had no room for being original by inventing gestures etc., for that was the business of masters [*acāryas*] of the art who knew its theory and practice.

In this work, music, dancing and dialogue—the elements of drama—are treated in a cursory manner, only as far as they are concerned in the presentation of Sanskrit plays. In ancient theatre musicians used to sit in *raṅgaśiṛṣa* between the two doors leading to *nepathyaḅṛha*. Music was prevalent on the stage in order to add charm to the special dramatic actions presented on the stage. It may be remarked here with emphasis that the orchestra could be organized on the ancient Indian stage with the help of four kinds of instruments i. e., '*tata* [stringed musical instruments], '*suśira*' [wind instruments], *avanaddha* and *ghana* [instruments of percussion i.e. drums, cymbals, bells and gongs]. The reason is obvious because various

kinds of instruments, which are required for the performance of a play on the stage, are Indian in origin and because they can serve to strike a particular *rasa* as desired in a particular Sanskrit play and because they have a rich variety and are used even today in orchestral form in South India and at the dances of prominent dancing masters like Uday Shankar and Ram Gopal.

As to who should play a particular role is a very important subject which is treated in this work. In Sanskrit plays, the roles are of three different nature: '*anurūpā*', similar to the nature for the person he is acting, '*virūpā*', contrary to the nature for the person he is acting, '*rūpānusāriṇī*' imitative by nature. In '*anurūpā*' women take the roles of women, and men, those of men. In '*virūpā*', the child plays the role of an old man or an old man takes the role of a child. In '*rūpānusāriṇī*', if a man plays the part of a female character it is called imitative acting. A man's role may be played by a woman according to the desire of the manager, but an old man and a boy should not be made to play the role of the opposite sex. This item of work is very significant and valuable as drama is the true representation of life.

The qualities and usefulness of different *nāṭyācāryas*, who were proficient in one or more branches of art connected with drama, are also described in this work. This shows the height of development of dramatic art in ancient India. Elaborate education in the science of dramatic art was imparted by *nāṭyācāryas* to actors and actresses who appeared on the stage. Well-trained *ācāryas* used to prepare different materials required for the stage.

Actors and actresses were despised as low and were denied some of the privileges of the highest caste but, on the other hand, they enjoyed the friendship and love of great kings and eminent dramatists like Bhavabhūti.

The specialities of spectators and judges are described in detail as they are peculiar to Sanskrit plays which were enacted on the stage. This feature of the Sanskrit play significantly proves that dramatic art was critically observed and judged.

Sanskrit plays mostly were intended to be actually presented on the stage. There might be some literary dramas also which were meant for reading only but the number of such dramas was very small. As the aim of every Sanskrit play was to portray one main sentiment, it is carefully shown how different *rasas* were presented on the stage. The system of advertisement, though crude, was in existence. Arrangement was made for the judgment of the dramatic art which was shown on the stage by two or more theatrical companies. *Siddhilekhakas*, whose duty was to write the qualities i. e. different kinds of successes [*siddhis*] and obstacles [*ghātas*], existed in a sufficiently large number. They used to count them, pronounce judgment and offer *patākās* [banners] to the winning party. In case there was a conflict of opinion among the *siddhilekhakas*, reference was made to *prāśnikas*, who were considered to be the best arbitrators in different kinds of dramatic art. If they also failed to give correct opinion about the respective merits of the different companies, the matter was referred to the king whose judgment was final. In case the king also would not be able to pronounce his judgment owing to their equal merits, both the parties were offered *patākās*.

Thus we can assert that the art of presenting Sanskrit plays on the stage was developed to high excellence in ancient India and that the standard of the taste of cultured and *sahṛdaya* people was so high that they could appreciate and realize the portrayal of sentiment, the transcendental joy, for the realization of which the drama was specially enacted on the stage.

Such are the characteristic features of the classical theatre of ancient India. From the outset of the history of the Indian drama, *bhāṇa* and *prahasana* flourished side by side with it. But after the rise of the Mohammedan power in India, these species came more into prominence and then they contributed largely to the village drama. Artistic subtlety disappeared and old rules of decorum were violated. Still some of the elements of the ancient school lingered in these medieval dramatic performances. The marked feature of the rural drama consisted

in the introduction of singing and dancing carried to a farcical plane, without any consideration of the time element. The Epics and the *Purāṇas* formed the main sources of inspiration for classical as well as medieval representations, but in one case there was concentration on a special episode and in the other a clumsy reproduction of all the principal incidents of the *Rāmāyaṇa*.

*Bhāgavatam* in South India, *Yātrās* in Bengal. *Laṭita* in Maharashtra, *Bhavāi* in Gujarat, *Rāsalilā*, *Rāmalilā* and *Navāṭāṅkī* of Upper India and devotional romances of Gopichand, Puran and Hakikat in Punjab are the most ancient folk plays prevalent from medieval times.

Now coming to the modern Indian stage, we feel that there is a gap between the ancient and medieval stage on the one hand and the stage of today on the other. The modern Indian stage has been reared mostly on the influence of the West, but we must not forget that it has certainly imbibed, though to a limited extent, the cultural richness of the classical drama and the folk traditions of the medieval times.

In this work the salient features and main tendencies of different vernacular theatres—the Madras theatre, the Bengal theatre, the Marathi theatre, the Parsi and the Gujarati theatre and the Hindi theatre—have been carefully dealt with and it has been ascertained that the development of the stage in the last century from the primitive Tamil theatre to the most artistic one in Bengal reveals a great variety of culture. While the stock tricks of the stage, such as horror, suspense, surprise, disguise and mistaken identity were exploited by the Gujarati and Parsi stage, the Marathi and the Bengali adapters concentrated more on characterization and on the study of the human mind. Madras theatres still dabble in medieval practices of mythological plays. Though the Hindi or Hindustani theatre has developed under the foreign influence getting impetus at the hands of Wajid Ali Shah, Nawab of Oudh, and further being affected by touring Parsi companies in the beginning, it has followed an independent course. There have been dramatists like Bhāratendu Harish Chandra in the field of Hindi theatre, yet this theatre is still in its infancy.

Luckily, at the present moment, Prithviraj, an actor-producer, is making great efforts in the development of this kind of stage. The language of his dramas is simple and the improvisations made by Prithviraj in the course of playing a prominent role really make the presentation of his dramas lively. Sometimes the mannerisms of Prithviraj become somewhat hackneyed and his peculiar tone gives one an idea that he alone carries the audience with him by his lordly personality and the way of expressing the ideas contained in his dramas. It is feared that no one else would be able to take his place and represent his dramas in a faithful and realistic manner as he does. It is, therefore, suggested that he should not only devote his whole-hearted effort in acting and producing a certain play but should prepare certain other people to take his place in an emergency.

The theatrical development in India has got a great setback owing to the popularity of the 'talkies' in Hindi, Marathi, Gujarati and other vernaculars produced by the Indian film companies, which can afford to pay high salaries to actors and actresses and attract them to screen. Even Prithviraj today has to depend for financial reasons on 'talkies' and has to assume different roles on the screen to make up the loss he incurs in the carrying out of his theatrical performances in different parts of the country.

Though there is some theatrical activity in different parts of the country, it is not yet satisfactory. We are making an effort to achieve all round progress, and we should not neglect the theatrical art. The Government of India have begun to encourage dramatists, dancers and musicians and they have nominated Prithviraj, a first class actor, Rukmini Devi, a prominent dancer, to the Parliament as members of the Council of State. That is not enough. The Government should invite well-known artists to co-ordinate the salient features of the different theatres of the country and evolve a unified national theatre for India. Possibly, a beginning in this line has been made by the Ministry of Education in founding an *Akadami* of Fine Arts with its headquarters at Delhi.



## BIBLIOGRAPHY

### A. Sanskrit dramas and works on dramaturgy and other allied topics consulted and cited.

1. Agnipurāṇa by Vedavyāsa, Vangavasi Steam Mesina Press, Calcutta, Śaka, 1812.
2. Anargharāghava of Murāri, with commentary of Rucipati, Nirnaya Sagar Press, Bombay, 1929.
3. Abhidhānaratnamālā [a Sanskrit Vocabulary], ed. with a Sanskrit-English Glossary by Th. Aufrecht, Williams and Norgate, 1861.
4. Abhinayadarpaṇa of Nandikeśvara, ed. by Manomohan Ghosh, Calcutta Sanskrit Series No. 5, 1934.
5. Abhinavabhāratī of Abhinavagupta, in manuscript form copied from Mss. Government Oriental Manuscript Library, Madras, contained in Sarasvati Bhawan Library, Sanskrit Government College, Banaras.
6. Amarakoṣa of Amara Simha, ed. with Hindi notes by Manna Lal, Banaras, 1937.
7. Arthaśāstra of Kauṭilya, with commentary Śrīmūla of Gaṇapati Śāstrī, I-1, II; II-III-VII. Trivandrum Sanskrit Series No. LXXIX and LXXX, Trivandrum, 1924.
8. Avadānaśataka, ed. by Dr. J. S. Speyer II, 8-10, St. Petersbourg, 1909.
9. Āryamañjuśrīmūla-Kalpa, ed. by Gaṇapati Śāstrī, I Trivandrum Sanskrit series No. LXX, Trivandrum, 1920.
10. Uttararāmacarita of Bhavabhūti, ed. by M. R. Kale, Bombay, 1934.
11. Ṛgveda Samhitā, ed. by Maxmuller, Oxford, 1873.
12. Karmasundarī of Bilhaṇa, ed. by Durgā prasāda Kāśinātha Paṇḍuraṅga, Nirnaya Sagar Press, K. M., No. 7, Bombay, 1895.
13. Karpūramañjarī of Rājaśekhara, with commentary of

- Vāsudeva, Nirnaya Sagar Press, K. M., No. 4, Bombay, 1927.
14. Kāṭhaka, Von Leopold von Schroeder, Leipzig, 1900.
  15. Kāmasūtra of Vātsyāyana, with Jaimaṅgala commentary, Haridas Gupta Karyalaya, Banaras.
  16. Kāvyaṣaṅkṣa of Mammaṭa, with commentary by Vāmanācārya, Poona, 1933.
  17. Kāvya-mīmāṃsā of Rājaśekhara, Gaekwad Oriental Series, ed. by C. D. Dulah and R. A. Sastry, Baroda, 1934.
  18. Kuṭṭanīmata of Dāmodaragupta in KM Series, Part III, Nirnaya Sagar Press, Bombay, 1887 and also ed. by T. M. Tripathi, Bombay, 1924.
  19. Kundamālā of Diṇnāga, with notes by Vedavyas. The Punjab Sanskrit Book Depot, Lahore, 1932.
  20. Kauṣītaki Brāhmaṇa, Von B. Lindner I Text Jera, 1887.
  21. Caturbhāṇi, Śivapuri, publishers D. G. Sharma and Krishna, Bakerganj Patna, 1922. It contains the following four dramas : Padmaprābhṛtak of Śūdraka, Dhūrtaviṭa-saṃvāda of Īśvaradatta, Ubhayābhisārikā of Vararuci and Pādatāḍitaka of Śyamilaka.
  22. Daśarūpa of Dhanañjaya, with commentary of Dhanika, Nirnaya Sagar Press, Bombay, 1928.
  23. Digghanikāya, ed. by T. W. Rhys Davids and J. Eastlin Carpenter Vol. I [Pali Text Society], London, 1890.
  24. Dūtāṅgada of Subhaṭa, Nirnaya Sagar Press, KM No. 40, Bombay, 1922.
  25. Dhvanyāloka of Ānandavardhanācārya, Kāśī Sanskrit Series, Alaṅkāra section No. 5, Banaras, 1940.
  26. Nāṭakalakṣaṇaratnakoṣa of Sāgaranandin, ed. by Myles Dillon, Vol. I Text, Oxford University Press, London, 1937.
  27. Nāṭyadarpaṇa of Rāma Candra and Guṇa Candra, with their own commentary, Gaekwad Oriental Series, 1929.
  28. Nāṭyaśāstra of Bharata [editions of Nāṭyaśāstra: Kāvya-mālā Sanskrit Series No. 42, 1894; Kāśī Sanskrit Series No. 60, 1929; Gaekwad Oriental Series Vol. I No. 36,

- 1926 and Vol. II No. 68, 1934, Chapters I—XIV ed. by J. Grosset, XVI-XVII by P. Regnaud in his *rhétique Sanskrite*, XVIII-XX, XXIV by F. Hall in his edition of *Daśarūpa*; *Bhāratīya Nāṭyaśāstra* written by Godavari Vasudeva Ketakar in Marathi, Aryabhushana Press, Poona, 1928.
29. *Nirukta* of Yāska, with commentary by Durgācārya, Sri-Venkateshvara Steam Press, Bombay, Samvat 1982.
30. *Pañcadaśī* by Vidyāraṇyasvāmī, with English translation, Bombay, 1912
31. *Pārvatī-Parīṇaya* of Śrī Bāṇabhaṭṭa, Nirṇaya Sagar Press, Bombay, 1923.
32. *Pratāparudrīya* of Vidyānātha, with *Ratnapana* of Kumārasvāmin, ed. by Chandra Shekhar Shastri, Madras, 1914.
33. *Prabodhacandrodaya* of Kṛṣṇamiśra, with *Candrikā* and *Prakāśa* commentaries, Nirṇaya Sagar Press, Bombay, 1904.
34. *Priyadarśikā* by Śrī Harṣa, ed. by Jīvānanda Vidyāsāgara, Calcutta, 1874.
35. *Bālabhārata* of Rājaśekhara, ed. by Durgā Prasāda and Parab, KM No. 4. Bombay, 1887.
36. *Bāla Rāmāyaṇa* of Rājaśekhara, with Jīvānanda commentary, Valmiki Press, Calcutta, 1884.
37. *Bṛhaddeśī* of Maṇḍamuni, ed. by K. Sambaśiva Śāstrī, Trivandrum Sanskrit Series No. XCIV, Trivandrum 1928.
38. *Bhagvadbhaktirasāyana* of Madhusūdana Sarasvatī, with Sanskrit *ṭika* by Goswami Damodara Shastri, *Acyuta granthamālā* II Puṣpa Kāśī, Vikram, 1984.
39. *Bhāvaprakāśana* of Śāradātanaya, Gaekwad Oriental Series No. 45, Baroda, 1930.
40. *Bhāsanāṭakacakra*, ed. by C.R. Devadhar, Poona Oriental series No. 54, Poona, 1937. It contains the following 13 dramas of Bhāsa : *Svapnavāsavadattā*, *Pratijñāyugandharāyaṇa*, *Avimāraka*, *Cārudatta*, *Pratimā*, *Abhiṣeka*,

- Pañcarātra, Madhyamavyāyoga, Dūtavākya, Dūtaghaṭ-  
tkaca, Kaṇabhāra, Ūrubhaṅga and Bālacarita.
41. Manusmṛti by Manu, with commentary by Kullukabh-  
aṭṭa, and ed. by Vāsudeva, Nirnaya Sagar Press,  
Bombay. 1902.
  42. Mahābhārata, I with commentary of Nilakaṇṭha, Chitra-  
Shala Press Poona, 1929; III. and V. ed. by S. Sukthankara,  
Bhandarkar Oriental Research Institute, Poona, 1941, 1937.
  43. Mahābhāṣya of Patañjali, ed. by Kielhorn, Bombay, 1883.
  44. Mahāvīracarita of Bhavabhūti, with commentary of Vīra-  
rāghava, ed. by T. R. Ratnam Aiyar, Nirnaya Sagar Press.  
Bombay, 1901.
  45. Mānasāra Śilpāśāstra, ed. by P. K. Acharya, Oxford Univ-  
ersity Press, London, 1933.
  46. Mārkaṇḍeyapurāṇa of Vedavyās, Calcutta, Śaka, 1812.
  47. Mālatīmādhava of Bhavabhūti, ed. by M. R. Kale, Gopal  
Narayana and Co., Kalbadevi Road, Bombay, 1928.
  48. Mālavikāgnimitra of Kālidāsa, with commentary of Kaṭa-  
yavema, Nirnaya Sagar Press, Bombay, 1930.
  49. Mudrārākṣasa of Viśākhadatta, ed. by Saradaranjan Ray,  
Harrison Road, Calcutta, 1929.
  50. Mr̥cchakaṭika of Śūdraka, with commentary of Pṛthvī-  
dhara, and notes by M. R. Kale, 1924.
  51. Meghadūta of Kālidāsa, with commentary by Mallinātha,  
ed. by Kāśinātha 2nd ed., Poona, 1916.
  52. Yājñavalkyasmṛti, Anandashrama Press, Vol. I, 1903;  
Vol. II 1904.
  53. Raghuvamśa of Kālidāsa, VI-X sargas, Kāśī Sanskrit  
Series No. 84, 1987.
  54. Ratnāvalī of Śrī Haṛṣadeva, with notes by M. R. Kale,  
Bombay, 1925.
  55. Rasārṇavasudhākara of Singhabhūpāla, ed. by T. Gaṇa-  
pati Śāstrī, Trivandrum Sanskrit Series. No. L. Trivan-  
drum, 1916.
  56. Rāgavibodha of Somanātha, with Sanskrit commentary,  
Śaka, Lahore, 1817.

57. Rāmāyaṇa of Vālmīki, with commentary, Nirnaya Sagar Press, Bombay, 1824.
58. Rūpakaṣaṭakam, a collection of six dramas of Vatsarāja, ed. by D. Dalal, Gaekwad Oriental Series No. VIII, Central Library, Baroda. 1918. It contains the following six dramas: Kirātārjunīyavyāyoga [ PP. 1-22 ], Karpūracaritaḥṇa [ PP. 23-36 ], Rukmiṇiharaṇa ihāmṛga [ PP. 37-44 ], Tripuradāhaḍima [PP. 75-119], Hāsyacūḍamaṇi prahasana [PP. 118-148], Samudramanthana Samavakāra [PP. 148-192].
59. Vikramorvaṣīya of Kālidāsa, with Kaṭayavema's commentary and ed. by Cārudeva Śāstrī, Lahore, 1929.
60. Viddhaśālabhañjikā of Rājaśekhara, with commentary of Jivānanda, Calcutta, 1873 and with Sanskrit ṭikā and preface by B. R. Arte and K. R. Godbole, Poona, 1886.
61. Viṣṇudharmottarapurāṇa, ed. by Madhusūdana Mādhava prasāda., Venkateshvar Press, Bombay.
62. Viṣṇusmṛti of Viṣṇu, ed. by Julius Jolly, Asiatic Society, Calcutta, 1881.
63. Śākuntala, Abhijñana, of Kālidāsa, with notes by M. R. Kale, Bombay 1934.
64. Śilparatna of Śrīkumāra, ed. by Gaṇapati Śāstrī, I, Trivandrum Sanskrit Series, No. LXXV, 1922.
65. Śuklayajurveda Samhitā [ Vajasaneyī Samhitā ], with Mantrabhāṣya of Uvaṭācārya and Vedadīpabhāṣya of Mahidhara, ed. by Wasudeo Lakṣhmaṇa Śāstrī Pansikar, Nirnaya Sagar Press, Bombay, 1929.
66. Śrīmadbhāgavata Purāṇa, in two khaṇḍas, with Bālabodhinī bhāṣāṭikā by Pt. Govindadāsa Vyāsa 'vinīta' saṁvat 1991.
67. Saṅgītapārijāta of Ahobala Pandit, ed. by Kalindajī, Sangit Karyalaya, Hatharas, 1941.
68. Sāṅgīta-Makaranda of Nārada, ed. by Maṅgeśa Rāma Kṛṣṇa Telāṅg, Gaekwad Oriental Series No. XVI, Baroda, 1920.

69. Saṅgitaratnākara of Śaraṅgadeva, with Kallinātha, commentary I and II by Maṅgeśa Rāma Kṛṣṇa Telaṅga, Ānandāśrama Sanskrit Granthāvali No. 35, Bombay, 1896, 1897.
70. Saṅgītasamayāsāra of Saṅgītakara Śrī Pārśvadeva, ed. by T. Gaṇapati Śāstri, Trivandrum Sanskrit Series No. LXXXVII, 1925.
71. Sāhityadarpaṇa of Viśvanātha, with commentary by Hari-dāsa Siddhāntavāgīśabhaṭṭa Vaṅgabda Nakipur Siddhanta Press, 1335.
72. Siddhānta Kaumudī of Bhaṭṭoji Dīkṣita, with Tattva-bodhini, Subodbhīni, Candrāloka commentaries, Sri Venka-tesvar Steam Press, Bombay, 1926.
73. Subhaṣitatriśati by Bhartṛhari, ed. by Vāsudeva, Bombay, 1914.
74. Hanumannāṭaka or Mahānāṭaka, with bhāṣāṭikā, Lakshmi Venkateshvar Press, Bombay, 1924.
75. Harivaṁśa, with commentary, Bombay, 1895.
76. Harṣacarita of Bāṇabhaṭṭa, ed. by P. V. Kane, Bombay, 1918.

**B. Articles and works in English on Indian Stage  
and kindred topics consulted and  
cited only where necessary**

1. A. C. Woolner and Lakshmana Sarup, 'Translation of Thirteen Trivandrum plays attributed to Bhāsa' Oxford University Press, London, Vol. I, 1930 and Vol. II 1931.
2. A. D. Pusalkar, article on 'Critical study of the works of Bhāsa', Journal of the University of Bombay, Vol. II Part VI May, 1934.
3. A. K. Coomaraswamy and Duggirala Gopal Krisnayya, 'The Mirror of Gesture' translation of Abhinayadarpaṇa, London 1917, New York, 1936.
4. A. K. Coomaraswamy, 'The Dance of Śiva', 14 Indian Essays, New York, 1918.
5. A. K. Coomaraswamy, article on 'Hindu Theatre' in Indian Historical quarterly Vol. IX, Calcutta, 1933.

6. Alain Danielon, 'Northern Indian Music', London: Christopher Johnson Vol. 1. Calcutta, Vishva Bharati, 1949.
7. A. Sankaran, 'Some Aspects of Literary Criticism in Sanskrit literature' or 'The theories of Rasa and Dhvani' Madras, 1929.
8. Bloch, article on 'Caves and Inscriptions in Ramgarh hills', published in 'Archaeological Survey of India Annual Report, 1903-4.
9. Brajendra Nath Banerjee 'Bengali Stage', Ranjan Publishing House', 1943.
10. Cintaharana Cakravarti, articles on 'Saṭṭaka' and 'Bharata-Vākya' in Indian Historical Quarterly. Vol. VII. 1931 and Vol. VI. 1930.
11. C. O. Hass, 'Translation of the Daśarūpa' Columbia University Press, 1912.
12. D. R. Mankad, 'Types of Sanskrit Drama' Urmi Prakashan Mandir Denso Hall, Karachi, 1930.
13. D. R. Mankad, article on 'Hindu Theatre' in Indian Historical Quarterly, Vol. VIII, Calcutta 1932, Vol. IX, 1933.
14. D. R. Mankad, 'Ancient Indian Theatre', Charutar Prakashan Vallabh Vidyanagar 1950.
15. E. Clements, "Indian Music" Longmans, Green, & Co. London, 1913.
16. Gaṅgānātha Jhā, 'Translation of Kāvya-prakāśa' of Mammata, Allahabad, 1925.
17. Guha-Thakurta, P, The Bengali Drama, its Origin and Development, London, 1930.
18. Haigh, 'Attic Theatre' III ed.
19. H. N. Des Gupta, 'The Indian stage' Vols. I and II, Calcutta, 1934 and 1938.
20. Harprasad Shastri, article on 'The Origin of Indian Drama' in journal and proceedings of the Asiatic Society of Bengal, New Series Vol. V, 1909.
21. Itsing, a record of Buddhistic Religion practised in India

and the Malay Archipalego [ 671-695 A. D. ], translated by J. Takakusa, Oxford, 1896.

22. ✓ Keith, 'The Sanskrit Drama' in its Origin, Development, Theory and Practice, Oxford, 1924.
23. K. R. Pisharoti's article on 'The Ancient Indian Theatre' published in Rajah Sir Annamalai Chettiar Commemoration Volume, 1941.
24. Levi, 'Le Theatre Indien' Paris, 1890.
25. Luders, 'Sitzungsherichte der Konigl Akademie der Wissenschaften Zu Berlin,' 1916.
26. Macdonell, 'A History of Sanskrit Literature', London, 1905.
27. Manomohan Ghosh, article on 'Problems of the Nāṭya-śāstra' in Indian Historical Quarterly. Vol VI. 1930.
28. Manomohan Ghosh, article on 'Hindu Theatre' in Indian Historical Quarterly, Vol. IX, Calcutta 1933.
29. Manomohan Ghosh, 'English Translation of the Nāṭya-śāstra, chapters I to XXVII,' Royal Asiatic Society of Bengal, Calcutta, 1951.
30. Monier Williams, 'A Sanskrit-English Dictionary', Oxford Clarendon Press, 1899.
31. Mulk Raj Anand, 'The Indian Theatre', London, Dennis Dohson Ltd.
32. Naidu and Pantab, 'Tāṇḍavalakṣaṇa,' G. S. Press, Madras, 1936.
33. P. K. Acharya, 'A Dictionary of Hindu Architecture,' Oxford University Press, London [University of Allahabad], 1927.
34. ✓ P. K. Acharya, article on 'The Play-house of the Hindu Period,' published in Dr. S. K. Aiyangar Commemoration Volume.
35. P. K. Gode, article on 'The Bharata-Ādi-Bharata Problem and the MS of Ādi-Bharata in the Government Oriental Library, Mysore'. Annals of the Bhandarkar



- Oriental Research Institute, Poona, Vol. XIII, 1931-32
36. Pischel, 'Die Heimat des Puppenspiels', 1902.
  37. P. V. Kane, 'Introduction to Sāhityadarpaṇa', The History of Alaṅkāra Literature, Bombay, 1923.
  38. R. K. Yajnik, 'The Indian Theatre', London, 1933.
  39. Ridgeway, 'The Dramas and Dramatic Dances of Non-European Races,' Cambridge, 1915.
  40. Ridgeway, article on 'Cult of the Dead' in Journal of Royal Asiatic Society of Great Britain and Ireland, 1916.
  41. Schuyler, 'Bibliography of the Sanskrit Drama' with an introductory sketch of the Dramatic Literature of India, Columbia University Press, Indo-Iranian Series, Vol. III, 1906.
  42. S. C. Mukerjee, 'The Nāṭyaśāstra of Bharata' Chapter VI, ed. with an English translation of Rasādhyāya, Paris, 1926.
  43. S. K. De, 'Studies in the History of Sanskrit Poetics' vol. II, 1925.
  44. S. K. De, 'The curtain in Ancient Indian Theatre,' published in Bhāratīya Vidyā, Vol. IX, 1948.
  45. S. M. Tagore, 'The Eight Principal Rasas of the Hindus' with Murthi and Vrindaka, Calcutta, 1880.
  46. Stella Kramrisch, 'Translation of Viṣṇu-dharmottara, Part III,' a treatise on Indian Painting and Image-making, Calcutta University Press, 1928.
  47. V. Raghavan, 'The number of Rasas,' Adyar, Madras, 1940.
  48. V. Raghavan, 'Some Concepts of Alaṅkāraśāstra,' Adyar, Madras, 1942.
  49. V. Raghavan, articles on 'Ancient Indian Theatre Architecture,' in Journal Triveni of Madras, 1932-35.
  50. V. Raghavan, 'Nāṭyadharmī and Lokadharmī' in the Journal of Oriental Research, Madras, Vol. VII and VIII, 1933 and 1934.
  51. V. Raghavan, article on 'Hindu Theatre' in Indian Historical Quarterly, Vol. IX, Calcutta, 1933.

52. V. S. Apte, 'The Practical Sanskrit-English Dictionary,' Bombay, 1924.
53. V. S. Agarwala, 'Study of Rājaghāṭa Toys' in Nāgarī-pracārīṇī Patrikā, Kārtika Samvat, 1997.
54. Wilson, 'Select Specimens of the Theatre of the Hindus,' Vol. I, 1827.
55. Windisch, 'Der griechische Einfluss im indischen Drama,' 1882.
56. Winternitz, 'Some Problems of Indian Literature,' Calcutta University Press, 1925.

# INDEX

## A. Sanskrit Dramatic Terms, Works and Dramatists

- Amśa, 91  
Amśopitika, 78  
Akampita, 95  
Agnipurāṇa, 122, 139  
Aṅka, 106, 142, 143, 145  
Aṅkamukha, 131, 132  
Aṅkāvatāra, 131  
Aṅkāśya, 131  
Aṅga, 94, 144  
Aṅgada, 77, 78  
Aṅgaracanā, 73, 82, 84, 85, 180  
Aṅgavyāpāra, 138  
Aṅgaśauṣṭhava, 100  
Aṅgaḥāras, 99, 138  
Aṅgula, 32, 75, 76, 80, 81  
Aṅgulimudrā, 77  
Aṅgulīyaka, 78  
Ajjukā, 133  
Aṇu, 32  
Atihāśya, 153  
Attā, 133  
Atharvaveda, 3  
Advibhūmi, 37  
Adbhuta, 84, 152  
Anargharāghava, 13, 22, 150  
Anucārikā, 111  
Anudātta, 90  
Anumitivāda, 17  
Anuraṇana, 53  
Anurūpā, 104, 181  
Anuvādī, 90  
Anuṣṭubh, 103  
Anyā, 111  
Apati, 63, 64  
Apatikṣepeṇa, 56, 57  
Apanītā, 56  
Apabhraṁśa, 149  
Apavārita, 132  
Abaraka, 86, 87  
Abhijñānaśākuntala, 21, 61, 63, 67, 68, 73, 74, 86, 98, 102, 109, 130, 134, 146, 149, 151, 153, 166, 168, 173, 175  
Abhinaya, 3, 14, 15, 72, 97, 100, 101, 113, 120, 136, 138, 140  
Abhinayadarpaṇa, 4, 21, 79, 96, 97, 113, 121  
Abhinayavidyā, 100  
Abhinavagupta, 12, 18, 20, 31, 33, 34, 37, 46, 47, 49, 50, 51, 52, 53, 56, 74, 91, 122, 137, 138, 139, 178  
Abhinavabhāratī, 34, 52, 60, 61, 81, 91, 138  
Abhinayācāryas, 100  
Abhivyaktivāda, 18  
Amarakoṣa, 62  
Amātya, 110, 132  
Arthaśāstra, 7, 12, 32, 116, 118  
Arthopakṣepakas, 131, 177  
Ardhamāgadhi, 128  
Ardhamukuṭa, 80  
Alaka, 85, 172

- Alaṅkāra, 73, 77, 81, 98, 180  
 Alaukika, 20  
 Avakruṣṭa, 153, 154  
 Avataraṇa, 119  
 Avadānaśataka, 6, 149  
 Avanaddha, 92, 180  
 Avantijā, 128, 129  
 Avarohī, 91  
 Avaloka, 74, 119, 133, 145, 146  
 Avimāraka, 57, 59  
 Aśocaḥ, 115  
 Aśvaghoṣa, 8, 12, 148  
 Asi, 76  
 Asita, 83, 84  
 Asragīta, 145  
 Ahokāra, 153  
 Ākāśagāmī, 96  
 Ākāśabhāṣita, 132, 143, 144  
 Ākāśika, 96  
 Āg Gārī, 170  
 Āgneya, 50  
 Ācāryas, 97, 107, 132, 137, 180, 181  
 Āṅgika, 15, 72  
 Āṅgikābhinaya, 94, 95, 98  
 Ātasya, 65  
 Ātodya, 119  
 Ātmagata, 132  
 Ādibharata, 122, 123  
 Ābharaṇakṛt, 107  
 Ābhīrī, 128, 129  
 Ābhyantaragaṇa, 111  
 Āyuṣman, 132  
 Āyogava, 116  
 Ārabhaṭī, 16, 106  
 Ārambha, 119  
 Āropya, 77  
 Ārohi, 91
- Ārya, 132  
 Āryaputra, 133  
 Āryamañju-Śrīmūla-Kalpa, 65  
 Āvantī, 129  
 Āviddha, 106  
 Āvedhya, 77  
 Āśrāvaṇā, 119  
 Āsārīta, 119  
 Āhārya, 15, 72  
 Āhāryābhinaya, 72, 73, 77, 82  
 86, 87, 138, 154  
 Āhuti, 172, 173  
 Indradhvaja, 10, 21  
 Indranīlamanī, 79  
 Indra Sahhā, 171  
 Iṣvastravit, 114  
 Ihāmṛga, 106, 141, 142, 146  
 Uccā, 103  
 Uccitika, 77  
 Uttarakāmarita, 11, 22, 26, 67, 68, 72, 102, 107, 111, 130, 134, 150, 153  
 Utsṛṣṭikāṅka, 142  
 Utthāpana, 120  
 Utpattivāda, 17  
 Udayanacarita, 74  
 Udātta, 90  
 Uddhata, 138  
 Uddhatamiśra, 138  
 Uparūpaka, 139, 140, 144, 146, 147  
 Upāṅga, 94  
 Upādhyāya, 37, 51  
 Ullāpya, 145  
 Ūrubhaṅga, 130  
 Ūha, 45  
 Ṛgveda, 3, 5, 136  
 Ṛṣabha, 89

- Aindrajālika, 7  
 Aīśāna, 50  
 Audri, 128  
 Autpātika, 155  
 Aupasthāyika, 111  
 Kakṣyā, 38, 41, 42, 45, 49, 61, 68, 179  
 Kakṣyāvibhāga, 38  
 Kañcukin or Kañcukiya, 111  
 Kaṭaka, 78  
 Kaṇaya, 76  
 Kathākālī, 94, 160, 163  
 Kanāta, 62  
 Kapota, 83, 84  
 Kapotālī, 45  
 Karaṇa, 96, 99  
 Karbalā, 172  
 Karuṇa, 20, 84, 130, 152  
 Karṇacūlikā, 79  
 Karṇapūra, 78  
 Karṇamudrā, 78  
 Karṇavalaya, 78  
 Karṇasundarī, 69  
 Karṇikā, 78  
 Karṇotkilaka, 78  
 Karpūramañjarī, 105, 127, 150, 171  
 Kalahakandala, 22  
 Kalaka, 79  
 Kalākāra, 172, 173, 174  
 Kalāpa, 78  
 Kaliñja, 74, 86  
 Kallinātha, 88  
 Kaṣāya, 81, 83  
 Kaṣṭa, 153  
 Kāmpandī, 76  
 Kāmpita, 95  
 Kāmsavadha, 8  
 Kākapada, 85  
 Kāku, 103  
 Kāñcī, 78  
 Kāṭhakam, 5  
 Kāmasūtra, 12  
 Kāyābhīnaya, 1  
 Kālapriyanātha, 22, 26  
 Kāruka, 108  
 Kālidāsa, 22, 23, 70, 85, 102, 111, 137, 147, 148, 149, 173, 175  
 Kālina, 75  
 Kāvya, 145  
 Kāvya prakāśa, 14, 19  
 Kāvya mīmāṃsā, 25  
 Kiṅkiṇī, 78  
 Kiṅkiṇī-cakravāla, 79  
 Kirātārjunīya-vyāyoga, 24, 69, 146  
 Kirīṭī, 80  
 Kila, 77  
 Kuṭṭanimata, 56, 105, 149  
 Kuṭṭima, 46  
 Kuṇḍala, 77  
 Kutapa, 119  
 Kunta, 75  
 Kundamālā, 23  
 Kumāra, 110  
 Kumbhīpadaka, 79  
 Kulastri, 111  
 Kulinakulasarvasva, 164  
 Kuśilava, 7, 108, 116  
 Kusumāvacaya, 98  
 Kuhara, 45  
 Kṛṣṇa, 84  
 Kṛṣṇamiśra, 151  
 Kṛṣṇalīlā, 170, 175  
 Keyūra, 77

Keśaracanā, 84  
 Kaiśikī, 16, 69, 144, 146  
 Koṇa, 46  
 Kauṣītaki Brāhmaṇa, 5  
 Kriyā, 100  
 Kriḍāniyaka, 3  
 Khaṇḍa, 96  
 Khaṇḍapātra, 78  
 Khaṇḍamātrā, 145  
 Kharjura, 78  
 Kheṭaka, 76  
 Khyāla, 169  
 Gaṇa, 4  
 Gaṇapati Śāstrī, 8  
 Gaṇikā, 7, 111  
 Gadā, 76  
 Gandharva, 114  
 Gati, 96, 97  
 Gaddāra, 172, 173  
 Gamaka, 89  
 Gambhirā, 161  
 Garbhasandhi, 144  
 Gavākṣa (window), 45, 46  
 Gavākṣa (ornament), 78  
 Gātravikṣepa, 137, 138  
 Gāndhāra, 89, 90  
 Gāyaka, 6, 93, 94, 119  
 Gāyikā, 93  
 Gita, 3, 88, 119  
 Guṇacandra, 20  
 Goṣṭhī, 144  
 Graha, 91  
 Grāma, 90, 91  
 Gaura, 83, 84  
 Ghaṭṭita, 65  
 Ghana, 92, 180  
 Ghāta, 155, 182  
 Cakra, 76

Caturasra, 30, 31, 34, 39, 46, 47,  
 49, 50, 51, 52, 178  
 Caturbhāṇi, 146  
 Candrahāsa, 172  
 Carma, 76  
 Calita, 101, 115, 136, 137  
 Cāṇḍālī, 128, 129  
 Cāmara, 76  
 Cārī, 96, 97, 120  
 Citrakara, 108  
 Citraturaganyāya, 18  
 Citravat, 114  
 Citrābhinaya, 97  
 Cūḍāpāśa, 85  
 Cūdāmaṇi, 77, 78  
 Cūlikā, 131  
 Ceṭa, 110, 128  
 Ceṣṭita, 74  
 Chatra, 76  
 Chandovit, 114  
 Chalika, 136  
 Chalita, 136  
 Chāyānāṭaka, 11  
 Janānta or Janāntika, 132  
 Jarjara, 3, 71, 76, 120, 125, 126  
 Jarjarapūjā, 120  
 Jarjaraśloka, 120  
 Javanikā, 55, 56, 61, 62, 63,  
 64, 179  
 Javanīkāntara, 133, 145  
 Jātakas, 102  
 Jānakī Maṅgala, 171  
 Jāyājīva, 116  
 Jāla, 45  
 Jṛmbhaka, ( missiles ), 67  
 Jhallarī, 94  
 Ṭhāṭa, 91  
 Dakkinī, 94

- Dīma, 31, 106, 142, 146  
 Dhakktī, 129  
 Taṇḍu, 4, 99  
 Tata, 92, 180  
 Tantrās, 102  
 Tantrī, 119  
 Tapti-svayamvara, 151  
 Tamāśā, 166  
 Tarala, 77  
 Taliya, 74  
 Tāṇḍava, 4, 99, 100, 120  
 Tāta, 132, 133  
 Tāla, 75, 76, 88, 137, 138, 145  
 Tīraskariṇī, 56, 62, 63  
 Tilaka, 78  
 Tīlottamā, 172  
 Tepita, 81  
 Toṭaka, 144  
 Tomara, 75  
 Taurika, 108  
 Tauryaṭṭka, 88, 107  
 Trigata, 120  
 Tripatākā, 96, 132  
 Tripuradāha, 4, 99, 146  
 Trisara, 77  
 Troṭaka, 139, 144, 145, 146  
 Tryasra, 30, 31, 34, 43, 46, 47, 51, 52, 178  
 Daṇḍa, 31, 32, 76  
 Daṇḍaka, 103  
 Dantapatra, 78  
 Dardura, 94  
 Daśarūpa, 13, 74, 119, 122, 129, 131, 133, 137, 139, 140, 141, 142, 143, 144, 145, 146  
 Daśāvatāsam, 161, 163  
 Dākṣiṇātyā, 128, 129  
 Dāmodaragupta, 149  
 Dārūkarma, 72  
 Dīkpālastuti, 120, 126  
 Digghanikāya, 6  
 Dīnnāga, 23  
 Dīptā, 103  
 Divyā, 110  
 Dīvāra, 172, 173, 174  
 Dundubhi, 94  
 Durgāpūjā, 162  
 Durmallikā, 146  
 Durmallī, 146  
 Duṣprajyā, 101  
 Dūta, 110  
 Dūtavākya, 127  
 Dūtāṅgada, 23, 151  
 Duḥkhātmaka, 20  
 Dr̥śyakāvyas, 13  
 Deva, 133  
 Devatā, 172  
 Devī, 111, 133  
 Deśī, 88, 137  
 Daivikī, 153, 154  
 Drāviḍī, 128, 129  
 Druta, 97  
 Drutā, 103  
 Dvāra, 46  
 Dvipadikā, 145  
 Dvipadikhaṇḍa, 92  
 Dvibhūmi, 37  
 Dhanañjaya Vijaya, 171  
 Dhanu, 75  
 Dharanī, 45  
 Dharmī, 15  
 Dhīralalita, 108, 109  
 Dhīraprasānta, 141  
 Dhīrasānta, 109  
 Dhīrodātta, 109, 140  
 Dhīroddhata, 109

- Dhūrtaviṭaṣaṁvāda, 21  
 Dhaivata, 89  
 Dhauta, 65  
 Dhruvasvāminī, 172  
 Dhruvā, 55  
 Dhvaja, 76  
 Dhvani, 14, 88  
 Dhvanyāloka, 14  
 Naṭa, 5, 6, 7, 8, 12, 17, 23, 52,  
 69, 81, 83, 97, 108, 116,  
 122, 138, 154, 179, 180  
 Naṭarāja, 98, 99  
 Naṭasū'ras, 8, 95  
 Naṭī, 21, 105  
 Nandikeśvara, 4  
 Nartaka, 5, 6, 114, 116  
 Nartakī, 138  
 Nartana, 88  
 Napuṁsaka, 111  
 Narmasaciva, 109  
 Narmasuhṛd, 109  
 Navataṅkī, 162, 172, 174, 183  
 Navanna, 165  
 Nāgaraka, 7  
 Nāgānanda, 149, 151  
 Nāgdanta, 46  
 Nāṭaka, 5, 106, 131, 140, 141,  
 144, 146, 149, 150, 151  
 Nāṭakābhinaya, 6  
 Nāṭakamaṇḍalī, 7, 153, 155, 156,  
 163, 166  
 Nāṭakalakṣaṇaratnakosa, 13, 70,  
 122, 137  
 Nāṭakīyā, 108  
 Nāṭamandira, 26, 29  
 Nāṭikā, 22, 139, 144, 146  
 Nāṭī, 144  
 Nāṭya, 4, 8, 21, 96, 102, 105,  
 106, 108, 136, 137, 138, 139,  
 140, 154, 177  
 Nāṭyagrha, 24, 52  
 Nāṭyadarpaṇa, 20, 122, 123  
 Nāṭyadharmā, 132  
 Nāṭyadharmī, 15  
 Nāṭyamāṇḍapa, 24, 30, 37, 53,  
 125  
 Nāṭyarāsaka, 145  
 Nāṭyaveda, 3, 4, 124  
 Nāṭyaveśman, 33  
 Nāṭyaśālā, 53, 116  
 Nāṭyaśāstra, 3, 30, 31, 32, 33,  
 38, 42, 45, 47, 48, 49, 50,  
 51, 52, 53, 55, 60, 61, 66, 69,  
 70, 71, 73, 75, 76, 77, 80, 82,  
 84, 85, 92, 93, 94, 95, 96,  
 97, 99, 100, 101, 102, 105, 106,  
 107, 109, 110, 111, 113, 114, 117,  
 119, 121, 122, 123, 124, 126, 127,  
 131, 132, 137, 144, 148, 175, 178  
 Nāṭyakāra, 108  
 Nāṭyācārya, 97, 106, 181  
 Nāda, 89  
 Nāḍikā, 71, 141, 146, 155  
 Nāṇḍī, 120, 121, 122, 123, 124,  
 145, 177  
 Nāyaka, 108  
 Nāyikā, 110  
 Nirukta, 5  
 Nirmuṇḍa, 111  
 Nirāhuta, 115  
 Nirbrahmaṇa, 115  
 Niṣāda, 89  
 Nīla, 82, 84  
 Nīlakaṇṭha, 69  
 Nirvyūha, 45, 46



- Nicā, 103  
 Nūpura, 77, 78, 79  
 Nṛtta, 4, 5, 21, 95, 136, 137, 138, 139, 177  
 Nṛttakāvyas, 138  
 Nṛtya, 4, 88, 136, 137, 138, 139, 140, 145, 177  
 Nṛtyaśālā, 53  
 Nṛtta-sabhā, 99  
 Nṛpapatnī, 111  
 Nepathye, 56  
 Nepathyagrha, 34, 35, 38, 39, 43, 46, 47, 51, 52, 55, 57, 60, 68, 179, 180  
 Nairṛta, 50  
 Nyāsa, 91  
 Pañca, 155  
 Pañcadaśī, 65  
 Pañcama, 89  
 Pancarātra, 128, 146  
 Paṭa, 63, 66  
 Paṭaha, 94  
 Paṭi, 56, 63, 64  
 Paṭī, 80  
 Paṭṭisa, 76  
 Paṭhāna, 172, 173, 174  
 Paṇa, 7  
 Paṇava, 93  
 Patañjali, 8, 12  
 Patākā [Episode], 109, 140  
 Patākā [Flag hand], 96  
 Patākā [Banner], 155, 156, 182  
 Patrapūraka, 78  
 Patralekhā, 78  
 Pattara, 76  
 Padma, 86  
 Padmamāṇi, 79  
 Parighaṭṭanā, 119  
 Paricārikā, 111  
 Parivartana, 120  
 Pariṣad, 113  
 Pāṭhya, 3  
 Pāṇavika, 93  
 Pāṇḍu, 83  
 Pāṇini, 8, 62, 136  
 Pāda, 120, 121, 122, 123, 124  
 Pādapātra, 78  
 Pāripārśvika, 105, 107, 120, 121, 123, 124  
 Pārvatīpariṇaya, 21  
 Pārśvamaulī, 80  
 Pārśvagata, 80  
 Pīṭha, 45  
 Piṇḍibandhas, 99  
 Pīṭhamarda, 7, 109, 146  
 Pīta, 82, 84  
 Putraka, 133  
 Purohita, 110  
 Puṣya, 33, 125  
 Pusta, 73, 74  
 Pūrvaraṅga, 55, 119, 120, 121, 122  
 Pūrvaraṅga [Caturasra], 120  
 Pūrvaraṅga [Tryasra], 120  
 Pūrvaraṅga [Citra], 120  
 Pekkhāghara, 53  
 Paisāci, 129  
 Powada, 166  
 Prakaraṇa, 31, 106, 131, 141, 144, 146  
 Prakaraṇikā, 146  
 Prakarī, 140  
 Prakāśa, 132  
 Prakhyāta, 141  
 Prakṣepya, 77  
 Pratāpa [name of drama], 164

Pratāparudriya, 123, 137	Prekṣāgrha, 24
Pratijñāyugandharāyaṇa, 57, 74, 76	Prekṣāpati, 122
Pratidvāra, 46	Preṅkhaṇa, 145
Pratināyaka, 109	Prema ki Vedī, 172
Pratimānāṭaka, 76	Baḍā Tamāśā, 161
Pratisīrā, 63, 80	Bandhanīya, 77
Pratihārī, 111	Balibandha, 8
Pratyaṅga, 94	Bāṇa, 4, 117
Pratyāhāra, 119	Bāhya, 110
Pratyūha, 45	Bāla, 32
Prabodhacandrodaya, 23, 127, 151	Bālacarita, 76, 101
Pramāṇa, 32	Bālabbhārata, 150
Prayoga, 100	Bālārāmāyaṇa, 74, 133, 150
Prarocanā, 120, 121, 122, 145	Bālhikā, 128, 129
Pralambita, 81	Bilva, 80
Pravṛtti, 16	Bija, 131
Pravṛdhanāda, 153	Bibhatsa, 20, 84, 113, 152
Praveśaka, 131, 144	Burrakathās, 163
Prasādhana, 98	Bṛhaddeśī, 88, 89, 90, 91
Prastāvanā, 121	Baudha-ākhyāna, 102
Prasthāna, 145	Bhagavadajju, 151
Prasthānaka, 145	Bhagavadbhaktirasāyana, 20
Prahasana, 32, 143, 146, 160, 182	Bhagavan, 132
Prākṛta, 9, 62, 63, 64, 127, 128, 129, 131, 133, 144, 177	Bhagnatāla, 145
Prācyā, 128, 129	Bhaṭṭhari, 117
Prāḍvivāka, 110	Bhaṭṭa Lollāṭa, 17
Prāśnika, 71, 114, 115, 155, 156, 182	Bhaṭṭa Nāyaka, 18
Prāsa, 75, 76	Bhaṭṭā, 133
Prāsaṅgika, 109	Bhaṭṭinī, 133
Priyadarśikā, 105, 146, 149	Bhaṭṭoji Dikṣita, 62
Priye, 133	Bhayānaka, 20, 84, 152
Pṛthvidhara, 129	Bharata, 3, 4, 5, 12, 13, 14, 15, 16, 17, 21, 30, 33, 53, 72, 74, 75, 76, 77, 78, 81, 82, 89, 95, 99, 100, 105, 107, 111, 115, 117, 118, 119, 120, 122, 123, 124, 125, 126, 128, 129, 131, 133, 134, 139, 140, 144, 178
Prekṣāgāra, 24	

- Bhaṛata Nāṭyam, 94, 164  
 Bhārataputras, 117  
 Bharataavākya, 177  
 Bhalla, 116  
 Bhavāi, 161, 183  
 Bhavabhūti, 22, 70, 102, 111, 112, 118, 148, 150, 175, 181  
 Bhagavat, 143  
 Bhāgavatam, 160, 183  
 Bhāṇa, 32, 106, 109, 132, 143, 144, 146, 160, 182  
 Bhāṇikā, 146  
 Bhāṇī, 146  
 Bhāṇḍavādya, 138  
 Bhāratī, 16, 122  
 Bhāva, 14, 15, 19, 20, 100, 101, 103, 114, 137, 139  
 Bhāvaprakāśana, 4, 30, 123, 137, 139, 140  
 Bhāvātmaka, 140  
 Bhāsa, 8, 12, 102, 120, 121, 130, 146, 147, 148, 151, 175  
 Bhiṇḍi, 75  
 Bhūmi, 37  
 Bhūmikā, 104  
 Bhr̥ṅgāra, 76, 120  
 Bheṇḍa, 74, 86, 87  
 Bhojakatva, 18  
 Bhauma, 96  
 Bhramarabādhā, 98  
 Bhrūkumśa, 105  
 Makarikā, 78  
 Maṇḍapa, 37, 45, 50  
 Maṇḍalas, 96, 97  
 Mataṅga, 88  
 Mattavarāṇa, 49  
 Mattavarāṇis, 33, 34, 37, 46, 48, 49, 52, 72, 93, 126  
 Mattavilāsa, 151  
 Madhusūdana Sarasvatī, 20  
 Madhya, 97, 123  
 Madhyama, 89, 90  
 Mantrin, 110  
 Manu, 116  
 Manusmṛti, 116  
 Mammāṭa, 14  
 Malina, 81  
 Malla, 116  
 Maṣṛṇa, 138  
 Maṣṛṇamiśra, 138  
 Mastakī, 80  
 Mahācārī, 120  
 Mahādevī, 111  
 Mahānāṭaka or Hanumannāṭaka, 24, 29, 109, 151  
 Mahābhārata, 6, 29, 69, 102, 151  
 Mahābhāṣya, 8, 12, 105, 116  
 Mahārāja, 132  
 Mahārāṣṭrī, 128  
 Mahāvīracarita or Viracarita, 150  
 Mahāvratastoma (rite), 5  
 Māgadhi, 110, 128, 129  
 Mātrkā, 99  
 Mānasāraśilpaśāstra, 26, 32  
 Mānuṣī, 153  
 Māyecāpūta, 166  
 Mārkaṇḍeya Purāṇa, 6  
 Mārga, 88, 137  
 Mārgasārīta, 119  
 Mārdaṅgika, 93  
 Māltimādhava, 69, 102, 105, 109, 111, 146, 150  
 Mālavikāgnimitra, 21, 22, 25, 63, 66, 92, 100, 112, 115, 136, 137, 149

- Mālyakṛt, 108  
 Mukuṭa, 77, 80, 107  
 Mukuṭakara, 107  
 Mukṭājāla, 78  
 Mukṭāvalī, 77, 78  
 Mudrā, 95  
 Mudrārākṣasa, 65, 68, 102, 112, 171  
 Muṇḍāsana, 75  
 Muraja, 94, 121  
 Mūrccchanā, 91  
 Mṛccakaṭika, 9, 25, 37, 41, 45, 48, 56, 59, 66, 70, 72, 74, 86, 92, 101, 102, 109, 111, 116, 117, 127, 129, 130, 146  
 Mṛdaṅga, 7, 93  
 Mekhalā, 78  
 Meghadūta, 53, 85  
 Menā Gurjarī, 169, 170  
 Mocaka, 77  
 Yajurveda, 3, 5  
 Yajñavit, 114  
 Yantra, 45, 72  
 Yabanikā, 60  
 Yamanikā, 61, 62, 63, 64, 179  
 Yava, 32  
 Yavanikā, 55, 56, 61, 62, 63, 64, 179  
 Yājñavalkya, 116  
 Yātrā, 22, 24, 26, 29, 160, 161, 183  
 Yātrāvālas, 160, 164  
 Yūka, 32  
 Rakta, 82, 84  
 Raghuvamśa, 85  
 Raṅgadvāra, 120  
 Raṅgapīṭha, 34, 37, 46, 47, 48, 49, 50, 52, 55, 56, 57, 58, 61, 68, 93, 179  
 Raṅgabhūmi, 33  
 Raṅgamaṇḍala, 33, 48, 50  
 Raṅgamaṇḍapa, 49  
 Raṅgaśīrṣa, 33, 34, 38, 46, 47, 52, 55, 56, 57, 61, 68, 93, 126, 179, 180  
 Raja, 32  
 Rajaka, 108  
 Rañjita, 65  
 Ratnajāla, 78  
 Ratnamālikā, 78  
 Ratnāvalī (Jewel necklace), 78  
 Ratnāvalī, ( Nāṭikā ), 22, 23, 37, 48, 56, 66, 68, 70, 79, 87, 92, 100, 101, 102, 105, 109, 111, 112, 117, 135, 146, 149, 164  
 Raśanā, 78  
 Rasa, 3, 8, 14, 15, 16, 17, 18, 19, 20, 21, 84, 94, 103, 130, 136, 137, 139, 151, 152, 156, 176, 178, 179, 181, 182  
 Rasātmaka, 140  
 Rasārṇavasudhākara, 13, 123  
 Rasiko Nāṭaḥ, 8  
 Rasodbhāvana, 134  
 Rāga, 90, 91, 92  
 Rāgavibodha, 88, 89, 91  
 Rāghavabhaṭṭa, 98, 123  
 Rājan, 114, 133  
 Rājaśekhara, 133, 150  
 Rājaputras, 128  
 Rājamaṇḍala, 7  
 Rājasevaka, 114  
 Rāmacandra, 20  
 Rāmadāsa, 160  
 Rāmarājyaviyoga, 166

- Rāṃallā, 162, 170, 174, 183  
 Rāmāyaṇa, 5, 6, 29, 69, 115, 162, 183  
 Rāsa, 172, 174  
 Rāsaka, 145  
 Rāṣadhāris, 162  
 Rāsamaṇḍalīs, 170  
 Rāsalīla, 171, 183  
 Rukmiṇīharaṇa, 69, 146  
 Rucika, 77  
 Rūḍhiśabda, 133  
 Rūpa, 13  
 Rūpaka, 4, 6, 13, 139, 140, 147  
 Rūpakaṣaṭkam, 146  
 Rūpājīva, 116  
 Rūpānusāriṇī, 104, 105, 181  
 Recakas, 99, 138  
 Romaśa, 85, 86  
 Rohiṇi, 33, 125  
 Raudra, 20, 84, 113, 152  
 Laya, 97, 137  
 Laṭita, 161, 183  
 Lāñchita, 65  
 Lāśya, 4, 100, 143  
 Lāsikā, 101  
 Likṣā, 32  
 Lokacarita, 137  
 Lokadharmī, 15  
 Laukika, 20  
 Vaktrapāṇi, 119  
 Vajra, 76  
 Vaṭikā, 77  
 Vatsa, 132  
 Vayasya, 110, 133  
 Varjura, 78  
 Varṇa (colour), 83  
 Varṇa (melodic movement), 22 01  
 Vartalaṭika, 79  
 Vardhamāna, 120  
 Varṣadhara, 111  
 Valaya, 77, 78  
 Vanśa, 94  
 Vanśikas, 93  
 Vanmayī, 153  
 Vacika, 15, 72  
 Vācikaḥhinaya, 102  
 Vājasneyī Samhita, 5, 63  
 Vadi, 89, 90, 91  
 Vadya, 88, 119, 138  
 Vātāyana, 46  
 Vatsyāyana, 7, 109  
 Vānaukaśi, 128  
 Vāyava, 50  
 Vārtikakāra, 51  
 Vikramāditya, 172  
 Vikramorvaśīya, 23, 58, 102, 146, 149  
 Vikṛta, 141, 143  
 Vikṛṣṭa, 30, 31, 35, 46, 47, 49, 51, 52, 178  
 Vicitra, 81, 85, 86  
 Viṭa, 7, 101, 109, 110, 143, 146  
 Vitata, 81  
 Vīdūṣaka, 7, 10, 56, 67, 85, 87, 92, 108, 110, 120, 128, 133, 144, 146  
 Viddhaśālabhañjika, 65, 150  
 Vinayikā, 146  
 Vipralambha, 79, 130  
 Vibhāṣas, 128, 129  
 Viralanepathya, 100  
 Virūpa, 104, 181  
 Vilāmbita, 103  
 Vilāsikā, 146  
 Vivadi, 90

Viṣkambha or Viṣkambhaka, 131, 140, 144	Śaṅkuka, 17, 34, 50, 51
Viśakhadatta, 111	Śaṅkha, 94
Viśliṣṭa, 131	Śataghñī, 75
Viṣṇusmṛti, 116	Śabala, 76
Viṣṇudharmottara, 30, 64, 65, 82, 83, 175	Śabdavit, 114
Viśvanātha, 127, 128	Śara, 76
Viṇā, 7, 94	Śaṅkakalāpī, 78
Viṇā-ghoṣavatī, 76	Śākārī, 128, 129
Vīthī, 103, 106, 144	Śābarī, 128, 129
Vīthyaṅga, 103	Śāriputraprakaraṇa, 8, 148
Vīra, 84, 152	Śāinī, 153, 154
Viratanaya, 166	Śārṅgadeva, 89, 91
Vṛtta, 30	Śikhaṇḍa, 79
Vṛtti, 16, 122, 140, 141, 146	Śikhā, 79, 85
Vṛddha, 111	Śikhājāla, 78
Vedika, 45, 46	Śikhāpāśa, 78, 84
Veedhi Bhagavatam, 163	Śikhāpuṭa, 79
Veṇī, 84	Śilpaka, 146
Veṇīsamhāra, 102, 146, 153	Śilparatna, 25, 30, 65
Veṇu, 7	Śilāveśma, 53
Veśyā, 114	Śivāji, 164
Veṣakara, 108	Śirṣajāla, 78
Veṣṭita, 73, 74, 81	Śuddha, 81, 85, 86, 131, 141, 143
Vaidūrya, 79	Śūdra, 115, 116
Vaiṇika, 93	Śūdrācāra, 115
Vaitālika vākyas, 29	Śūla, 75
Vaiśyas, 116	Śuskāvakṛṣṭa, 120
Vyañjanā, 18	Śṛṅgāra, 20, 79, 84, 105, 130, 151
Vyājima 73, 74	Śṛṅgāralajjā, 98
Vyāyāma, 96	Śailaguhākāra, 37, 53
Vyāyoga, 106, 142, 146	Śailūṣa, 5, 115
Vyāla, 45	Śaurasenī, 127, 128, 129
Vyālapaṅkti, 78	Śmaśru, 85
Śakārā, 110, 129, 130	Śyāma, 83, 84, 85, 86
Śakuntalā (a drama), 172, 173	Śravaṇa, 33, 125
Śakti, 75	Śrigadita, 145, 146
	Śrī Harṣa, 22, 111, 112, 117, 164

- Śrīmadbhāgavata Purāṇa, 6  
 Śrūtiś, 89, 90, 91, 102  
 Śreṣṭhīn, 128  
 Śveta, 84  
 Ṣaḍja, 89, 90, 91  
 Ṣaḍ-dārūka, 93  
 Saṅkrānti, 100  
 Saṅkīrṇa, 141, 143  
 Saṅgīta, 5, 88, 107  
 Saṅghāta, 142  
 Saṅghātya, 81  
 Saṅgītapārijāta, 88, 89, 90, 91  
 Saṅgīta-makaranda, 25, 88, 89,  
 90, 94  
 Saṅgītaratnākara, 25, 88, 89, 90,  
 91, 92, 114, 137  
 Saṅgītaśālā, 54, 115, 178  
 Saṅgītasamayāsāra, 89  
 Saṅghoṭanā 119  
 Saciva, 110, 132  
 Sañcārī, 91  
 Sañcārikā, 111  
 Sañjīva, 73, 86, 87  
 Sañjavana, 45  
 Saṭṭaka, 133, 144, 145  
 Sattva, 18  
 Sandhi, 131, 140  
 Sandhima, 73  
 Sābhāpati, 113, 114, 124  
 Sābhāṣad, 112  
 Samājas, 6  
 Samavakāra, 106, 141, 146  
 Samudramanthana, 146  
 Saḥṛdaya, 18, 182  
 Saṁlāpaka, 145  
 Saṁvāda sūktas, 5  
 Saṁvādī, 90  
 Saṁsad, 113  
 Saṁskāra, 18  
 Saṁhitās, 102  
 Sāgaranandin, 128  
 Sātvika, 15, 72, 140  
 Sātvatī, 16, 106  
 Sādhāraṇīkaraṇa, 19  
 Sādhāraṇī, 111  
 Sādhikṣepa, 154  
 Sādhukāra, 153  
 Sādho, 132  
 Sāmaveda, 3, 5  
 Sādhāraṇāstrī, 111  
 Sārvavārṇika, 3  
 Sālabhañjikā, 45  
 Sāhityadarpaṇa 13, 119, 121,  
 123, 127, 128, 131, 139, 143,  
 144  
 Siddhi, 153, 154, 155, 182  
 Siddhilekhakas, 155, 156, 182  
 Siddhāntakaumudī, 621, 36, 137  
 Sita, 82, 84  
 Sītā Svayamvara, 165  
 Sīmanta 85  
 Sukumāra, 105, 106  
 Subhaṭa, 151  
 Subhadra, 166  
 Subhadrā Dhanañjaya, 151  
 Suṣira, 92, 180  
 Sūta, 5  
 Sūtra, 77  
 Sūtraka, 77, 78  
 Sūtradhāra, 6, 11, 21, 22, 23,  
 71, 105, 106, 107, 114, 116,  
 120, 121, 123, 124, 145, 150  
 Senāpati, 110  
 Stambha, 46  
 Sthāyī, 91  
 Sthāpaka, 69, 107, 123

Sthita, 97	Harita, 83
Snātaka, 111	Harsaka, 77
Smita, 153	Harivamśa, 6, 69
Svagata, 132	Harṣacarita, 117
Svara, 88, 89, 90, 91	Hasta, 30, 31, 32, 51
Svarita, 90	Hastidanti cuḍiyān, 78
Svapnavāsavadattā, 64, 68, 79, 86	Halāyudha, 56
Svāṅga, 49	Halliśa, 146
Svāminī, 133	Halliṣaka, 101
Svīyā, 111	Hastavī, 77
Svecchitika, 78	Hāra, 77, 78
Hañje, 133	Hāsyā, 84, 145, 152
Harikathā, 161, 163	Hāsyacūḍāmaṇi, 146
Hariścandra (a play) 164, 169	Hemasūtra, 77
	Homoeopathy, 165

### B. Theatrical Companies, Artists and Authors

Acharya, P. K., 49	Bombay Gujarati company, 169
Aishvarya Narayan Singh, 171	Bombay Theatre, 167
Akadami of Fine Arts, 184	Bohtlingk, 62
Alfred company, 168	Chaturvedi, Sitaram, 172
Altekar company, 167	Chinese Theatre, 61
Andhra open-air stage, 163	Classical Theatre, 182
Apte, V. S., 62, 136	Coomaraswamy, A. K., 46, 60, 61
Aryoddharaka company, 166	Dahyabhai, 169
Athenian stage, 93	Dayashanker, 169
Atre, 166	De, S. K., 56, 62, 63
Babu Jayaram Bysack, 164	Deshi company, 169
Badri Nath Bhatta, 171	Desinga Raja, 160
Bāla Vinoda Nāṭakasabhā, 162	Dewal, 166
Balliwala, 168	English Theatre, 164
Balliwala company, 168	Folk dances, 98
Bālāmaṇi company, 162	Folk Theatre, 49, 164
Bengal Theatre, 165, 183	French opera, 171
Bhave company, 166	Gaṅgānātha Jhā, 19
Bhavāi maṇḍali, 169	Gadkari, Ram Ganesh, 166
Bijon Bhattacharya, 165	Ghosh, Girish Chandra, 164
Bloch, 9, 60	



- Ghosh, Monomohan, 47  
 Gopichand, 162, 183  
 Great National Theatre, 165  
 Greek Theatre, 9, 70  
 Greek theory, 12  
 Grosset, 48, 61  
 Gujarati Theatre, 167, 169, 170, 183  
 Guhathakurta, P. 160  
 Harish Chandrā, Bhāratendu, 170, 171, 183  
 Haraprasāda Śāstrī, 10  
 Ḥakikat, 162, 183  
 Harvest dance dramas, 175  
 Haas, C. O., 142  
 Hindi Theatre, 170, 172, 183  
 Hindustani Theatre, 183  
 Hirabai Barodkar, 166  
 Hirabai Barodkar Nāṭakamaṇḍalī, 167  
 Indian Film company, 184  
 Itsing, 149  
 Jai Shankar Prasad, 171, 175  
 Jagannath Prasad, 171  
 Jagannath Shankerseth, 167  
 Jogīmārā cave, 60  
 Kalahakandala, 22  
 Kalākṣetra, 164  
 Kalidasa Elphinstone Society of Bombay, 168  
 Kanaiyā and Company, 162  
 Kanarese Theatre, 163  
 Keith, A. B., 10, 63  
 Kirloskar, 166  
 Kirloskar Nāṭakamaṇḍalī, 166  
 Kolhatkar, 166  
 Krishnamacharya, 162  
 Lawis Theatre, 165  
 Levi, Sylvan, 64  
 Luders, 11  
 Maithili Sharan Gupta, 172  
 Madan company, 168  
 Madras Theatre, 162, 163, 183  
 Maharashtra company, 166  
 Maharashtra Nāṭakamaṇḍalī, 166  
 Marathi Theatre, 165, 167, 183  
 Manoranjan Bhattacharya, 165  
 Madhav Shukla, 171  
 Mankad, 56  
 Macdonell, 54  
 Maypole theory, 10, 12  
 Medieval stage, 183  
 Mehta, C. C., 170  
 Morbi company, 169  
 Monier Williams, 73  
 Mukerjee, S. C., 152  
 Munshi, K. M., 170  
 Museum Theatre, 162  
 Nāṭa Maṇḍala, 169  
 Nāṭarāja temple, 93  
 National Theatre, 159, 174, 175, 176, 184  
 National Theatre of Bengal, 164  
 Open-air Theatre, 52, 53, 179  
 Opera House, 172  
 Original Theatrical Company, 168  
 Palace Theatre, 25, 26, 27, 178  
 Parsi Theatre, 167, 168, 169, 171, 172, 183  
 Pestanji Framji, 168  
 Pischel, 11  
 Pisharoti, K. R., 93  
 Pillars, Positions of, 51

- Prithvi Theatre, 172, 173, 174  
 Prithviraj, 172, 173, 174, 184  
 Prem Chand, 172  
 Public Theatre, 53, 164, 178  
 Puppet Show, 11, 163  
 Puppet Play, 12  
 Puran, 162, 183  
 Ram Gopal, 181  
 Ray, Dvijendra Lal, 165  
 Ranachodbhai, 169  
 Rangdekar, 166  
 Rectangular (theatre), 30, 31, 33  
 Ridgeway, William, 10, 161  
 Roth, 62  
 Rukmini Devi, 164, 184  
 Sahakāri Manoranjana  
     Maṇḍala, 166  
 Sanglikar company, 167  
 Sarasa Vinodini Sabhā, 162  
 Shadow Play, 11, 12, 23, 151, 163  
 Shakespeare, 133, 166  
 Shambhumitra, 165  
 Shahunagaravasi company,  
     The, 166  
 Sitābeṅgā cave, 9, 60  
 Square (Theatre), 30  
 Sugun Vilās Sabhā, 162  
 Tagore, Ravindranath, 165, 175  
 Tagore, S. M., 59, 68  
 Tamil Theatre, 159, 163, 183  
 Talkies, 160, 184  
 Telugu Theatre, 163  
 Temple Theatre, 26, 178  
 Teruvukk-kootu, 163  
 Tolu Bommālāṭalu, 163  
 Triangular ( Theatre ), 30  
 Uday Shankar, 94, 163, 164, 181  
 Varerkar, 166  
 Vaghaji Oza, 169  
 Vernacular Theatres, 183  
 Vegetation Spirit theory, 10,  
     11, 12  
 Vishṇudas Bhave, 165  
 Wajid Ali Shah, 170, 183  
 Wilson, H. H., 10, 24, 60  
 Windisch, E., 8, 9, 63  
 Winternitz, 148  
 Yajnik, R. K., 162

## CORRIGENDUM

- Page 5, line 29, read cheered for echeered  
Page 5, line 36, read Kāṭhakam for Kāṭhakarṇ  
Page 10, line 5, read attached for attaeched  
Page 20, lines 1 and 8, read *bībhatsa* for *vībhatsa*  
Page 22, line 18, read Puruṣottama for Puruśottama  
Page 22, line 27, read Śrī for Sri  
Page 25, line 30, read the for thc  
Page 63, line 17, read theatre.<sup>2</sup> for theatre  
Page 77, line 3, read C for B  
Page 77, line 27, read *Kuṇḍala* for *Kṇḍala*  
Page 78, line 4, read wore for were  
Page 80, line 6, read birth for brith  
Page 84, line 24, read *bībhatsa* for *vībhatsa*  
Page 92, line 26, read *tatam* for *tatam*  
Page 92, line 27, read category for cetegory  
Page 92, line 28, read *avanaddham* for *avanaddham*  
and *ghanam* for *ghanam*  
Page 111, line 3, read *svīyā* for *suīyā*  
Page 113, line 17, read *bībhatsa* for *vībhatsa*  
Page 128, line 14, read *cāṇḍālī* for *cāṇḍālī*  
Page 143, line 24, read *ākāśabhāṣita* for *ākāśabhaṣita*  
Page 146, line 25, read *Rūpakaṣaṭkam* for *Rūpakaṣaṭkam*  
Page 153, line 32, read *Kaṣṭam* for *Kaṣṭam*  
Page 155, line 7, read ancient for ancicnt  
Page 184, line 21, read depend for depcnd



## OPINIONS

I have read with much pleasure and admiration almost all of the thesis on 'Presentation of Sanskrit plays on the Stage,' which won for Dr. Chandra Bhan Gupta his Doctorate from the Banaras Hindu University. He has broken new ground in it. I am not aware of any other work in English which has dealt with the subject. How such presentation originated, what was its object; what the occasions; kinds of theatres; construction of them, decorations, green room, orchestra, curtains, auditorium etc; paraphernalia, how to represent carriages, horses, elephants, reptiles; how to colour hair, beard etc; dancing; dialogue, actors and actresses; spectators and judges; social position of actors and actresses; religious ceremonies connected with presentation of plays; dialects used; portrayal of sentiments and emotions; injunctions and prohibitions; different types of plays; and finally evolution of drama and how far can the ancient Indian stage be successful in modern times—all these multifarious themes are dealt with in the thesis in a lucid, interesting and informing manner.

A number of useful diagrammatic illustrations have also been put in. I would be glad to see this valuable work in print and having a wide circulation amongst literate generally and Indologists specially.

31—1—1952.

**Bhagavan Das**

I have been much delighted to see the thesis of Dr. Chandra Bhan Gupta on the 'Presentation of Sanskrit plays.' It is a scholarly work based on a critical and exhaustive study of the Nāṭyaśāstra of Bharata. It also takes note of the evidence about the Indian Theatre from the available dramas and dramatic literature in Sanskrit. It discusses in a lucid manner not only the construction of the stage but

also the scenic representation, accessory arts like music and dancing helpful in the presentation of plays, the functions and classes of the actors and professor dramatists, as well as the stage conventions. The author has also thrown light on the origin of Indian drama and focussed the Indian evidence on this point which shows in a satisfactory manner that the Indian theatre originated and developed in accordance with Indian needs, conditions and social and religious beliefs. I consider this a meritorious piece of research work.

26—12—1951.

**V. S. Agrawala**

The author in his thesis on the 'Presentation of Sanskrit Plays' has undoubtedly treated his subject in a very exhaustive manner. It has really given me a great pleasure to find that the bud of preliminary work of this subject which I had seen and admired eight years ago, has since blossomed forth in the shape of this full-fledged thesis, quite deservedly approved for the doctorate. I have highest admiration for the author's patient, industrious and thorough-going method of work.

16—7—1952.

**Vishva Bandhu**

This Thesis presented for the Degree of Doctor of Letters by Chandra Bhan Gupta contains much useful information. The writer has gone extensively into the original sources and brought together extremely valuable material which till now, lay scattered in the various works to which references have been made in the body of the paper. This must have been a difficult task. The greatest treatise on Indian Dramaturgy, Bharata's Nāṭyaśāstra, has itself not yet been properly collated and edited. The commentary, Abhinavabhāratī of Abhinavagupta, a knowledge of which is so essential to an understanding of the Nāṭyaśāstra, is available only in one edition. The pre-Bharata literature on the subject is scattered through the Vedas, the Purāṇas, the Buddhist Canons etc. The Post-Bharata contributions have been numerous and often overlap each other. All this difficulty has been sensibly

tackled and the essential information presented in one connected sequence. The author has also dealt with various western theories as to the debt the Sanskrit drama owes to the Western stage and has shown how the debt is only an imaginary one and that the two schools are independent of each other and have had completely independent lines of development.

The Hindu Śāstras went into great detail over the construction of the theatre; it is of much interest to see that their ideas are still valid with regard to many particulars. The diagrams, which the author has given in this connection, are of particular interest.

Of similar importance is the chapter on the paraphernalia of the stage. How rich the ancient stage was in matters of decor and make-up. The wealth of detail given in connection with Āhāryābhinaya is of importance not only to the Producer of today who can find therein names of materials of make-up which will suit Indian conditions but also to those interested in Jewellery and new types of ornaments. These are described in great detail by Bharata and his chapter on Āhāryābhinaya is one of the most fascinating parts of the Nāṭyaśāstra.

Dr. Gupta has done a great service to his country and to the world of scholars in collecting and disseminating all this knowledge. The critical parts of his study are also interesting because he brings to bear an original intelligence on the problems of the stage both ancient and modern.

5—2—1952.

**Rukmini Devi Arundale**

डा० श्री चन्द्रभानुगुप्तलिखितस्य भारतीयनाट्यकलाविषयकस्य आङ्गलभाषामयस्य महतो निबन्धस्य कतिचिदंशा ग्रन्थकर्त्रैव मह्यं भाविताः । तत्र निहितानि नाट्यशालाचित्राणि प्रदर्शितानि । आङ्गलभाषां विशेषतोऽजानन्नपि अहं स्पष्टमेतद्वक्तुं शक्नोमि यन्निबन्धोऽयं महता परिश्रमेण लिखितः । अन्वेषण पद्धतिश्चात्र गौरवास्पदी-भूता मननार्हा च । आशासे, विद्वांस एतत् सफलयेयुरिति ।

१६-११-१९५२

गिरिधरशर्मा चतुर्वेदः

I have gone through some portions of 'The Indian Theatre' of Dr. Chandra Bhan Gupta and am delighted to express my opinion about the intrinsic merits of the work. The learned author has laboured hard in collecting his materials from a wide range and from a variety of sources and the result presented here is at once convincing and scholarly, interesting and informative. The work is undoubtedly a mine of information, accurate as well as useful, about everything connected with the ancient theatre of the Hindus and is bound to be a source of inspiration to the general readers as well as to the scholars interested in the history of the ancient Hindu stage and in the development of the modern National Theatre of India.

6—1—1954.

**Baldeva Upadhyaya**

One of the most authentic and scholarly treatment of the theatrical aspect of the Indian drama has recently appeared under the caption. "The Indian Theatre." The author of this great work is Dr. Chandra Bhan Gupta, M. A., D. Litt. who has taken immense pains and has evinced keen insight in dealing with the various aspects of the problem in hand. Very few scholars have gone beyond a cursory note on the three types of the stage cum-auditorium mentioned by Bharata in his Nāṭyaśāstra though it is evident that those types were never adopted in use as far as historical records bear evidence.

Subsequent stage-artists of different ages started their own conventions, production techniques, stage-settings and other crafts related to the presentation of the plays. Dr. Gupta has very ably surveyed the whole field of Indian-dramatic presentation and has discussed in details the development of the Indian Theatre down to the present day.

I am confident that this work shall be welcomed by all lovers of Indian culture, drama and literature alike, for it will serve as a faithful guide to those who are interested in the rejuvenation of Indian drama. I whole-heartedly congratulate the author for his singular achievement.

23—5—1953,

**Sitaram Chaturvedi.**









